Uplands Initiative

Gwaunceste Archaeological Survey Site Gazetteer



Report by: Trysor

For: The Royal Commission on Ancient and Historical Monuments (Wales)

March 2007



Uplands Initiative

Gwaunceste Archaeological Survey Site Gazetteer

By

Jenny Hall MIFA & Paul Sambrook Trysor

Trysor Project No. 2007/87

For: The Royal Commission on Ancient and Historical Monuments (Wales)

Royal Commission Ref. No. RCS 1/2/56

March 2007



Introduction

This is the second part of a two part report.

Part One includes a synthesis of the results of fieldwork carried out by Trysor in the Gwaunceste study area during the summer and autumn of 2006, and winter of 2006-7.

This section includes location maps and the Site Gazetteer based on the findings of that fieldwork.


The layout of the report is self-explanatory; the site location maps (10 figures in total) precede the printout of the Site Gazetteer on page 13


The location maps use the 2nd Edition Ordnance Survey maps of 1905 as background data as supplied by the RCAHMW for the use of the project

The Historical Map Data is © and database right Crown copyright and Landmark Information Group Ltd. All rights reserved. The archaeological data superimposed on the map is Crown copyright: RCAHMW, 2004.


The Site Gazetteer itself is a copy of the information provided in the project database created for the project and submitted to the RCAHMW in digital format

Jenny Hall & Paul Sambrook Trysor







The Historical Map Data is © and database right Crown copyright and Landmark Information Group Ltd. All rights reserved. The archaeological data superimposed on the map is Crown copyright: RCAHMW, 2004.




The Historical Map Data is © and database right Crown copyright and Landmark Information Group Ltd. All rights reserved. The archaeological data superimposed on the map is Crown copyright: RCAHMW, 2004.




The Historical Map Data is © and database right Crown copyright and Landmark Information Group Ltd. All rights reserved. The archaeological data superimposed on the map is Crown copyright: RCAHMW, 2004.



The Historical Map Data is © and database right Crown copyright and Landmark Information Group Ltd. All rights reserved. The archaeological data superimposed on the map is Crown copyright: RCAHMW, 2004.




The Historical Map Data is © and database right Crown copyright and Landmark Information Group Ltd. All rights reserved. The archaeological data superimposed on the map is Crown copyright: RCAHMW, 2004.




The Historical Map Data is © and database right Crown copyright and Landmark Information Group Ltd. All rights reserved. The archaeological data superimposed on the map is Crown copyright: RCAHMW, 2004.

Map 7: Colva Scale 1:10000




The Historical Map Data is © and database right Crown copyright and Landmark Information Group Ltd. All rights reserved. The archaeological data superimposed on the map is Crown copyright: RCAHMW, 2004.



The Historical Map Data is © and database right Crown copyright and Landmark Information Group Ltd. All rights reserved. The archaeological data superimposed on the map is Crown copyright: RCAHMW, 2004.

Map 9: Cefn Hir Scale 1:10000



The Historical Map Data is © and database right Crown copyright and Landmark Information Group Ltd. All rights reserved. The archaeological data superimposed on the map is Crown copyright: RCAHMW, 2004.

Site Gazetteer

GIANTS GRAVE, BARROW ROUND BARROW

NGR: SO14025437 Grid reference taken at centre of site Altitude: 446

Period: Bronze Age Broadclass: Religious, Ritual and Funerary

Form: Earthwork **Condition:** B

Site Status: RD218

Description: 1. A mound, set beside a track in a col, 16m in diameter and 1.3m high.

(source Os495card; SO15SW3)

J.Wiles 23.08.02

2. Remains of a large burial cairn, probably dating to the Bronze Age, situated in moorland on the saddle between Little Hill to the south and Llyn-y-waun to the north. The heather covered cairn is circular on plan and measures about 16.5m in diameter and up to 1.8m in height.

Source: Cadw scheduling description 07/10/2004/RCAHMW/FF

3. An earthen round barrow, 16m in diameter and 1.3m high, situated in a saddle between Little Hill and Llyn y Waun. The top of the barrow is flat but has been disturbed by animal activity and possibly by humans as there is a large hollow to the northwest of the top of the mound. A smaller mound, NPRN 289361, approximately 20m to the north, has formerly been interpreted as natural, a possible round barrow or a possible gibbet mound. When the barrow was recorded in June 2006 it was covered in heather. J.J.Hall, Trysor, 10 November 2006

SMR PRN: CPAT 338

Relationships: Photographs:

GC2006-004 18/06/2006 Barrow on right hand side of

photo, looking east

GC2006-005 18/06/2006 Barrow, looking west

NPRN: 32528

GELLIDYWYLL FARM, SPRING SPRING

NGR: SO1442153052 Grid reference taken at centre of site Altitude: 410

Period: Modern Broadclass: Water Supply and Drainage

Form: Other Structure **Condition:** A

Site Status:

Description: 1. Above farm of Gelli Dywyll, spring flowing from man-made hollow; overflow covered by

small flat stone slabs. Anon

2. An artificial hollow with a spring, below which water is culverted via a stone chamber. The owner of Gelli Dywyll says that this spring is the water supply for the farm and flows throughout the year. He remembered the feature being dug by hand. When recorded in June 2006, the feature was still in use and had recently had some work done on it. J.J.Hall, Trysor,

10 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-006 18/06/2006 Covered culvert and hollow

above, looking northwest

LLANHAYLOW, LINEAR EARTHWORK TRACKWAY

NGR: SO205537 Grid reference taken at point along linear site Altitude: 390

Period: Post Medieval? Broadclass: Transport

Form: Earthwork Condition: C

Site Status:

Description: 1. High above West side of stream. Fades at approach to boundary of Llanhaylow land. No

apparent connection with any mill.

2. A linear earthwork feature recorded from aerial photographs and originally interpreted by RCAHMW as a leat. When the feature was visited on the ground it was seen to run diagonally

down a steep slope and was a trackway. J.J.Hall, Trysor, 26 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289000

LITTLE HILL, QUARRY I QUARRY

NGR: SO1384652642 Grid reference taken at centre of site Altitude: 360

Period: Post Medieval Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A small quarry annotated as "Old Quarry" on 1st edition Ordnance Survey map of 1891 but no

longer depicted on modern Ordnance Survey mapping. However, the quarry can still be seen on the ground, and measures 17m northwest-southeast by 10m and is up to 2m deep. When visited during Uplands Survey fieldwork in June 2006, the feature was covered with turf and

bracken. J.J. Hall, Trysor, 17 July 2006

SMR PRN:

Relationships: Photographs:

GC2006-001 18/06/2006 Quarry, looking south

LITTLE HILL. ENCLOSURE I **ENCLOSURE**

NGR: SO1382452864 Grid reference taken at centre of site Altitude: 360

Broadclass: Monument <By Form> Period: Post Medieval

Form: Earthwork **Condition:**

Site Status:

Description: A rectilinear enclosure, c. 142m north-south by 55m east-west shown on the 1st edition

Ordnance Survey map of 1891and all later editions. It is detached from the enclosed fields immediately to the west by a trackway, and is a lone enclosure within the common boundary. When visited during fieldwork in June 2006, the enclosure was defined by a bank 2m wide and 0.5m wide. In the southwest corner, close to a former house site, NPRN 289014, the outside edge of the bank was defined by upright slab stones. The northwest corner was defined by a well built stone wall which provided revetting to the trackway to the west. The enclosure has some internal divisions but density of bracken cover when the site was visited during Uplands Survey fieldwork in June 2006 made these hard to define. J.J. Hall, Trysor, 17 July 2006

SMR PRN:

Relationships: Photographs:

Associated with 289014 GC2006-002 18/06/2006 Detail of wall, at northwest

Associated with 289018 corner, looking south

Consists of 289019 GC2006-003 18/06/2006 Enclosure overgrown with

bracken, looking southeast

NPRN: 289002

LITTLE HILL, QUARRY II **QUARRY**

NGR: SO1412552487 Grid reference taken at centre of site **Altitude:** 340

Period: Post Medieval **Broadclass:** Industrial

Form: Earthwork **Condition:**

Site Status:

Description: A small quarry shown on the 1st edition Ordnance Survey map of 1891 alongside a trackway

> and annotated as "Quarry". By the time of the 2nd edition of 1905 it was annotated as "Old Quarry". When visited during fieldwork in June 2006, the quarry was overgrown with grass and bracken. It measured 15m northeast-southwest by 10m and was up to 2m deep. J.J. Hall,

Trysor, 17 July 2006

SMR PRN: CPAT 22498

Relationships: Photographs:

NPRN: 289003

UPPER YSGAWEN, QUARRY IV **QUARRY**

SO1356153251 Grid reference taken at centre of site NGR: Altitude: 330

Period: Post Medieval **Broadclass:** Industrial Form: **Documents Condition:**

Site Status:

Description: A small quarry shown on the 1st edition Ordnance Survey map of 1891 in the northwest corner

of a small field system, and annotated as "Old Quarry". The quarry is shown all later editions

of the Ordnance Survey maps from 1905 onwards. J.J. Hall, Trysor, 17 July 2006

SMR PRN: CPAT 22490

UPPER YSGAWEN, QUARRY I QUARRY

NGR: SO1369253134 Grid reference taken at centre of site Altitude: 360

Period: Post Medieval Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: Small quarry shown on the 1st edition Ordnance Survey map of 1891 and annotated as "Old

Quarry". It is not shown on later edition Ordnance Survey maps from 1905 onwards. The feature was found during fieldwork in June 2006 in bracken, and measured 16m

northwest-southeast x 10m and was 4-5m deep. J.J. Hall, Trysor, 15 June 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289005

UPPER YSGAWEN, FARMSTEAD FARMSTEAD?

NGR: SO1361453173 Grid reference taken at centre of site Altitude: 335

Period: Post Medieval? Broadclass: Agriculture and Subsistence

Form: Complex Condition: D

Site Status:

Description: A small farmstead shown on the 1st edition Ordnance Survey map of 1891. At this time it

consists of four fields within a rectilinear enclosure with a trackway entering the complex at the south end, adjacent to which one or more buildings are shown. The same complex is shown on the 2nd edition Ordnance Survey map of 1905 but only the outer enclosure is depicted on

modern mapping. J.J. Hall, Trysor, 15 June 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289007

TY'N-Y-COED, WELL WELL

NGR: SO1343554294 Grid reference taken at centre of site Altitude: 335

Period: Post Medieval **Broadclass:** Water Supply and Drainage

Form: Documents Condition: U

Site Status:

Description: A well shown on the 1st edition Ordnance Survey map of 1891 and all subsequent editions.

J.J. Hall, Trysor, 17 July 2006

SMR PRN:

LITTLE HILL, SHEEP FOLD II SHEEP FOLD

NGR: SO1780453281 Grid reference taken at centre of site Altitude: 340

Period: Post Medieval Broadclass: Agriculture and Subsistence

Form: Documents Condition: D

Site Status:

Description: Small sheepfold shown on 1st edition Ordnance Survey map of 1891 at the edge of the

common. Not shown on later editions. When the site was visited in November 2006 as part of

Uplands Survey, no trace of the fold could be seen. J.J. Hall, Trysor, 6 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289009

LITTLE HILL, SHEEP FOLD I SHEEP FOLD?

NGR: SO1404252443 Grid reference taken at centre of site Altitude: 337

Period: Post Medieval? **Broadclass:** Agriculture and Subsistence

Form: Earthwork **Condition:** C

Site Status:

Description: A rectangular enclosure, 10m west southwest-north northeast by 5m, defined by broad earth

banks on three sides. The fourth side was open to the south but may have originally been enclosed by the boundary of the common, which at this point is a well built stone wall. The banks of the enclosure are up to 3m wide and 1m high and the feature is slightly terraced in to the slope on its north northwest side. The feature is associated with a larger enclosure to its east with a terrace above it. The features stand at the edge of the common alongside a road/trackway. This enclosure was interpreted as a fold at an entrance onto the common. When visited during Uplands Survey fieldwork in June 2006, the feature was covered with turf

and bracken. J.J. Hall, Trysor, 17 July 2006

SMR PRN:

Relationships: Photographs:

Associated with 289010 GC2006-007 18/06/2006 Earthwork, looking southwest

NPRN: 289010

LITTLE HILL, ENCLOSURE II ENCLOSURE

NGR: SO1404852450 Grid reference taken at centre of site Altitude: 338

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A rectangular enclosure attached to the easternside of sheep fold NRPN 289009. This

enclosure is 14m east-west by 11m, defined by earth banks up to 3m wide and 1m high. The south side is open but may have been truncated by the east-west road/trackway. When the site was visited during Uplands Survey fieldwork in June 2006, the feature was covered in closely

cropped turf and bracken. J.J. Hall, Trysor, 17 July 2006

SMR PRN:

Relationships: Photographs:

Associated with 289009 GC2006-008 18/06/2006 Enclosure, looking southeast

LITTLE HILL, MOUND I MOUND

NGR: SO1401052464 Grid reference taken at centre of site Altitude: 344

Period: Unknown **Broadclass:** Monument <By Form>

Form: Earthwork Condition: U

Site Status:

Description: An irregular earth mound, with some stone content. It measured 4m east northeast-west

southwest by 3m and 0.5m high. When visited during Uplands Survey fieldwork in June 2006,

the mound was covered with turf and bracken. J.J. Hall, Trysor, 17 July 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289012

LITTLE HILL, CULTIVATION RIDGES II CULTIVATION RIDGE

NGR: SO1397252510 Grid reference taken at a central point within an extensive site Altitude: 350

Period: Unknown **Broadclass:** Agriculture and Subsistence

Form: Earthwork **Condition:** C

Site Status:

Description: An area of ridge and furrow on the Little Hill common, adjacent to the common boundary. The

ridges were approximately 1m wide with 1m furrows. When visited during Uplands Survey fieldwork in June 2006, the area was covered by close cropped turf. J.J. Hall, Trysor, 18 July

2006

SMR PRN:

Relationships: Photographs:

GC2006-009 18/06/2006 Ridge and furrow, looking north

NPRN: 289013

LITTLE HILL, QUARRY III QUARRY

NGR: SO1379452670 Grid reference taken at centre of site Altitude: 354

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork Condition: B

Site Status:

Description: A small quarry, approximately 12m square and 2m deep, with some rock exposed. Vegetation

cover, when the site was visited during Uplands Survey fieldwork in June 2006, was turf and

bracken. J.J. Hall, Trysor, 18 July 2006

SMR PRN:

Relationships: Photographs:

GC2006-010 18/06/2006 Quarry, looking west

LITTLE HILL, BUILDING I BUILDING

NGR: SO1380552815 Grid reference taken at centre of site Altitude: 360

Period: Post Medieval? Broadclass: Domestic

Form: Ruin Condition: D

Site Status:

Description: The remains of a rectangular building recorded in the southwest corner of enclosure NPRN

289001 during Uplands Survey fieldwork in June 2006. The building measured 5.75m north-south by 3.5m. Part of the eastern wall survived including the northeast corner, up to a height of 0.3m. The feature was under the cover of a large tree growing in the enclosure boundary, and ground vegetation cover was nettles and grass when visited in June 2006. J.J.

Hall, Trysor, 18 July 2006

SMR PRN:

Relationships: Photographs:

Associated with 289001 GC2006-011 18/06/2006 Remains of building, looking

south southwest

GC2006-012 18/06/2006 Remains of building, looking

north northeast

NPRN: 289015

LITTLE HILL, QUARRY IV QUARRY

NGR: SO1380752809 Grid reference taken at centre of site Altitude: 360

Period: Post Medieval Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A small, rectilinear quarry pit, 6m east-west by 3m and 1m deep. The quarry lies just outside

the south side of enclosure NPRN 289001, and may have been used to provide stone for building NPRN 289014. The vegetation cover was nettles and grass when visited in June

2006 during fieldwork for an Uplands Survey project. J.J. Hall, Trysor, 18 July 2006

SMR PRN:

Relationships: Photographs:

Associated with 289016 GC2006-013 18/06/2006 Quarry, looking east

NPRN: 289016

LITTLE HILL, MOUND II MOUND

NGR: SO1380552798 Grid reference taken at centre of site Altitude: 360

Period: Unknown Broadclass: Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A discrete earthen mound, 2m in diameter and 0.5m high. It is possibly spoil from quarry

NPRN 289015. When visited during Uplands Survey in June 2006 the feature was grass

covered. J.J. Hall, Trysor, 18 July 2006

SMR PRN:

Relationships: Photographs:

Associated with 289015 GC2006-014 18/06/2006 Mound, looking south

LITTLE HILL, QUARRY V QUARRY

NGR: SO1378752833 Grid reference taken at centre of site Altitude: 356

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A linear quarry below the trackway on the western side of enclosure NPRN 289001. The

quarry was over 40m north-south and approximately 4m wide. It was overgrown with bracken when visited during Uplands Survey fieldwork in June 2006. J.J. Hall, Trysor, 18 July 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289018

LITTLE HILL, PLATFORM I PLATFORM?

NGR: SO1380952856 Grid reference taken at centre of site Altitude: 360

Period: Unknown **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: A platform 20m east-west by 9m and cut to 1.5m deep into the slope at its eastern end. The

platform lies within the enclosure NPRN 289001 and was overgrown with bracken when

visited during Uplands Survey fieldwork in June 2006. J.J. Hall, Trysor, 18 July 2006

SMR PRN:

Relationships: Photographs:

Associated with 289001 GC2006-015 18/06/2006 Bracken covered platform,

looking west

NPRN: 289019

LITTLE HILL, BANK I BANK (EARTHWORK)

NGR: SO1381952864 Grid reference taken at point along linear site Altitude: 362

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: An earthwork bank creating an internal division within enclosure NPRN 289001. The bank

measured 15m north-south, 2m wide and up to 1m high. The bank may have extended further as a more denuded feature but dense bracken made it difficult to follow the feature any further

when visited in June 2006. J.J. Hall, Trysor, 18 July 2006

SMR PRN:

Relationships: Photographs:

Part of 289001

UPPER YSGAWEN, QUARRY II QUARRY

NGR: SO1363953079 Grid reference taken at centre of site Altitude: 341

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork Condition: B

Site Status:

Description: A small quarry, 15m north-south by 10m, just south of the enclosure at Upper Ysgawen,

NPRN 289005. When visited during Upland Survey fieldwork in June 2006, the vegetation

cover was bracken and grass. J.J. Hall, Trysor, 18 July 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289021

UPPER YSGAWEN, FARMHOUSE FARMHOUSE

NGR: SO1363253093 Grid reference taken at centre of site Altitude: 340

Period:Post Medieval?Broadclass:DomesticForm:RuinCondition:D

Site Status:

Description: The remains of a building, probably the farmhouse, at Upper Ysgawen. The building is shown

on the 1st edition Ordnance Survey map of 1891 but by the 2nd edition of 1905 it is shown as roofless. When visited during Upland Survey fieldwork in June 2006, the footprint of the building could still be distinguished. The building measured 14m north northwest-south south east by 6m. The walls were 0.6m wide and of laid shale. The southeast corner stood up to 0.50m high but the rest of the walls were reduced to ground level. The vegetation cover was

grass. J.J. Hall, Trysor, 18 July 2006

SMR PRN:

Relationships: Photographs:

GC2006-016 18/06/2006 Remains of building, looking

northeast

GC2006-017 18/06/2006 Remains of building, looking

north

NPRN: 289022

UPPER YSGAWEN, QUARRY III QUARRY

NGR: SO1372653101 Grid reference taken at centre of site Altitude: 371

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork Condition: B

Site Status:

Description: A small quarry, approximately 10m square with spoil tips adjacent. When visited during

Uplands Survey fieldwork, the quarry was overgrown with grass and bracken. J.J. Hall,

Trysor, 18 July 2006

SMR PRN:

LITTLE HILL, QUARRY VI QUARRY

NGR: SO1353253430 Grid reference taken at centre of site Altitude: 356

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: An area of quarrying 15m north-south by 13m on a steep west facing slope. One or more pits

had been worked but the area had been disturbed recently by scramble bikes, making it hard to

precisely define. J.J. Hall, Trysor, 18 July 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289024

TY'N-Y-COED, QUARRY I QUARRY

NGR: SO1351654365 Grid reference taken at centre of site Altitude: 372

Period: Post Medieval? **Broadclass:** Industrial

Form: Earthwork Condition: C

Site Status:

Description: Small scale quarrying in the form of a small hollow and some tips. When visited in June 2006

during Uplands Survey fieldwork the feature was covered with close cropped turf and bracken.

J.J. Hall, Trysor, 18 July 2006

SMR PRN: CPAT 36955

Relationships: Photographs:

NPRN: 289025

TY'N-Y-COED, QUARRY III QUARRY

NGR: SO1349854403 Grid reference taken at centre of site Altitude: 373

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: A linear cut, probably a quarry, alongside a trackway that runs to the north of it. There is a

bank 0.5m high and 1m wide on the south side of the cut. It is likely that it was a quarry for the

trackway material. J.J. Hall, Trysor, 18 July 2006

SMR PRN:

TY'N-Y-COED, TRACKWAY TRACKWAY

NGR: SO1357554443 Grid reference taken at point along linear site Altitude: 390

Period: Post Medieval? **Broadclass:** Transport

Form: Earthwork **Condition:** V

Site Status:

Description: A roughly east-west trackway or hollowway with a pronounced bank on the southern downhill

isde. The trackway provides acces from farms to the west onto the common and is overlain in

places by the modern gravelled trackway. J.J. Hall, Trysor, 18 July 2006

SMR PRN: CPAT 81490

Relationships: Photographs:

GC2006-018 18/06/2006 Trackway, looking west GC2006-019 18/06/2006 Trackway, looking northeast

NPRN: 289027

LITTLE HILL, MOUND V ROUND BARROW?

NGR: SO1406353141 Grid reference taken at centre of site Altitude: 452

Period: Bronze Age? **Broadclass:** Religious, Ritual and Funerary

Form: Earthwork **Condition:** C

Site Status:

Description: An earthen mound, 12m in diameter and up to 1m high, with a flat top. When the site was

visited during fieldwork in June 2006, the feature was overgrown with bilberries. J.J. Hall,

Trysor, 18 July 2006

SMR PRN:

Relationships: Photographs:

GC2006-022 18/06/2006 Barrow, looking south

southwest

GC2006-023 18/06/2006 Barrow, looking southeast

NPRN: 289028

BLAEN BEDW, RIDGE AND FURROW CULTIVATION RIDGE

NGR: SO1388054460 Grid reference taken at a central point within an extensive site Altitude: 430

Period: Post Medieval?; Modern? **Broadclass:** Agriculture and Subsistence

Form: Earthwork **Condition:** D

Site Status:

Description: Traces of ridge and furrow running west southwest - east northeast on either side of trackway

NPRN 289029. The ridges were 2.5m ridge to ridge. When visited during Uplands Survey in June 2006, the vegetation over the feature was grass. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-035 25/06/2006 Remains of ridge and furrow,

looking southwest

BLAEN BEDW, TRACKWAY TRACKWAY

NGR: SO1396754452 Grid reference taken at centre of site Altitude: 440

Period: Post Medieval? Broadclass: Transport

Form: Earthwork Condition: C

Site Status:

Description: A many braided trackway running northwest-southeast. The trackway was shown on 1st, 2nd

and 4th edition maps but is no longer depicted. Ridge and furrow, NPRN 289028, lay to the north and south of the trackway. When visited in June 2006, the trackway was covered with

grass. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-036 25/06/2006 Mound, looking south

NPRN: 289030

BLAEN BEDW, MOUND II ROUND BARROW?

NGR: SO1404754620 Grid reference taken at centre of site Altitude: 451

Period: Bronze Age? **Broadclass:** Religious, Ritual and Funerary

Form: Earthwork Condition: C

Site Status:

Description: An earthen mound, just off a local summit, measuring 5m by 4m and less than 0.2m high. A

modern trackway has cut the feature on its eastern side. When the site was visited during Uplands Survey in June 2006, the vegetation was close-cropped grass. J.J. Hall, Trysor, 7

November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289031

LLYN Y WAUN, POND II POND

NGR: SO1445254844 Grid reference taken at centre of site Altitude: 465

Period: Post Medieval?; Modern? Broadclass: Water Supply and Drainage

Form: Earthwork Condition: B

Site Status:

Description: An artificial pond, 7m southeast-northwest by 5m, within a natural broad gully. An earth and

stone bank on the downslope, southern side, dammed the pond. The bank was 2m wide and 0.5m high. A drainage gully, NPRN 289032, runs into the pond. When the site was visited in

June 2006, the pond still held water. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

Associated with 289032 GC2006-037 25/06/2006 Pond, looking east southeast.

Drainage channel in background, NPRN 289032

LLYN Y WAUN, GULLY II

DRAINAGE CHANNEL

NGR: SO1447754838 Grid reference taken at point along linear site Altitude: 465

Period: Post Medieval?;Modern? **Broadclass:** Water Supply and Drainage

Form: Earthwork **Condition:** B

Site Status:

Description: A drainage channel running for at least 50m from the southeast to the northwest into pond

NPRN 289031. The channel varies in width along its length from 1m to 3m and was up to 0.75m deep. When the site was visited during Uplands Survey in June 2006, the vegetation

cover was heather and bilberries. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

Associated with 289031 GC2006-038 25/06/2006 Drainage gully, looking east

southeast. Pond NPRN 289031

Altitude:

458

in foreground

NPRN: 289033

LLYN Y WAUN, GULLY I

DRAINAGE CHANNEL

NGR: SO1441354839 Grid reference taken at centre of site Altitude: 463

Period: Post Medieval?; Modern? Broadclass: Water Supply and Drainage

Form: Earthwork **Condition:** C

Site Status:

Description: A drainage channel at least 80m long aligned roughly east-west. When the site was visited

during Uplands Survey in June 2006, the vegetation cover was heatehr and bilberries. J.J. Hall,

Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289034

LLYN Y WAUN, QUARRY

QUARRY

NGR: SO1443054796 Grid reference taken at centre of site

Period: Post Medieval?; Modern? Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A small area of quarrying in a natural gully. When the feature was recorded during Uplands

Survey in June 2006, vegetation cover was grass. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

LLYN Y WAUN, POND I POND

NGR: SO1498955066 Grid reference taken at centre of site Altitude: 499

Period: Post Medieval?; Modern? Broadclass: Water Supply and Drainage

Form: Earthwork **Condition:** B

Site Status:

Description: A natural pond or boggy area to which has been added a bank or dam along its western edge to

enhance its water holding capabilities. The pond itself is irregular in shape and has recently had a rectangular island created within it. The bank is composed of earth and stone and is up to 2m wide and 0.50m high. The pond still held water when the site was visited in June 2006.

J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-039 25/06/2006 Pond, looking northeast GC2006-040 25/06/2006 Pond, looking west

NPRN: 289036

LLYN Y WAUN, BANK BANK (EARTHWORK)

NGR: SO1496255004 Grid reference taken at point along linear site Altitude: 498

Period: Post Medieval?;Modern? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: An earthen bank up to 2m wide and 0.30m high. When visited during Uplands Survey in June

2006, the feature was covered with long grass and heather. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-041 25/06/2006 Bank, looking north northwest

NPRN: 289037

LLYN Y WAUN, DRAINAGE SYSTEM DRAINAGE SYSTEM

NGR: SO1494555013 Grid reference taken at point along linear site Altitude: 498

Period: Post Medieval?;Modern? **Broadclass:** Water Supply and Drainage

Form: Earthwork **Condition:** V

Site Status:

Description: A drainage channel west of the pond at Llyn y Waun, NPRN 289035, which splits into two as

it approaches the pond. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

GWAUNCESTE HILL, TRIANGULATION TRIANGULATION POINT

POINT

NGR: SO1582255553 Grid reference taken at centre of site Altitude: 542

Period:Modern?Broadclass:CivilForm:Other StructureCondition:A

Site Status:

Description: A concrete triangulation post on the top of Gwaunceste Hill, surrounded on the south and east

by a semicircular bank. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-042 25/06/2006 Triangulation Point, looking

northwest

NPRN: 289039

GWAUNCESTE HILL, PLATFORM VI PLATFORM?

NGR: SO1570355731 Grid reference taken at centre of site Altitude: 520

Period: Unknown Broadclass: Monument < By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A probable platform 7m northwest-southeast by 4m. The southeast end is terraced into the

slope for 2.5m and there is a 3m apron at the northwest end. There was a possible smaller platform, approximately 3m square ,adjacent to its northeast side, but the density of vegetation (heather and bilberries) masked it when the site was visited in June 2006. J.J. Hall, Trysor, 7

November 2006

SMR PRN:

Relationships: Photographs:

GC2006-043 25/06/2006 Platform, looking northwest

NPRN: 289040

GWAUNCESTE HILL, GULLY I WATER CHANNEL

NGR: SO1567155796 Grid reference taken at point along linear site Altitude: 513

Period: Unknown Broadclass: Water Supply and Drainage

Form: Earthwork **Condition:** C

Site Status:

Description: A linear gully running south southwest - north northeast. It was very overgrown when visited

in June 2006 and was of uncertain purpose but appears not to be natural. J.J. Hall, Trysor, 7

November 2006

SMR PRN:

Relationships: Photographs:

GC2006-044 25/06/2006 Gully, looking south southwest

GWAUNCESTE HILL, GULLY II WAT

WATER CHANNEL

NGR: SO1566355797 Grid reference taken at point along linear site Altitude: 512

Period: Unknown Broadclass: Water Supply and Drainage

Form: Earthwork **Condition:** C

Site Status:

Description: A linear gully, 2m wide, running south southwest - north northeast, cut by the modern

trackway. It was very overgrown when visited in June 2006 and was of uncertain purpose but

appears not to be natural. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-045 25/06/2006 Gully, looking south southwest

NPRN: 289042

GWAUNCESTE HILL, GULLY III WATER CHANNEL

ong linear site Altitude:

511

Altitude:

511

NGR: SO1565155799 Grid reference taken at point along linear site

Period: Unknown Broadclass: Water Supply and Drainage

Form: Earthwork **Condition:** C

Site Status:

Description: A linear gully, 2m wide, running south southwest - north northeast, cut by the modern

trackway. It was very overgrown when visited in June 2006 and was of uncertain purpose but

appears not to be natural. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-046 25/06/2006 Gully, looking south southwest

NPRN: 289043

GWAUNCESTE HILL, GULLY IV

WATER CHANNEL

NGR: SO1564355799 Grid reference taken at point along linear site

Period: Unknown Broadclass: Water Supply and Drainage

Form: Earthwork **Condition:** C

Site Status:

Description: A linear gully, 1.5m - 2m wide, running south southwest - north northeast, cut by the modern

trackway. It was very overgrown when visited in June 2006 and was of uncertain purpose but

appears not to be natural. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

GWAUNCESTE HILL, GULLY V

WATER CHANNEL

NGR: SO1561955800 Grid reference taken at point along linear site Altitude: 511

Period: Unknown Broadclass: Water Supply and Drainage

Form: Earthwork **Condition:** C

Site Status:

Description: A linear gully, 3m wide, running south southwest - north northeast, cut by the modern

trackway. It was very overgrown when visited in June 2006 and was of uncertain purpose but

appears not to be natural. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289045

GWAUNCESTE HILL, TRACKWAY II TRACKWAY

NGR: SO1561155889 Grid reference taken at point along linear site Altitude: 515

Period: Unknown Broadclass: Transport

Form: Earthwork **Condition:** C

Site Status:

Description: An overgrown trackway shown on the 1st edition Ordnance Survey map of 1891. It was

difficult to follow on the ground in June 2006 due to the dense cover of heather. At

SO1561155889, the trackway was 1.5m-2m wide. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-047 25/06/2006 Trackway, looking east

southeast

GC2006-048 25/06/2006 Trackway, looking west

northwest

NPRN: 289046

GWAUNCESTE HILL, DITCH I DITCH

NGR: SO1584956198 Grid reference taken at point along linear site Altitude: 496

Period: Unknown Broadclass: Monument < By Form>

Form: Earthwork Condition: V

Site Status:

Description: A linear ditch, running northwest -southeast. which could be traced for over 230m. It was on

average 2.5m wide at the top and 0.5m at the bottom, and from 0.75m to 1.5m deep. The 1st edition Ordnance Survey map of 1891shows a trackway here and this ditch would seem to be running on the north side of it. When visited in June 2006, it was covered in thick heather.

J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-050 25/06/2006 Ditch, looking north northwest GC2006-051 25/06/2006 Ditch, looking northwest

GWAUNCESTE HILL, TRACKWAY III TRACKWAY

NGR: SO1570156439 Grid reference taken at point along linear site Altitude: 462

Period: Unknown Broadclass: Transport

Form: Earthwork **Condition:** V

Site Status:

Description: A trackway shown on 1st edition Ordnance Survey map of 1891. It could be partially traced

on the ground, between SO1571556396 and SO1568756480, when recorded during Uplands Survey in June 2006. The vegetation cover was heather. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289048

GWAUNCESTE HILL, DITCH II DITCH

NGR: SO1568356499 Grid reference taken at point along linear site Altitude: 453

Period: Unknown **Broadclass:** Monument <By Form>

Form: Earthwork Condition: V

Site Status:

Description: A ditch running parallel to trackway NPRN 289047 and probably a continuation of ditch

NPRN 289046. This part of the ditch is fragmented now. In general it is 3m wide at the top and 1m wide at the base and 0.75m deep. When recorded in June 2006, it was overgrown with

heather. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289049

GWAUNCESTE HILL, DITCH III DITCH

NGR: SO1566656501 Grid reference taken at point along linear site Altitude: 452

Period: Unknown **Broadclass:** Monument <By Form>

Form: Earthwork Condition: V

Site Status:

Description: A ditch with upcast soil to the southwest side. The ditch is 1.5m wide and up to 0.5m deep.

When the site was visited in June 2006, the vegetation cover was heather. J.J. Hall, Trysor, 7

November 2006

SMR PRN:

GWAUNCESTE HILL, FINDSPOT FINDSPOT

NGR: SO1564656551 Grid reference taken at centre of site Altitude: 441

Period: Modern **Broadclass:** Monument <By Form>

Form: Finds Condition: U

Site Status:

Description: A corroded and inert mortar or cannon shell was picked up from the ground surface during

Uplands Survey. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289051

GWAUNCESTE HILL, LONG HUT LONG HUT

NGR: SO1548756453 Grid reference taken at centre of site Altitude: 360

Period: Post Medieval Broadclass: Domestic

Form: Earthwork Condition: C

Site Status:

Description: An earthwork long hut, or cottage, on a terrace. The structure measured 14m

northeast-southwest by 5.5m overall. The walls or banks were between 1m to 3m wide. The feature sat within an enclosure as shown on modern Ordnance Survey mapping. The vegetation on the site when visited during Uplands Survey in June 2006 was bracken and grass.

J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-052 25/06/2006 Long hut, looking northeast

NPRN: 289052

GWAUNCESTE HILL, POND III POND

NGR: SO1543655829 Grid reference taken at centre of site Altitude: 507

Period: Modern Broadclass: Water Supply and Drainage

Form: Earthwork Condition: A

Site Status:

Description: A modern artificial pond, 30m in diameter, with a central island. The feature held water when

visited in June 2006. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-053 25/06/2006 Pond, looking southeast

WERN, QUARRY QUARRY

NGR: SO1652453445 Grid reference taken at centre of site Altitude: 383

Period: Modern Broadclass: Industrial

Form: Earthwork Condition: B

Site Status:

Description: A modern quarry, 25m east-west by 15m and up to 4m deep, alongside the road. When the site

was visited in June 2006, the vegetation was sparse within the quarry. J.J. Hall, Trysor, 7

November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289054

LITTLE HILL, EARTHWORK I PLATFORM?

NGR: SO1656953665 Grid reference taken at centre of site Altitude: 412

Period: Unknown **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: A possible platform 6m southwest-northeast by 3m. There is a square cut to its northeast end

into the slope up to 2m deep and a very slight apron extending for 1.5m. There is some stone on the floor of the feature which is also quite damp compared to the surrounding area. This dampness is unusual on this hill and may mean that the feature is connected with water supply

rather than habitation. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-054 30/06/2006 Platform, looking north

NPRN: 289055

LITTLE HILL, MOUND IV MOUND?

NGR: SO1626754622 Grid reference taken at centre of site Altitude: 442

Period: Unknown **Broadclass:** Monument < By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A possible mound of unknown purpose, 7m south southeast- north northeast by 3.5m and 0.5m

high. However when the site was recorded in June 2006, it was very hard to define due to the

dense coverage of bilberries. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-055 30/06/2006 Mound, looking south southeast

BLAEN HEATH, QUARRY QUARRY?

NGR: SO1623054723 Grid reference taken at centre of site Altitude: 470

Period: Unknown Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A small hollow 10m in diameter. When the site was recorded in June 2006 the vegetation

cover was grass, bilberries and thistles. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289057

BLAEN HEATH, EARTHWORK I QUARRY?

NGR: SO1621554731 Grid reference taken at centre of site Altitude: 469

Period: Unknown Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A rock outcrop, possibly the result of quarrying activity at its base. J.J. Hall, Trysor, 7

November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289058

GWAUNCESTE HILL, POND II POND

NGR: SO1596754910 Grid reference taken at centre of site Altitude: 500

Period: Modern? **Broadclass:** Water Supply and Drainage

Form: Earthwork **Condition:** C

Site Status:

Description: A hollow, probably natural, enhanced by a bank damming the southern end to create a pool.

The pond was over 10m in diameter and filled with reeds when the site was recorded during Uplands Survey in June 2006. The dam bank was 4m northwest-southeast, 1.5m wide and 0.5m

high. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-056 30/06/2006 Pond, looking southeast

CLAS BROOK, BANK II

BANK (EARTHWORK)

NGR: SO1555055092 Grid reference taken at point along linear site Altitude: 477

Period: Post Medieval? Broadclass: Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: An earth bank up to 0.60m high, with a ditch/trackway up to 0.30m deep on its northern side.

The bank ran from SO1564955039 to SO1560755100 where it was broken by a more recent pond, NPRN 289060. It restarted at SO1559655098 and ran to SO1551055083 where it changed direction slightly to run to SO1546355061. At this point it turned 90 degrees to run to SO1546255053. Vegetation cover was bracken when recorded in June 2006. J.J. Hall,

Trysor, 26 March 2007

SMR PRN:

Relationships: Photographs:

GC2006-057 30/06/2006 Bracken covered bank, looking

northwest

GC2006-059 30/06/2006 Bank, looking east

NPRN: 289060

CLAS BROOK, POND POND

NGR: SO1560055096 Grid reference taken at centre of site Altitude: 462

Period: Modern? **Broadclass:** Water Supply and Drainage

Form: Earthwork Condition: B

Site Status:

Description: An artificial pond created by damming a natural gully. The squarish pond measured

approximately 6m in diameter. The dam bank was 5m by 1.5m and 0.5m high. When the site was recorded in June 2006, the pond still held water although it was becoming overgrown with

reeds and bracken around the edges. J.J. Hall, Trysor, 9 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-058 30/06/2006 Pond, looking south-southeast

NPRN: 289061

CLAS BROOK, PLATFORM I PLATFORM

NGR: SO1550155056 Grid reference taken at centre of site Altitude: 470

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** B

Site Status:

Description: An earth platform, 14m southeast-northwest by 4.25m. It was cut into the slope at the

northwest end by 3m and the apron was 3m. The platform falls by c. 0.5m along its length. Fragmentary remains of a stone wall base were seen on the west side of the northwest end. Other stones were scattered around. When the site was recorded in June 2006, the platform was covered in grass, a relatively clear area in surrounding bracken. J.J. Hall, Trysor, 9

November 2006

SMR PRN:

Relationships: Photographs:

GC2006-060 30/06/2006 Platform, looking northwest

showing stonework

GC2006-061 30/06/2006 Platform, looking southeast

CLAS BROOK, BANK I

BANK (EARTHWORK)

NGR: SO1546455036 Grid reference taken at point along linear site Altitude: 473

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: B

Site Status:

Description: A linear earthwork bank running from SO1542255020 where it met a natural gully to

SO1549955052 where it met platform NPRN 289061. The bank was 0.5m high and up to 1.5m wide. When the feature was recorded in June 2006, the vegetation cover was bilberries in an

area densely covered in bracken. J.J. Hall, Trysor, 9 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289063

CLAS BROOK, SHELTER SHELTER?

NGR: SO1542955029 Grid reference taken at centre of site Altitude: 474

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A U shaped earthwork feature enclosing an internal area of 5m southeast-northwest by 1m.

The northwest end was cut into the slope and the southwest and northeast sides were formed by broad banks, 2.75m and 2.5m wide respectively. The southeastern side was open but could have been cut by a trackway that ran along the north side of bank NPRN 289062. Vegetation

cover in June 2006 was bracken and bilberries.J.J. Hall, Trysor, 9 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-062 30/06/2006 Shelter, looking north-northwest

GC2006-063 30/06/2006 Shelter, looking northeast

NPRN: 289064

CLAS BROOK, PLATFORM II PLATFORM

NGR: SO1569354873 Grid reference taken at centre of site Altitude: 457

Period: Post Medieval? Broadclass: Monument < By Form>

Form: Earthwork **Condition:** B

Site Status:

Description: A broad platform, 11m northeastsouthwest by 10m, on a south west facing slope. The hood is

1.25m deep and the apron 1m high. The internal area of the platform is 8.1m with a step down of 0.25m 5m from the hood. When the site was recorded in June 2006 the feature was heavily

covered with bracken. J.J. Hall, Trysor, 9 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-064 30/06/2006 Platform, looking southwest GC2006-065 30/06/2006 Platform, looking northeast

CLAS BROOK, PLATFORM III PLATFORM

NGR: SO1570254805 Grid reference taken at centre of site Altitude: 447

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: B

Site Status:

Description: An earthwork platform, 13.7m southwest-northeast by 4.75m. The northeast end was cut into

the slope, and the apron was 2m wide and 1.5m high. The remains of a possible wall base were seen in the west corner near to the apron. Other stone was scattered around the platform. When the site was recorded in June 2006, it was covered with thick bracken. J.J. Hall, Trysor,

9 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-066 30/06/2006 Platform, looking southwest

NPRN: 289066

CWM TWRCH, QUARRY II QUARRY

NGR: SO1569054704 Grid reference taken at centre of site Altitude: 431

Period: Post Medieval?; Modern? **Broadclass:** Industrial

Form: Earthwork Condition: B

Site Status:

Description: A series of small quarries, probably for the construction of the adjacent common boundary.

When the site was recorded in June 2006 it was covered in grass and bracken. J.J. Hall,

Trysor, 9 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289067

CWM TWRCH, BANK III BANK (EARTHWORK)

NGR: SO1570854657 Grid reference taken at point along linear site Altitude: 424

Period: Post Medieval? Broadclass: Monument < By Form>

Form: Earthwork **Condition:** V

Site Status:

Description: A 2m wide bank running east northeast - west southwest. When the site was visited in June

2006, the vegetation was bilberries and bracken. J.J. Hall, Trysor, 9 November 2006

SMR PRN:

CWM TWRCH, QUARRY I

taken at centre of site Altitude: 410

QUARRY

NGR: SO1577554545 Grid reference taken at centre of site **Period:** Post Medieval?:Modern? **Broadclass:** Industrial

Form: Earthwork Condition: B

Site Status:

Description: An area of small quarry pits, close to the common boundary. When the site was recorded in

June 2006 it was covered in grass and bracken. J.J. Hall, Trysor, 9 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289069

UPPER CWM-TWRCH, QUARRY III QUARRY

NGR: SO1598654438 Grid reference taken at centre of site Altitude: 392

Period: Post Medieval?; Modern? Broadclass: Industrial

Form: Earthwork Condition: B

Site Status:

Description: A quarry, 5m in diameter and cut up to 5m deep at the back of the quarry. Vegetation cover

was grass and nettles in June 2006. J.J. Hall, Trysor, 9 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-067 30/06/2006 Quarry, looking northeast

NPRN: 289070

UPPER CWM-TWRCH, QUARRY II QUARRY

NGR: SO1605054420 Grid reference taken at centre of site Altitude: 399

Period: Post Medieval?;Modern? **Broadclass:** Industrial

Form: Earthwork Condition: B

Site Status:

Description: A small quarry adjacent to the common boundary. When the site was recorded in June 2006,

the vegetation cover was grass and bracken. J.J. Hall, Trysor, 9 November 2006

SMR PRN:

UPPER CWM-TWRCH, QUARRY I QUARRY

NGR: SO1611354392 Grid reference taken at centre of site Altitude: 402

Period: Post Medieval?;Modern? **Broadclass:** Industrial

Form: Earthwork Condition: C

Site Status:

Description: A small quarry, 10m by 5m. When the site was recorded in June 2006, the quarry was grassed

over with little stone showing. J.J. Hall, Trysor, 9 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289072

CWM TWRCH, FIELD SYSTEM FIELD SYSTEM

NGR: SO1631554218 Grid reference taken at a central point within an extensive site Altitude: 405

Period: Post Medieval? Broadclass: Agriculture and Subsistence

Form: Complex **Condition:** V

Site Status:

Description: A field system on the common above the eastern side of Cwm Twrch. Field banks encosed

areas of cultivation ridges. When the site was visited in June 2006, the feature was covered in

bracken. J.J. Hall, Trysor, 9 November 2006

SMR PRN:

Relationships: Photographs:

 Consists of
 289264
 GC2007-077
 25/02/2007
 Field system, looking south

 Consists of
 289265

 Consists of
 289268

 Consists of
 289264

 Consists of
 289073

Consists of 289265 Consists of 289268

NPRN: 289073

CWM TWRCH, CULTIVATION RIDGES CULTIVATION RIDGE

NGR: SO1629954229 Grid reference taken at a central point within an extensive site Altitude: 405

Period: Post Medieval? Broadclass: Agriculture and Subsistence

Form: Earthwork **Condition:** C

Site Status:

Description: Cultivation ridges within the field system NPRN 289072. J.J. Hall, Trysor, 20 November 2006

SMR PRN:

Relationships: Photographs:

Part of 289072

LITTLE HILL, POND II POND

NGR: SO1441953071 Grid reference taken at centre of site Altitude: 415

Period: Modern? Broadclass: Water Supply and Drainage

Form: Earthwork Condition: B

Site Status:

Description: A small artificial pond, 6m by 5m, with a dam of stone and soil to the south. A spring trickled

into the pond area when the site was visited in June 2006. J.J. Hall, Trysor, 10 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-068 04/07/2006 Pond, looking west-southwest

NPRN: 289075

LITTLE HILL, MOUND III MOUND

NGR: SO1450953170 Grid reference taken at centre of site Altitude: 413

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: Two mounds, each approximately 2m square, probably derived from quarrying. Vegetation

cover was grass and bracken in July 2006. J.J. Hall, Trysor, 10 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289076

LITTLE HILL, QUARRY IX QUARRY

NGR: SO1448753922 Grid reference taken at centre of site Altitude: 463

Period: Post Medieval? **Broadclass:** Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: Quarrying in an area 12m by 10m and up to 2m deep to the east of a rock outcrop. When the

site was recorded in July 2006 vegetation cover was grass and nettles. J.J. Hall, Trysor, 10

November 2006

SMR PRN:

Relationships: Photographs:

GC2006-069 04/07/2006 Quarry, looking east-southeast

CWM TWRCH, POND POND

NGR: SO1431654030 Grid reference taken at centre of site Altitude: 460

Period: Modern? **Broadclass:** Water Supply and Drainage

Form: Earthwork Condition: C

Site Status:

Description: An artificial, circular pond created by damming a natural gully. When visited in July 2006, the

dam had been breached and the pond no longer held water. Vegetation cover was grass. J.J.

Hall, Trysor, 10 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289078

LITTLE HILL, BANK III BANK (EARTHWORK)

NGR: SO1437553248 Grid reference taken at point along linear site Altitude: 448

Period: Unknown **Broadclass:** Monument <By Form>

Form: Earthwork Condition: B

Site Status:

Description: A bank aligned northeast - southwest with a slight ditch on the northern, uphill side. The ditch

could be traced for 146m and was 2m wide and between 0.30m-0.40m high. There was a slight kink in the ditch at SO1437553248. When the feature was recorded in July 2006, the

vegetation growing on it was bilberries. J.J. Hall, Trysor, 10 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-070 04/07/2006 Bank, looking west

NPRN: 289079

LITTLE HILL, EARTHWORK II EARTHWORK

NGR: SO1433253186 Grid reference taken at centre of site Altitude: 444

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: A negative earthwork, probably a platform with some later disturbance. The platform overall

was 22m northeast-southwest by 9m. The hood was 3m deep and the apron 0.8m high. An earth bank 3m wide and 4-5m long and 0.5m high ran across the feature. When the site was recorded in July 2006, the vegetation cover was short grass and bracken. J.J. Hall, Trysor, 10

November 2006

SMR PRN:

Relationships: Photographs:

GC2006-071 04/07/2006 Platform, looking

south-southeast

GELLIDYWYLL, PLATFORM VI PLATFORM

NGR: SO1443652788 Grid reference taken at centre of site Altitude: 345

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status: RD168

Description: A large earthwork platform measuring overall 23m southeast-northwest by 10m. It is cut into

the slope at is northwest end and with a large lipped bank at the southeast, apron end. The internal level area measured 16m by 4.5m. When the site was visited in June 2006, the feature

was covered in bracken. J.J. Hall, Trysor, 6 November 2006

SMR PRN: CPAT 50334

Relationships: Photographs:

NPRN: 289081

GELLIDYWYLL, PLATFORM VII PLATFORM

NGR: SO1434352752 Grid reference taken at centre of site Altitude: 358

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork Condition: B

Site Status: RD168

Description: An earthwork platform, 7m north northeast-south southwest and 4m wide. It had a slight hood

at the north northeast end and an apron 1m deep at the south southwest end. When the site was visited in June 2006 the vegetation cover was bracken. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-031 18/06/2006 Bracken covered platform,

looking east northeast

NPRN: 289082

LITTLE HILL, POND III POND

NGR: SO1683753647 Grid reference taken at centre of site Altitude: 435

Period: Post Medieval?; Modern? Broadclass: Water Supply and Drainage

Form: Earthwork **Condition:** C

Site Status:

Description: A small artificial pond, on a south facing slope, measuring 4m in diameter and 0.50m deep.

The pond had been created by building an earth bank dam, 1m wide and 0.20m high, on the south and west sides of the feature. The southern side had been breached and the feature no

longer held water when visited in November 2006. J.J. Hall, Trysor, 6 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-032 18/06/2006 Large platform, looking

northwest

GC2006-033 18/06/2006 Large platform, looking

southwest

GC2006-034 18/06/2006 Detail of the bank at the positive

end of the platform, looking

northeast

GC2006-072 04/11/2006 Drainage trench for pond,

looking southeast

LITTLE HILL, QUARRY VIII QUARRY

NGR: SO1702253531 Grid reference taken at centre of site Altitude: 418

Period: Post Medieval?; Modern? Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A former quarry 15m northwest-southeast by 6m and up to 2.5m deep, adjacent to the

boundary of the common. When the site was visited during Uplands Survey in November 2006, the vegetation cover was bracken and close cropped grass. J.J. Hall, Trysor, 6 November

2006

SMR PRN:

Relationships: Photographs:

GC2006-073 04/11/2006 Quarry, looking south

NPRN: 289084

GLASCWM-IG, ENCLOSURE I ENCLOSURE

NGR: SO1719053503 Grid reference taken at centre of site Altitude: 400

Period: Post Medieval?;Modern? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: V

Site Status:

Description: A polygonal enclosure measuring roughly 300m east-west by 95m. It is defined by an earth

bank 1m wide and 0.3-0.5m high to the east and north, and part of the west side and by the common boundary to the south. The bank appears intact apart from the western extent where it has been removed by a quarry, NPRN 289085, and the eastern extent removed by a modern track that runs along the common boundary at SO1732253424. The enclosure seems to be later development after the enclosure of the common and connected to Glascwm Ig to the south. J.J.

Hall, Trysor, 6 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-074 04/11/2006 Section of bank, looking north GC2006-083 04/11/2006 Enclosure bank, looking south

NPRN: 289085

GLASCWM-IG, QUARRY V QUARRY

NGR: SO1704153506 Grid reference taken at centre of site Altitude: 404

Period: Post Medieval?;Modern? **Broadclass:** Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: A small quarry, 4m in diameter and up to 1.5m deep, near the common boundary. It appears to

have removed the western end of the bank of enclosure NPRN 289084. When visited in November 2006 the quarry was overgrown with grass and bracken. J.J. Hall, Trysor, 6

November 2006

SMR PRN:

GLASCWM-IG, QUARRY IV QUARRY

NGR: SO1705553459 Grid reference taken at centre of site Altitude: 390

Period: Post Medieval?; Modern? Broadclass: Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: A quarry, 25m east-west by 15m and up to 2m deep, along the common boundary. There was

some evidence of the stone that had been quarried, a shale with very well developed cleavage planes. When the site was visited in November 2006, the vegetation growing in the quarry was

grass and nettles. J.J. Hall, Trysor, 6 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-075 04/11/2006 Quarry, looking northwest

NPRN: 289087

LITTLE HILL, POND IV POND

NGR: SO1754753606 Grid reference taken at centre of site Altitude: 435

Period: Modern? **Broadclass:** Water Supply and Drainage

Form: Earthwork Condition: B

Site Status:

Description: An artificial pond measuring 20m northwest-southeast by 8m. It was formed by a depression

cut into the gentle southeast facing slope with a slight bank damming it to the southeast. Its depth was not ascertained as it was still holding water when visited in November 2006. J.J.

Hall, Trysor, 6 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-081 04/11/2006 Pond, looking southeast

NPRN: 289088

GLASCWM-IG, QUARRY II QUARRY

NGR: SO1730353440 Grid reference taken at centre of site Altitude: 392

Period: Post Medieval?:Modern? **Broadclass:** Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: A quarry, 20m east-west by 10m, with a level base, cut into the south facing slope. A short

trackway lead to it from the west. When the site was visited in November 2006, the quarry was

overgrown with bracken. J.J. Hall, Trysor, 6 November 2006

SMR PRN:

GLASCWM-IG, BANK

BANK (EARTHWORK)

NGR: SO1725853453 Grid reference taken at point along linear site Altitude: 393

Period: Post Medieval?;Modern? Broadclass: Monument < By Form>

Form: Earthwork Condition: V

Site Status:

Description: A bank 1m wide and up to 0.3m high running from SO1723753462 to SO1725953444.

Vegetation cover in November 2006 was bracken. J.J. Hall, Trysor, 6 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289090

GLASCWM-IG, QUARRY I QUARRY

NGR: SO1740453409 Grid reference taken at centre of site Altitude: 391

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A quarry approximately 10m square and less than 2m deep at the southern, downslope end of a

natural gully. When the site was visited in November 2006, the vegetation cover in the quarry

was grass and bracken. J.J. Hall, Trysor, 6 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289091

CWM CRAWNLLWYN, POND POND

NGR: SO1592156048 Grid reference taken at centre of site Altitude: 507

Period: Modern Broadclass: Water Supply and Drainage

Form: Earthwork Condition: A

Site Status:

Description: A recent circular pond, 35m in diameter, created by damming a natural gully. The dam bank

was 2m high from the downslope side and 10m wide made of soil and stone. J.J. Hall, Trysor,

6 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-049 25/06/2006 Pond, looking north

GLASCWM-IG, QUARRY III QUARRY

NGR: SO1748253357 Grid reference taken at centre of site Altitude: 385

Period: Post Medieval?;Modern? **Broadclass:** Industrial

Form: Earthwork Condition: C

Site Status:

Description: A quarry, 12m north-south by 6m cut into a south facing slope. When visited in November

2006 the vegetation cover in the quarry was close cropped grass and bracken. J.J. Hall,

Trysor, 6 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289093

GLASCWM-IG, QUARRY VI QUARRY

NGR: SO1755853323 Grid reference taken at centre of site Altitude: 380

Period: Post Medieval?;Modern? **Broadclass:** Industrial

Form: Earthwork Condition: C

Site Status:

Description: At least two small quarry pits up to 6m in diameter and 2m deep. When visited in November

2006, the vegetation cover in the quarry pits was bracken. J.J. Hall, Trysor, 6 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289094

GLASCWM-IG, ENCLOSURE II ENCLOSURE

NGR: SO1744353447 Grid reference taken at centre of site Altitude: 410

Period: Post medieval?; Modern? **Broadclass:** Monument < By Form>

Form: Earthwork Condition: B

Site Status:

Description: An irregular polygonal enclosure, 230m east-west by up to 190m. The eastern and northern

sides are defined by a bank and ditch. The ditch was on the eastern, "external" side of the bank. The bank and ditch were c.1.5m wide each with an overall depth of 1m. The bank and ditch had been removed close to the common boundary by a modern track. The western side was part of NPRN 289084 and the southern side the common boundary. The enclosure was full of

bracken when visited in November 2006. J.J. Hall, Trysor, 6 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-076 04/11/2006 Enclosure boundary, looking

north-northwest

GC2006-082 04/11/2006 Enclosure, looking southeast

LITTLE HILL, ENCLOSURE III ENCLOSURE

NGR: SO1771453304 Grid reference taken at centre of site Altitude: 394

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: A polygonal enclosure defined on the southwest, northwest and northeast by a bank and ditch,

up to 1.25m wide and 0.5m high. The southern side was formed from the common boundary. Enclosure NPRN 289097 lay to the north of it separated by a trackway. Vegetation cover in

November 2006 was bracken. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-077 04/11/2006 Enclosure boundary, looking

northwest

NPRN: 289096

LITTLE HILL, CULTIVATION RIDGES I CULTIVATION RIDGE

NGR: SO1771853295 Grid reference taken at a central point within an extensive site Altitude: 393

Period: Post Medieval?; Modern? Broadclass: Agriculture and Subsistence

Form: Earthwork **Condition:** C

Site Status:

Description: Possible ridge and furrow within enclosure NPRN 289095, less than 0.10m high. Vegetation

cover in November 2006 was grass and bracken.. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289097

LITTLE HILL, ENCLOSURE IV ENCLOSURE

NGR: SO1784853476 Grid reference taken at centre of site Altitude: 385

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: A polygonal enclosure measuring 200m northeast-southwest by c.60m. It is defined by a bank

and external ditch on the north and west sides, and by the common boundary on the south and east sides. Enclosure NPRN 289095 lay to the south of it separated by a trackway. Vegetation

cover in November 2006 was bracken and grass. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-078 04/11/2006 Enclosure boundary, looking

northwest

LITTLE HILL, TRACKWAY I TRACKWAY

NGR: SO1786153585 Grid reference taken at point along linear site Altitude: 385

Period: Post Medieval? **Broadclass:** Transport

Form: Earthwork Condition: C

Site Status:

Description: A trackway running east-west downslope towards the common boundary. The trackway was

2.5m wide and 0.5m deep. When seen in November 2006, it was overgrown with bracken. J.J.

Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-079 04/11/2006 Trackway, looking east

NPRN: 289099

LITTLE HILL, TRACKWAY II TRACKWAY

NGR: SO1779153766 Grid reference taken at point along linear site Altitude: 375

Period: Post Medieval? **Broadclass:** Transport

Form: Earthwork Condition: C

Site Status:

Description: A trackway on the north facing slope of Little Hill. The trackway could only be traced for a

short distance but was a cut level track, 2m wide. When the site was visited in November

2006, the vegetation cover was bracken. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289100

LITTLE HILL, BANK II BANK (EARTHWORK)

NGR: SO1722754236 Grid reference taken at point along linear site Altitude: 400

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A short section of bank, 1.2m wide and 0.3m high with a ditch, 1m wide and 0.3m deep on its

southern side. When the site was visited in November 2006, the feature was covered with

bracken and bilberries. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

LITTLE HILL, QUARRY VII QUARRY

NGR: SO1701354376 Grid reference taken at centre of site Altitude: 400

Period: Post Medieval?;Modern? **Broadclass:** Industrial

Form: Earthwork Condition: C

Site Status:

Description: A small quarry, 10m northeast-southwest by 5m and up to 1.5m deep cut into north facing

slope, close to the common boundary. When the site was visited in November 2006, the

vegetation in the quarry was grass and bracken. J.J. Hall, Trysor, 7 November 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289102

LITTLE HILL, POND I POND

NGR: SO1702654239 Grid reference taken at centre of site Altitude: 438

Period: Modern **Broadclass:** Water Supply and Drainage

Form: Earthwork Condition: A

Site Status:

Description: An artificial pond 20m in diameter, surrounded by rough banks made from material scooped

from the centre of the feature. The damming bank on the south side of the feature was 1m high. When visited in November 2006, the feature still held water. J.J. Hall, Trysor, 7

November 2006

SMR PRN:

Relationships: Photographs:

GC2006-080 04/11/2006 Pond, looking north

NPRN: 289103

LITTLE HILL, ROUND BARROW ROUND BARROW

NGR: SO1712753796 Grid reference taken at centre of site Altitude: 461

Period: Bronze Age **Broadclass:** Religious, Ritual and Funerary

Form: Earthwork Condition: B

Site Status:

Description: A circular earth mound, 14m in diameter and 1m high, below the summit of Little Hill. When

the site was visited in November 2006, the feature was covered with short cropped grass and

bilberries. J.J. Hall, Trysor, 6 November 2006

SMR PRN:

Relationships: Photographs:

GC2006-084 04/11/2006 Round barrow, looking west GC2006-085 04/11/2006 Round barrow, looking north GC2007-097 01/03/2007 Round barrow, looking north

GWAUNCESTE HILL, PLATFORM I PLATFORM

NGR: SO1768355193 Grid reference taken at centre of site Altitude: 386

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** B

Site Status:

Description: An earthwork platform cut into the east facing slope. The level area measured 6.5m

north-south. It could be measured for 3m east-west, with it possibly exteneding another 8m eastwards but a mat of dead bracken obscured much of the rest of the feature. J.J. Hall,

Trysor, 11 December 2006

SMR PRN: CPAT 50299

Relationships: Photographs:

GC2006-086 09/12/2006 Platform, looking west

NPRN: 289105

GWAUNCESTE HILL, PLATFORM II PLATFORM

NGR: SO1767655244 Grid reference taken at centre of site Altitude: 389

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork Condition: B

Site Status:

Description: An earthwork platform, one of several cut into the east facing slope on the eastern edge of

Gwaunceste Hill. This platform is paired with NPRN 289106 which adjoins it to the north separated by a gully 0.2m deep and 2m wide. The level area of this platform measures 19m east-west by 9m. The western end cuts into the slope by 3m and the eastern end is terraced out by 2m. At the eastern end of the platform were low banks on the north and south sides. Some damage from animal burrowing had occurred and the vegetation cover was bracken and grass

in December 2006. J.J. Hall, Trysor, 11 December 2006

SMR PRN: CPAT 50300

Relationships: Photographs:

GC2006-087 09/12/2006 Platform, looking north GC2006-088 09/12/2006 Platform, looking northeast

NPRN: 289106

GWAUNCESTE HILL, PLATFORM III PLATFORM

NGR: SO1768255256 Grid reference taken at centre of site Altitude: 390

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: An earthwork platform, one of several cut into the east facing slope on the eastern edge of

Gwaunceste Hill. This platform is paired with NPRN 289105 which adjoins it to the south separated by a gully 0.2m deep and 2m wide. The level area of this platform measures 20m east-west by 9m. The western end cuts into the slope by 3.5m and the eastern end is terraced out by 2m. Some damage from animal burrowing had occurred and in December 2006 the

vegetation cover was bracken and grass. J.J. Hall, Trysor, 11 December 2006

SMR PRN: CPAT 50301

Relationships: Photographs:

GC2006-090 09/12/2006 Platform, looking east GC2006-091 09/12/2006 Platform, looking southeast,

with 289105 beyond

GWAUNCESTE HILL, EARTHWORK HOLLOW

NGR: SO1767455254 Grid reference taken at centre of site Altitude: 390

Period: Unknown Broadclass: Unassigned

Form: Earthwork **Condition:** C

Site Status:

Description: A rectangular cut feature, within platform NPRN 289106, embanked on the south and east

sides. It measured 2m north-south by 1.75m and 0.3m deep and where present the bank was 0.30m high. It was thought to be relatively modern feature compared to the platform but its function was unclear. Vegetation cover was bracken and grass in December 2006. J.J. Hall,

Trysor, 11 December 2006

SMR PRN:

Relationships: Photographs:

GC2006-089 09/12/2006 Hollow, looking east

NPRN: 289108

GWAUNCESTE HILL, PLATFORM V PLATFORM

NGR: SO1771155268 Grid reference taken at centre of site Altitude: 383

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: An earthwork platform, one of several cut into the east facing slope on the eastern edge of

Gwaunceste Hill. The level area of this platform roughly measures 10m east-west by 5m but the density of dead bracken in December 2006 made it difficult to assess the feature properly.

J.J. Hall, Trysor, 11 December 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289109

GWAUNCESTE HILL, BANK BANK (EARTHWORK)

NGR: SO1755055280 Grid reference taken at point along linear site Altitude: 418

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** V

Site Status:

Description: A bank enclosing a piece of land to the north of the platform group at Gwaunceste Hill,

probably with cultivation ridges within it. The bank ran from SO1768955284 to SO1767155274 then to SO1759055267. Up to this point a trackway ran alongside the southern side of the bank but disappeared from this point on. The bank though continued, 1.5m wide and up to 0.30m high, to SO1746355350 where it met an east-west stream. J.J. Hall, Trysor, 11

December 2006

SMR PRN:

Relationships: Photographs:

GC2006-095 09/12/2006 Bank, looking east-southeast

GWAUNCESTE HILL, PLATFORM IV PLATFORM

NGR: SO1767155281 Grid reference taken at centre of site Altitude: 391

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: An earthwork platform, the northernmost of several cut into the east facing slope on the eastern

edge of Gwaunceste Hill. The level area of this platform measures 14.5m east-west by 5.5m. The western end cuts into the slope by 1.8m and the eastern end is terraced out by 3.5m. Some damage from animal burrowing had occurred and in December 2006 the vegetation cover was grass and a little bracken. A shelter, NPRN 289111, was cut into the apron of the platform.

J.J. Hall, Trysor, 11 December 2006

SMR PRN: CPAT 50302

Relationships: Photographs:

GC2006-092 09/12/2006 Platform, looking

west-southwest

GC2006-093 09/12/2006 Platform, looking southeast

NPRN: 289111

GWAUNCESTE HILL, SHELTER SHELTER

NGR: SO1768255284 Grid reference taken at centre of site Altitude: 390

Period: Post Medieval? Broadclass: Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A sub circular earthwork cut into the apron of the platform, NPRN 289110. It measured 2m

internally with banks of 2m on the north and south sides J.J. Hall, Trysor, 11 December 2006

SMR PRN:

Relationships: Photographs:

GC2006-094 09/12/2006 Shelter, looking east

NPRN: 289112

GWAUNCESTE HILL, TRACKWAY I TRACKWAY

NGR: SO1771055380 Grid reference taken at point along linear site Altitude: 390

Period: Post Medieval? Broadclass: Transport

Form: Earthwork **Condition:** V

Site Status:

Description: A trackway running from SO1770055394 to SO1771355345, 60m west of the parallel

trackway shown on 1st edition Ordnance Survey map of 1891. The trackway was 2.2m wide at the base, 4m at the top and cut up to 0.80m deep. Vegetation cover was grass and bracken in

December 2006. J.J. Hall, Trysor, 11 December 2006

SMR PRN:

Relationships: Photographs:

GC2006-098 09/12/2006 Trackway, looking north

GWAUNCESTE HILL, CULTIVATION CULTIVATION RIDGE

RIDGES II

NGR: SO1769355390 Grid reference taken at a central point within an extensive site Altitude: 392

Period: Post Medieval **Broadclass:** Agriculture and Subsistence

Form: Earthwork Condition: C

Site Status:

Description: An extensive area of cultivation ridges running north- south on the east facing slopes at the

eastern end of Gwaunceste Hill. Vegetation cover was grass and dead bracken. J.J. Hall,

Trysor, 11 December 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289114

GWAUNCESTE HILL, CULTIVATION CULTIVATION RIDGE

RIDGES I

NGR: SO1761755442 Grid reference taken at a central point within an extensive site Altitude: 405

Period: Post Medieval Broadclass: Agriculture and Subsistence

Form: Earthwork Condition: C

Site Status:

Description: An extensive area of cultivation ridges running east-west on the east facing slopes at the

eastern end of Gwaunceste Hill. Vegetation cover was grass and dead bracken. J.J. Hall,

Trysor, 11 December 2006

SMR PRN:

Relationships: Photographs:

GC2006-099 09/12/2006 Cultivation ridges, looking west GC2006-102 09/12/2006 Cultivation ridges, looking west

NPRN: 289115

GILWERN BROOK, EARTHWORK III BUILDING?

NGR: SO1775455742 Grid reference taken at centre of site Altitude: 380

Period: Post Medieval Broadclass: Domestic

Form: Earthwork Condition: C

Site Status:

Description: AAs seen in December 2006, this feature was an earth mound, 9m north northeast-south

southwest by 5m with a possible building platform south of it. Clwyd Powys Archaeological Trust had previously identified the site from aerial photographs where it was seen as a building and enclosure to the north, NPRN 289117, with a trackway leading to them. In December 2006 the land around had been heavily improved, removing all trace of the trackway and

making the remaining features hard to interpret. J. Hall, Trysor, 11 December 2006

SMR PRN: CPAT 33934

Relationships: Photographs:

GC2006-103 09/12/2006 Building site, looking east

GILWERN BROOK, ENCLOSURE ENCLOSURE

NGR: SO1739455870 Grid reference taken at centre of site Altitude: 400

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: D

Site Status:

Description: A rectangular enclosure, 20m roughly north-south by 15m, in the southwest corner of a large

field. The enclosure was shown on modern Ordnance Survey mapping but not on previous editions. In December 2006, the feature had been remove,d as part of land improvement works, leaving only evidence at ground level for its existence. J.J. Hall, Trysor, 11 December

2006

SMR PRN:

Relationships: Photographs:

NPRN: 289117

GILWERN BROOK, EARTHWORK II ENCLOSURE?:BUILDING?

NGR: SO1775155755 Grid reference taken at centre of site Altitude: 380

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: As seen in December 2006, this feature was a rectilinear depression with a bank around it, 7m

north northeast – south southwest by 4m. Clwyd Powys Archaeological Trust had previously identified the site from aerial photographs where it was seen as a enclosure and a building to the south it, NPRN 289115, with a trackway leading to it. In December 2006 the land around had been heavily improved, removing all trace of the trackway and making the remaining

features hard to interpret. .J. Hall, Trysor, 11 December 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289118

GWAUNCESTE HILL, POND I POND

NGR: SO1748055650 Grid reference taken at centre of site Altitude: 418

Period: Modern Broadclass: Water Supply and Drainage

Form: Earthwork **Condition:** B

Site Status:

Description: A pond created by damming a natural gully. J.J. Hall, Trysor, 11 December 2006

SMR PRN:

GWAUNCESTE HILL, WATERCOURSE WATER CHANNEL

NGR: SO1774955192 Grid reference taken at point along linear site Altitude: 372

Period: Post Medieval? Broadclass: Water Supply and Drainage

Form: Earthwork **Condition:** C

Site Status:

Description: A gully cut into an eastfacing slope with a bank defining the feature on the east. The gully ran

around a bottom contour of a slope for approximately 20m north-south. The gully was 1m wide and 0.20m deep and the bank was 1m wide and 0.25m high. When the feature was recorded in

December 2006, the vegetation cover was grass. J.J. Hall, Trysor, 2 January 2007

SMR PRN:

Relationships: Photographs:

GC2006-105 22/12/2006 Gully, looking south-southwest

NPRN: 289120

GWAUNCESTE HILL, MOUND MOUND

NGR: SO1776355239 Grid reference taken at centre of site Altitude: 378

Period: Unknown **Broadclass:** Monument < By Form>

Form: Earthwork Condition: C

Site Status:

Description: Two linear mounds, each 4m north northeast - south southwest and 0.50m high with a ditch on

either side. They may be small pillow mounds or the result of heavy machinery. When the features were recorded in December 2006, the vegetation cover was bracken. J.J. Hall, Trysor,

2 January 2007

SMR PRN:

Relationships: Photographs:

GC2006-106 22/12/2006 Mounds, looking

north-northeast

NPRN: 289121

GWAUNCESTE HILL, TRACKWAY IV TRACKWAY

NGR: SO1776355314 Grid reference taken at point along linear site Altitude: 383

Period: Post Medieval? Broadclass: Transport

Form: Earthwork Condition: C

Site Status:

Description: A section of trackway 40m in length, 1.75m wide at the base and cut into the ground surface by

up to 1m. When the trackway was recorded in December 2006, the vegetation cover was

bracken, moss and grass. J.J. Hall, Trysor, 2 January 2007

SMR PRN:

Relationships: Photographs:

GC2006-107 22/12/2006 Trackway, looking south

GILWERN BROOK, SHEEP FOLD SHEEP FOLD?

NGR: SO1824756100 Grid reference taken at centre of site Altitude: 351

Period: Post Medieval? Broadclass: Agriculture and Subsistence

Form: Earthwork Condition: C

Site Status:

Description: A triangular, earthwork fold on the northern side of a bend in the stream. A bank, 0.50m high

and c. 2m wide, with an external ditch, defined the fold. The side parallel to the east northeast - west southwest fence to the north was the longest, 19m. The southwest side was 11m, and the southeast side was 17m with no external ditch and a possible entrance. When recorded in

December 2006, the vegetation cover was grass. J.J. Hall, Trysor, 2 January 2007

SMR PRN:

Relationships: Photographs:

GC2006-108 22/12/2006 Enclosure, looking northwest

NPRN: 289123

GILWERN BROOK, EARTHWORK I PLATFORM?

NGR: SO1833256131 Grid reference taken at centre of site Altitude: 353

Period: Unknown **Broadclass:** Monument <By Form>

Form: Earthwork Condition: D

Site Status:

Description: A possible platform on the south side of Gilwern Brook, cut into a northwest facing slope. The

feature was approximately 6m northwest - southeast by 5m. When recorded in December

2006, the vegetation cover was grass and reeds. J.J. Hall, Trysor, 2 January 2007

SMR PRN:

Relationships: Photographs:

GC2006-109 22/12/2006 Possible platform, looking east

NPRN: 289124

GILWERN BROOK, EARTHWORK IV QUARRY?

NGR: SO1854856157 Grid reference taken at centre of site Altitude: 360

Period: Unknown Broadclass: Unassigned

Form: Earthwork **Condition:** C

Site Status:

Description: A scoop 11m east southeast - west southwest by 2m and 1.5m deep. The spoil from the feature

was upcast to the north. When recorded in December 2006, the feature was covered in short

grass and some heather. J.J. Hall, Trysor, 2 January 2007

SMR PRN:

GILWERN BROOK, TRACKWAY II TRACKWAY

NGR: SO1860456238 Grid reference taken at point along linear site Altitude: 356

Period: Post Medieval? Broadclass: Transport

Form: Earthwork **Condition:** V

Site Status:

Description: A trackway, traced for over 90m, running southeast from the south side of Gilwern Brook at

SO1856756254 to SO1865056219. Vegetation cover in December 2006 was grass. J.J. Hall,

Trysor, 2 January 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289126

CAETY TRAYLOW, BANK II BANK (EARTHWORK)

NGR: SO1887056170 Grid reference taken at point along linear site Altitude: 388

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: V

Site Status:

Description: A substantial earthwork bank with a ditch on its northern side. It runs eastwards from the

enclosures at Pant Glas, via SO1879756144 and then turning northeast at SO1888556165 to SO1890756176. It appeared to be interrupted by ridge and furrow, NPRN 289128. The bank was up to 2.25m and 0.75m high and the ditch was 1.5m wide and up to 0.60m deep. When the feature was recorded in December 2006, the vegetation cover was bracken and moss. J.J.

Hall, Trysor, 2 January 2007

SMR PRN:

Relationships: Photographs:

GC2006-115 22/12/2006 Bank, looking west GC2006-116 22/12/2006 Bank, looking east

NPRN: 289127

CAETY TRAYLOW, CULTIVATION CULTIVATION RIDGE

RIDGES II

NGR: SO1891656187 Grid reference taken at a central point within an extensive site Altitude: 395

Period: Post Medieval? Broadclass: Agriculture and Subsistence

Form: Earthwork **Condition:** B

Site Status:

Description: An area 50m northeast-southwest by 25m of narrow ridges and deep furrows. The ridges are

about 1m wide and look more like lazy beds or preparation for conifer planting than ridge and furrow. The feature appears to interrupt bank NPRN 289126. When the feature was recorded in December 2006, the vegetation cover was moss and heather. J.J. Hall, Trysor, 2 January

2007

SMR PRN:

Relationships: Photographs:

GC2006-117 22/12/2006 Cultivation ridges, looking

north-east

CULTIVATION RIDGE GILWERN BROOK, CULTIVATION RIDGES

NGR: SO1887956265 Grid reference taken at a central point within an extensive site **Altitude:** 380

Agriculture and Subsistence Period: **Broadclass:** Post Medieval?

Form: Earthwork Condition:

Site Status:

Description: An area of ridge and furrow, approximately 50m northwest-southeast by 30m. The ridges run

northwest-southeast and when recorded in December 2006 were overgrown with bracken. J.J.

Hall, Trysor, 2 January 2007

SMR PRN:

Relationships: Photographs:

> GC2006-118 22/12/2006 Cultivation ridges, looking

> > north-west

NPRN: 289129

CAETY TRAYLOW, LINEAR EARTHWORK TRACKWAY?

SO1913756288 Grid reference taken at point along linear site **Altitude:** 410

Period: Post Medieval? **Broadclass: Transport**

Form: Earthwork **Condition:**

Site Status:

Description: A gully or narrow trackway on the same alignment, and continuing on from, bank NPRN

289126. It was 1m wide and up to 1m deep. In December 2006, vegetation cover was grass,

reeds and moss. J.J. Hall, Trysor, 2 January 2007

SMR PRN:

Relationships: Photographs:

> GC2006-119 22/12/2006 Trackway, looking north-east

NPRN: 289130

CAETY TRAYLOW, CULTIVATION **CULTIVATION RIDGE**

RIDGES I

NGR: SO1914656278 Grid reference taken at a central point within an extensive site Altitude: 430

Period: **Broadclass:** Post Medieval Agriculture and Subsistence

Condition: Form: Earthwork

Site Status:

Description: An area of ridge and furrow, aligned northeast-southwest. Vegetation cover in December 2006

was moss. J.J. Hall, Trysor, 2 January 2007

SMR PRN:

Relationships: Photographs:

> GC2006-120 22/12/2006 Cultivation ridges, looking west

GC2006-121 22/12/2006 Cultivation ridges, looking east

CWM Y BONT, BANK BA

BANK (EARTHWORK)

NGR: SO1948556909 Grid reference taken at point along linear site Altitude: 390

Period: Post Medieval? Broadclass: Monument <By Form>

Form: Earthwork Condition:

Site Status:

Description: An earthwork bank recorded for over 420m running roughly northeast-southwest on a

relatively steep northwest facing slop above Gilwern Brook. It was traced from SO1925656680 to SO1948556909. The feature was overgrown with heather when recorded in December

2006. J.J. Hall, Trysor, 2 January 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289132

CWM Y BONT, QUARRY I QUARRY

NGR: SO1958157085 Grid reference taken at centre of site Altitude: 370

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: A small quarry cut into a north facing slope above Gilwern Brook. The quarry was 10m by 5m

and up to 2m deep. When recorded in December 2006, it was grown over with grass and

heather. J.J. Hall, Trysor, 2 January 2007

SMR PRN:

Relationships: Photographs:

GC2006-123 22/12/2006 Quarry, looking northeast

NPRN: 289133

CWM Y BONT, QUARRY II QUARRY

NGR: SO1967257056 Grid reference taken at centre of site Altitude: 370

Period: Post Medieval? **Broadclass:** Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: A small quarry, 5m north northwest-south southeast by 4m, and up to 1.5m deep. When

recorded in December 2006 it was overgrown with short grass. J.J. Hall, Trysor, 2 January

2007

SMR PRN:

CWM Y BONT, TRACKWAY TRACKWAY

NGR: SO1969057057 Grid reference taken at point along linear site Altitude: 365

Period: Post Medieval Broadclass: Transport

Form: Earthwork Condition: C

Site Status:

Description: A trackway from quarry NPRN 289133, at SO1969057057 running to SO1971657027 where it

appeared to run into a natural gully downslope to the east. It was cut by a modern trackway close to the quarry. Vegetation cover in December 2006 was grass. J.J. Hall, Trysor, 2

January 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289135

CWM Y BONT, CULTIVATION RIDGES CULTIVATION RIDGE

NGR: SO1920356569 Grid reference taken at a central point within an extensive site Altitude: 400

Period: Post Medieval? Broadclass: Agriculture and Subsistence

Form: Earthwork Condition: C

Site Status:

Description: An area of ridge and furrow on the slopes above Cwm y Bont. The ridges were c. 1.5m wide

with 0.5m in between. J.J. Hall, Trysor, 2 January 2007

SMR PRN:

Relationships: Photographs:

GC2006-096 09/12/2006 Cultivation ridges, looking

northeast

GC2006-122 22/12/2006 Cultivation ridges, looking north

NPRN: 289136

CAETY TRAYLOW, TRACKWAY TRACKWAY

NGR: SO1942156495 Grid reference taken at point along linear site Altitude: 435

Period: Post Medieval? Broadclass: Transport

Form: Earthwork **Condition:** C

Site Status:

Description: A 40m section of trackway aligned approximately south southwest - north northeast. In

December 2006, the vegetation cover was heather and grass. J.J. Hall, Trysor, 2 January 2007

SMR PRN:

CAETY TRAYLOW, CULTIVATION CULTIVATION RIDGE

RIDGES III

NGR: SO1912456212 Grid reference taken at a central point within an extensive site Altitude: 422

Period: Post Medieval **Broadclass:** Agriculture and Subsistence

Form: Earthwork **Condition:** C

Site Status:

Description: An extensive area of ridge and furrow aligned northwest-southeast on a natural terrace. In

December 2006, the vegetation cover was grass and reeds. J.J. Hall, Trysor, 2 January 2007

SMR PRN:

Relationships: Photographs:

GC2007-105 01/03/2007 Cultivation, looking east GC2007-106 01/03/2007 Cultivation, looking southeast

NPRN: 289138

CWM CESTE, PIT PIT

NGR: SO1788655309 Grid reference taken at centre of site Altitude: 385

Period: Modern? Broadclass: Unassigned

Form: Earthwork **Condition:** B

Site Status:

Description: A rectangular, earth-cut pit, 3m east-west by 2m and 0.75m deep with spoil upcast to the north

and south. The pit lay alongside a small track, and was overgrown with grass and bracken

when recorded in December 2006. J.J. Hall, Trysor, 2 January 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289139

CWM CESTE, EARTHWORK I PLATFORM?

NGR: SO1792655317 Grid reference taken at centre of site Altitude: 385

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A levelled area on a gentle west facing slope. The feature measured 6m north - south by 5m

internally. The northern end was cut into the ground to a depth of 0.30m, with banks on the east and west side. In December 2006, the vegetation cover was bracken and grass. J.J. Hall,

Trysor, 2 January 2007

SMR PRN:

CWM CESTE, BANK II BA

BANK (EARTHWORK)

NGR: SO1794855422 Grid reference taken at point along linear site Altitude: 382

Period: Post Medieval? Broadclass: Monument < By Form>

Form: Earthwork Condition: V

Site Status:

Description: A denuded bank recorded as running from SO1793755483 to SO1796055366 with a ditch on

its western side. The bank was 2m wide and 0.40m increasing to 2.5m wide and 0.50m high as the bank ran southwards. Vegetation cover in December 2006 was grass and dead bracken.

J.J. Hall, Trysor, 2 January 2007

SMR PRN:

Relationships: Photographs:

GC2006-124 23/12/2006 Bank, looking north

NPRN: 289141

CWM CESTE, PLATFORM PLATFORM

NGR: SO1804155297 Grid reference taken at centre of site Altitude: 400

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A large platform, 20.5m east-west by 5m, cut deeply into a west facing slope. The apron

extended for 3m beyond the end of the platform. There was a drop in height of 0.25m of the platform at 7m from the cut end. A lter trackway cuts throughthe platform creating a 0.30m deep scar across the feature. Vegetation cover in December 2006 was grass and reeds. J.J.

Hall, Trysor, 2 January 2007

SMR PRN:

Relationships: Photographs:

GC2006-125 23/12/2006 Platform, looking west

NPRN: 289142

CWM CESTE, EARTHWORK II SHELTER?

NGR: SO1806255291 Grid reference taken at centre of site Altitude: 409

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** B

Site Status:

Description: An earthwork scoop, cut into a west facing slope, with spoil cast up to the north and south and

open to the west. The feature was 3.5m east - west and 3m wide with the spoil banks being a further 1m wide each. The scoop was thought to be related to the platform immediately below it, possibly some form of shelter. When the site was recorded in December 2006, the

vegetation cover was grass. J.J. Hall, Trysor, 2 January 2007

SMR PRN:

CWM CESTE, BANK I

BANK (EARTHWORK)

NGR: SO1806455279 Grid reference taken at point along linear site **Altitude:** 410

Post Medieval? **Broadclass:** Monument <By Form> Period:

Form: Earthwork **Condition:** V

Site Status:

Description: An earthwork bank, 1.5m wide and 0.50m high running intermittantly from SO1808055282 to

> SO1799155297. A spur ran off from the bank at SO1805455280 to SO1805255308. Vegetation cover in December 2006 was grass, reeds and dead bracken. J.J. Hall, Trysor, 2

January 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289144

CWM CESTE, CULTIVATION RIDGES **CULTIVATION RIDGE**

SO1805055360 Grid reference taken at a central point within an extensive site NGR: **Altitude:** 400

Period: Post Medieval **Broadclass:** Agriculture and Subsistence

Form: Earthwork **Condition:** C

Site Status:

Description: An extensive area of ridge and furrow aligned north-south, parallel to the contours. Vegetation

cover in December 2006 was grass and reeds. J.J. Hall, Trysor, 2 January 2007

SMR PRN:

Relationships: Photographs:

> GC2006-097 09/12/2006 Cultivation ridges, looking east GC2006-100 09/12/2006 Cultivation ridges, looking east

NPRN: 289145

LLANFIHANGEL HILL, QUARRY **QUARRY**

SO1855655648 Grid reference taken at centre of site NGR: **Altitude:** 465

Period: Post Medieval **Broadclass:** Industrial

Form: **Condition:** Earthwork

Site Status:

Description: A quarry, 20m north northwest-south southeast by 10m and up to 2m deep. When recorded in

December 2006, it was overgrown with short grass. J.J. Hall, Trysor, 2 January 2007

SMR PRN:

LLANFIHANGEL HILL, TRACKWAY TRACKWAY

NGR: SO1872055620 Grid reference taken at point along linear site Altitude: 485

Period: Post Medieval Broadclass: Transport

Form: Earthwork Condition: C

Site Status:

Description: A well defined trackway running approximately northwest-southeast on the western flank of

Llanfihangel Hill. The trackway ran past quarry NPRN 289145 to SO1880455532 where it met the ridge-top trackway shown on modern Ordnance Survey maps. It was approximately 2m wide and covered in short grass when recorded in December 2006. J.J. Hall, Trysor, 2

January 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289147

LLANFIHANGEL HILL, MOUND I ROUND BARROW?

NGR: SO1895955593 Grid reference taken at centre of site Altitude: 508

Period: Bronze Age? **Broadclass:** Religious, Ritual and Funerary

Form: Earthwork **Condition:** C

Site Status:

Description: A small earth mound, 2m in diameter and 0.5m high, to the west of round barrow NPRN

306098. When the feature was recorded in December 2006, it was covered with heather. J.J.

Hall, Trysor, 2 January 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289148

LLANFIHANGEL HILL, MOUND II ROUND BARROW?

NGR: SO1897055586 Grid reference taken at centre of site Altitude: 508

Period: Bronze Age? Broadclass: Religious, Ritual and Funerary

Form: Earthwork Condition: C

Site Status:

Description: A small earth mound, 2m in diameter and 0.4m high, to the southwest of round barrow NPRN

306098. When the feature was recorded in December 2006, it was covered with heather. J.J.

Hall, Trysor, 2 January 2007

SMR PRN:

CWNC BANK, POND POND

NGR: SO1859754025 Grid reference taken at centre of site Altitude: 395

Period: Post Medieval Broadclass: Water Supply and Drainage

Form: Earthwork Condition: A

Site Status:

Description: A pond, 27m north-south by 10m, shown on all editions of the Ordnance Survey maps since

1891. The southern end of the pond was dammed by an earth and stone bank, 1.5m wide and 0.60m high. When the feature was recorded in December 2006, it was still in use and held

water. J.J. Hall, Trysor, 2 January 2007

SMR PRN:

Relationships: Photographs:

GC2006-128 23/12/2006 Pond, looking south

NPRN: 289150

CNWCH, SPOIL TIP SPOIL TIP

NGR: SO1870453616 Grid reference taken at centre of site Altitude: 410

Period: Modern **Broadclass:** Monument <By Form>

Form: Earthwork Condition: B

Site Status:

Description: An area of rubble and stone arranged in linear heaps. It appears to be material dumped there

from elsewhere. The vegetation cover when recorded in December 2006 was bracken. J.J.

Hall, Trysor, 2 January 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289151

CNWCH, QUARRY V QUARRY

NGR: SO1852153450 Grid reference taken at centre of site Altitude: 360

Period: Post Medieval?;Modern? **Broadclass:** Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: A gravel and/or stone quarry. The quarry was 20m by 10m and up to 10m deep. J.J. Hall,

Trysor, 2 January 2006

SMR PRN:

CNWCH, QUARRY IV

QUARRY

NGR: SO1845853609 Grid reference taken at centre of site Altitude: 365

Period: Post Medieval **Broadclass:** Industrial

Form: Earthwork Condition: B

Site Status:

Description: A small quarry shown on all editions of the Ordnance Survey maps since 1891. When

recorded in December 2006, it was seen as a small quarry 10m in diameter and up to 4m deep.

J.J. Hall, Trysor, 2 January 2006

SMR PRN: CPAT 22506

Relationships: Photographs:

NPRN: 289153

CNWCH, QUARRY III QUARRY

NGR: SO1844153787 Grid reference taken at centre of site Altitude: 380

Period: Post Medieval **Broadclass:** Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: A small quarry shown on all editions of the Ordnance Survey maps since 1891. When

recorded in December 2006, it was seen as a small quarry 12m by 6m and 2m deep. J.J. Hall,

Trysor, 2 January 2006

SMR PRN: CPAT 22505

Relationships: Photographs:

NPRN: 289154

CNWCH, QUARRY II QUARRY

NGR: SO1841153831 Grid reference taken at centre of site Altitude: 381

Period: Post Medieval?:Modern? **Broadclass:** Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: A small quarry 6m by 3m, and up to 1m deep. When recorded in December 2006, the

vegetation cover was grass and gorse. J.J. Hall, Trysor, 2 January 2006

SMR PRN:

CNWCH, QUARRY I QUARRY

NGR: SO1833253928 Grid reference taken at centre of site Altitude: 378

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork Condition: B

Site Status:

Description: An area of small quarry pits covering 30m by 30m and up to 1m deep. When recorded in

December 2006, the vegetation cover was grass. J.J. Hall, Trysor, 2 January 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289156

CWM CESTE, QUARRY II QUARRY

NGR: SO1826253984 Grid reference taken at centre of site Altitude: 375

Period: Post Medieval?; Modern? Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A small quarry, 8m by 8m, and up to 4m deep. When recorded in December 2006, the

vegetation cover was grass. J.J. Hall, Trysor, 2 January 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289157

CWM CESTE, QUARRY IV QUARRY

NGR: SO1808754288 Grid reference taken at centre of site Altitude: 378

Period: Post Medieval Broadclass: Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: An area of small quarry pits adjacent to the common boundary. When recorded in December

2006, the vegetation cover was grass. J.J. Hall, Trysor, 2 January 2006

SMR PRN:

CWM CESTE, QUARRY III QUARRY

NGR: SO1809255157 Grid reference taken at centre of site Altitude: 420

Period: Post Medieval Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A small quarry, 7m by 7m, and up to 2m deep, adjacent to the common boundary. When

recorded in December 2006, the vegetation cover was grass. J.J. Hall, Trysor, 2 January 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289159

CWM CESTE, QUARRY I QUARRY

NGR: SO1808055256 Grid reference taken at centre of site Altitude: 413

Period: Post Medieval Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A small quarry, 10m by 10m, and up to 3m deep, adjacent to the common boundary. When

recorded in December 2006, the vegetation cover was grass. J.J. Hall, Trysor, 2 January 2006

SMR PRN:

Relationships: Photographs:

NPRN: 289160

GILWERN BROOK, BANK BANK (EARTHWORK)

NGR: SO1830756140 Grid reference taken at point along linear site Altitude: 360

Period: Post Medieval? Broadclass: Monument < By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: The remains of an earthwork bank on the northern side of the Gilwern Brook. The section of

bank was about 20m long and 0.40m high. Vegetation cover in December 2006 was grass.

J.J. Hall, Trysor, 4 January 2006

SMR PRN:

GILWERN BROOK, TRACKWAY I TRACKWAY

NGR: SO1833956123 Grid reference taken at point along linear site Altitude: 360

Period: Post Medieval? Broadclass: Transport

Form: Earthwork Condition: C

Site Status:

Description: A short section of trackway about 30m long, running roughly east from the Gilwern Brook.

When recorded in December 2006, the vegetation cover was grass and heather. J.J. Hall,

Trysor, 4 January 2006

SMR PRN:

Relationships: Photographs:

GC2006-110 22/12/2006 Trackway, looking east

NPRN: 289162

BRYNTEGAN, QUARRY II QUARRY

NGR: SO2014253228 Grid reference taken at centre of site Altitude: 378

Period: Post Medieval **Broadclass:** Industrial

Form: Earthwork Condition: C

Site Status:

Description: A small quarry, 10m northwest-southeast x 8m and up to 3m deep, cut into hillslope. No stone

visible. Vegetation cover in February 2007 was short-cropped grass and gorse. R.P.Sambrook,

Trysor, 27 February 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289163

BRYNTEGAN, TRACKWAY TRACKWAY

NGR: SO2011953233 Grid reference taken at point along linear site Altitude: 400

Period: Post Medieval Broadclass: Transport

Form: Earthwork **Condition:** C

Site Status:

Description: A trackway c.1.5m wide, running diagonally up a steep slope north-northwest to

south-southeast. It has a slight bank or revetment on its downslope side. It was not shown on late 19th century or 20th century maps. The trackway peters out in an area of quarrying and is presumably associated with it. Vegetation cover in February 2007 was dead bracken and

gorse. R.P.Sambrook, Trysor, 27 February 2007

SMR PRN:

BRYNTEGAN, QUARRY III **QUARRY**

NGR: SO2009853252 Grid reference taken at centre of site Altitude: 410

Broadclass: Period: Post Medieval Industrial

Form: **Earthwork** Condition:

Site Status:

Description: Linear quarry workings extending over an area of roughly 30m long east southeast-west

northwest. The pits and scoops are up to 1m deep but largely obscured by gorse.

R.P.Sambrook, Trysor, 27 February 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289165

BRYNTEGAN, MOUND I POTATO CLAMP?

NGR: SO2011653252 Grid reference taken at centre of site **Altitude:** 405

Period: Post Medieval **Broadclass:** Agriculture and Subsistence

Earthwork **Condition:** Form:

Site Status:

Description: An earth mound, 6m south southeast-north northwest by 1.5m wide, with a slight ditch to either

> side along the long axis. The mound is 0..3m high and thought to possibly be a potato clamp associated with nearby Bryntegan. Vegetation cover in February 2007 was dead bracken.

R.P.Sambrook, Trysor, 27 February 2007

SMR PRN:

Relationships: Photographs:

> GC2007-001 15/02/2007 Potato clamp, looking northeast

NPRN: 289166

BRYNTEGAN, PLATFORM II **PLATFORM**

NGR: SO2019653499 Grid reference taken at centre of site Altitude: 440

Period: Post Medieval? **Broadclass:** Monument <By Form>

Earthwork Condition: Form: \mathbf{C}

Site Status:

Description: A rectangular platform measuring 19m long west northwest-east southeast, by 6.25m wide.

> The level area of the platform measures 12m x 6.25m. There is some stone scattered on the platform. There is also the possible remains of a revetted edge at its southeastern end. At the same end there is a narrow gully in the centre of the edge of the platform which may have been deliberately created for drainage purposes. A smaller platform (NPRN 289167) sits immediately upslope to the west-northwest, which appears to have been related to this structure, possibly even an integral part of it. There is evidence of ridge and furrow close to the platform, particularly to the north, but any relationship is conjectural. Vegetation cover in

February 2007 was grass and bracken. R.P.Sambrook, Trysor, 27 February 2007

SMR PRN:

Relationships: Photographs:

Associated with 289167 GC2007-002 15/02/2007 Platform, looking Associated with 289168

west-southwest

GC2007-003 15/02/2007 Platform, looking

west-northwest

438

NPRN: 289167

BRYNTEGAN, PLATFORM I PLATFORM

NGR: SO2018653506 Grid reference taken at centre of site Altitude: 442

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: A small platform directly above, and possible integral to platform NPRN 289166, measuring

5m wide south southwest - north northeast by 2m deep. There is a small amount of stone scattered around, but no structural evidence on the platform itself. Vegetation cover in February 2007 was short-cropped grass and dead bracken. R.P.Sambrook, Trysor, 27

February 2007

SMR PRN:

Relationships: Photographs:

Associated with 289166 GC2007-004 15/02/2007 Platform, looking southeast

NPRN: 289168

BRYNTEGAN, MOUND II MOUND

NGR: SO2019053512 Grid reference taken at centre of site Altitude: 442

Period: Unknown **Broadclass:** Monument <By Form>

Form: Earthwork Condition: U

Site Status:

Description: An earth mound adjacent to the northeast side of platform NPRN 289166. The mound

measured 6m east southeast-west northwest by 2.5m and stood up to 0.5m high. Vegetation cover when the feature was recorded in February 2007 was dead bracken. J.J.Hall, Trysor, 13

March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289166 GC2007-005 15/02/2007 Mound, looking southwest

NPRN: 289169

BRYNTEGAN, BANK BANK (EARTHWORK)

NGR: SO2020953505 Grid reference taken at point along linear site Altitude:

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** V

Site Status:

Description: A faint earthwork feature consisting of a 1m wide bank and 1m wide gully on its downslope,

southern side running from the corner of platform NPRN 289166 to SO2022653509. When the site was recorded in February 2007, the vegetation cover was dead bracken. J.J.Hall, Trysor,

13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-006 15/02/2007 Bank, looking east

BRYNTEGAN, QUARRY IV QUARRY

NGR: SO2025953519 Grid reference taken at centre of site Altitude: 430

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A small quarry pit, 5m in diameter, and up to 2m deep. When recorded in February 2007, the

vegetation cover was grass and gorse. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289171

BRYNTEGAN, QUARRY V QUARRY

NGR: SO2025553531 Grid reference taken at centre of site Altitude: 431

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A small quarry pit, 8m north-south by 5m. When recorded in February 2007, the vegetation

cover was grass and dead bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289172

BRYNTEGAN, QUARRY I QUARRY?

NGR: SO2024653544 Grid reference taken at centre of site Altitude: 433

Period: Post Medieval? **Broadclass:** Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: A small depression, probably a quarry pit, 4m in diameter, but only 0.5m deep. When recorded

in February 2007, the vegetation cover was dead bracken. J.J.Hall, Trysor, $13\ \text{March}\ 2007$

SMR PRN:

LLANHAYLOW, CULTIVATION RIDGES CULTIVATION RIDGE

NGR: SO2026053670 Grid reference taken at a central point within an extensive site Altitude: 430

Period: Post Medieval? Broadclass: Agriculture and Subsistence

Form: Earthwork **Condition:** C

Site Status:

Description: An area of ridge and furrow covering an area at least 70m by 60m adjacent to the common

boundary. The ridges are aligned southwest-northeast. The distance ridge to ridge was 2.75m and the overall height 0.20m. When the feature was recorded in February 2007, the vegetation

cover was dead bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289174

LLANHAYLOW, QUARRY II QUARRY

NGR: SO2035753911 Grid reference taken at centre of site Altitude: 360

Period: Post Medieval Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A quarry is shown at this point on 1st and 2nd edition Ordnance Survey maps of 1891 and

1905 where it is named as "Gravel Pit". The quarry was cut into an east northeast facing slope and measured 10m west southwest-east northeast by 5m and up to 3m deep. When the site was recorded in February 2007, the vegetation cover was grass and dead bracken.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289175

COLVA HILL, FIELD FIELD

NGR: SO2010154075 Grid reference taken at centre of site Altitude: 410

Period: Post Medieval **Broadclass:** Agriculture and Subsistence

Form: Topography Condition: V

Site Status:

Description: A former field, at least 36m northeast-southwest by 26m, defined by an earthwork bank, 2m

wide and up to 0.75m high in places. The bank ran from SO2011954089 to SO2007954072 where it turned to run southeastwards along the stream to SO2010454064. When recorded in February 2007, the vegetation cover was dead bracken and grass. J.J.Hall, Trysor, 13 March

2007

SMR PRN:

Relationships: Photographs:

GC2007-007 15/02/2007 Bank, looking northwest GC2007-008 15/02/2007 Bank, looking southwest GC2007-010 15/02/2007 Bank, looking southeast

COLVA HILL, QUARRY II QUARRY

NGR: SO1999354080 Grid reference taken at centre of site Altitude: 410

Period: Post Medieval? **Broadclass:** Industrial

Form: Earthwork Condition: C

Site Status:

Description: An area of quarrying, consisting of at least three separate pits in an area 25m east-west by 12m.

Stone was seen outcropping in parts and the feature appears to be later than platform NPRN 289178. When recorded in February 2007, the vegetation cover was dead bracken and grass.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289177

COLVA HILL, PLATFORM V PLATFORM

NGR: SO2004954066 Grid reference taken at centre of site Altitude: 390

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: A large earthwork platform aligned west northwest-east southeast. The feature was 6m wide

and 19.5m long overall. The cut into the slope at the west northwest end was 1m deep and 2m long, the platform itself was 15.5m with an overall drop of 1m along its length and the apron was 2m wide and 0.5m high. When the feature was recorded in February 2007 the vegetation

cover was dead bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-009 15/02/2007 Platform, looking south GC2007-011 15/02/2007 Platform, looking east

NPRN: 289178

COLVA HILL, PLATFORM IV PLATFORM

NGR: SO2003454074 Grid reference taken at centre of site Altitude: 400

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A small platform or scoop just above and west of platform NPRN 298177. The roughly circular

scoop has a gap or entrance on the northeast side flanked by two short banks running into the slopes. Internally it measured 2m in diameter, externally it measured 4m. Vegetation cover in

February 2007 was dead bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

COLVA HILL, BANK BANK (EARTHWORK)

NGR: SO2002554084 Grid reference taken at point along linear site Altitude: 402

Period: Post Medieval? Broadclass: Monument < By Form>

Form: Earthwork Condition: B

Site Status:

Description: An earthen bank running from SO2001654067 to SO2006354112. Vegetation cover when the

feature was recorded in February 2007 was dead bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289180

COLVA HILL, PLATFORM II PLATFORM

NGR: SO1999954093 Grid reference taken at centre of site Altitude: 410

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: An earthwork platform 6m south southwest-north northeast by 2.5m. The south southwest end

may have been interrupted by nearby quarrying and the other end clipped by a trackway. When the feature was recorded in February 2007, the vegetation cover was dead bracken.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289181

COLVA HILL, QUARRY I QUARRY

NGR: SO1997854037 Grid reference taken at centre of site Altitude: 410

Period: Post Medieval **Broadclass:** Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: A quarry shown on the 1st edition Ordnance Survey map of 1891 where it was named as "Old

Quarry". The quarry when recorded in February 2007 covered an area 20m in diameter.

Vegetation cover was grass and dead bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

COLVA HILL, PLATFORM VII PLATFORM

NGR: SO2017154290 Grid reference taken at centre of site Altitude: 410

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: An earthwork platform, 14m overall northwest-southeast by 5.5m wide. The northwest end

was cut into the slope for 2m with a depth of 2m. The level area of the platform was 10m long and the apron was another 2m. There was a slight notch on the apron bank. The vegetation cover was grass and dead bracken when the site was visited in February 2007. J.J.Hall,

Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-012 15/02/2007 Platform, looking east-northeast GC2007-013 15/02/2007 Platform, looking southeast

NPRN: 289183

GLADESTRY BROOK, BANK I BANK (EARTHWORK)

NGR: SO2031454418 Grid reference taken at point along linear site Altitude: 380

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: V

Site Status:

Description: An earthwork bank running from SO2034454379 to SO2026854490. It was 2m wide and

0.75m high. When the feature was recorded in February 2007 it was covered with dead

bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-014 15/02/2007 Bank, looking north-northwest

GC2007-015 15/02/2007 Bank, looking west

NPRN: 289184

GLADESTRY BROOK, BANK II BANK (EARTHWORK)

NGR: SO2028454520 Grid reference taken at point along linear site Altitude: 390

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** V

Site Status:

Description: An earthwork bank running from SO2031554508 to SO2022254563. It was 1.5m wide and

0.30m high. When the feature was recorded in February 2007 it was covered with dead

bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-016 15/02/2007 Bank, looking northwest

GLADESTRY BROOK, BANK III

BANK (EARTHWORK)

NGR: SO2022054574 Grid reference taken at point along linear site Altitude: 400

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: V

Site Status:

Description: An earthwork bank running from SO2019954596 to SO2020654550. It was 1.5m wide and

0.30m high. When the feature was recorded in February 2007 it was covered with dead

bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289186

COLVA HILL, STONE PILE SHOOTING STAND?

NGR: SO1996455224 Grid reference taken at centre of site Altitude: 490

Period: Modern Broadclass: Recreational

Form: Other Structure **Condition:** C

Site Status:

Description: A pile of stones with wood debris around it. It was thought that this could be related to the

shooting butts in the area. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289187

COLVA HILL, SHOOTING STAND I SHOOTING STAND

NGR: SO1967055105 Grid reference taken at centre of site Altitude: 517

Period: Modern Broadclass: Recreational

Form: Earthwork **Condition:** C

Site Status:

Description: The remains of a shooting stand, one of four arranged around a pond on the top of Colva Hill.

The feature consisted of an earth mound, 4m wide and 0.2m high with a level top. Fragments of wood were scattered over the mound. When the site was recorded in February 2007 the

vegetation cover was grass and heather. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

COLVA HILL, SHOOTING STAND II SHOOTING STAND

NGR: SO1986255074 Grid reference taken at centre of site Altitude: 518

Period: Modern Broadclass: Recreational

Form: Earthwork Condition: C

Site Status:

Description: The remains of a shooting stand, one of four arranged around a pond on the top of Colva Hill.

The feature consisted of an 4m diameter ring of earth which stood 0.15m high. Fragments of wood were scattered over the mound and a metal spike stood upright. When the site was recorded in February 2007 the vegetation cover was grass and reeds. J.J.Hall, Trysor, 13

March 2007

SMR PRN:

Relationships: Photographs:

GC2007-017 15/02/2007 Shooting stand, looking west

NPRN: 289189

COLVA HILL, SHOOTING STAND III SHOOTING STAND

NGR: SO1966755048 Grid reference taken at centre of site Altitude: 519

Period: Modern Broadclass: Recreational

Form: Earthwork Condition: C

Site Status:

Description: The remains of a shooting stand, one of four arranged around a pond on the top of Colva Hill.

The feature consisted of an earth mound, 4m wide and 0.15m high with a level top. Fragments of wood were scattered over the mound. When the site was recorded in February 2007 the

vegetation cover was grass and heather. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-018 15/02/2007 Shooting stand, looking

northwest

NPRN: 289190

COLVA HILL, SHOOTING STAND IV SHOOTING STAND

NGR: SO1962455076 Grid reference taken at centre of site Altitude: 518

Period: Modern Broadclass: Recreational

Form: Earthwork **Condition:** C

Site Status:

Description: The remains of a shooting stand, one of four arranged around a pond on the top of Colva Hill.

The feature consisted of an earth mound, 4m wide with a level top. Fragments of wood were scattered over the mound. When the site was recorded in February 2007 the vegetation cover

was grass and heather. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

COLVA, QUARRY IV QUARRY

NGR: SO1978053131 Grid reference taken at centre of site Altitude: 413

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A series of small quarry pits, extending over an area 30m east-west by 10m. The quarry pits

were not shown on any edition of the Ordnance Survey maps. When the quarry pits were recorded in February 2007, the vegetation cover was gorse and grass which covered most of

the surface area. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289192

COLVA, QUARRY I QUARRY

NGR: SO2004153199 Grid reference taken at centre of site Altitude: 390

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A quarry pit, 10m in diameter, not shown on any edition of the Ordnance Survey maps. When

recorded in February 2007, the vegetation cover was bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289193

COLVA FARM, QUARRY QUARRY

NGR: SO2010653205 Grid reference taken at centre of site Altitude: 388

Period: Post Medieval **Broadclass:** Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: A quarry cut into a south facing rock face and measuring 20m in diameter. It is shown on the

1st Ordnance Survey map of 1891 and named as "Quarry". By the time of the 2nd edition map

of 1905 it is named as "Old Quarry". J.J. Hall, Trysor, 13 March 2007

SMR PRN:

CWM SHENKIN, PLATFORM PLATFORM

NGR: SO1944753622 Grid reference taken at centre of site Altitude: 425

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: An earthwork platform, the level area of which measured 10m southeast - northwest by 6m.

When the feature was visited in February 2007, the vegetation cover was dead bracken.

J.J.Hall, Trysor, 13 March 2007

SMR PRN: CPAT 70049

Relationships: Photographs:

GC2007-023 15/02/2007 Platform, looking northwest

NPRN: 289195

CWM SHENKIN, EARTHWORK QUARRY?;PLATFORM?

NGR: SO1951053700 Grid reference taken at centre of site Altitude: 431

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: An earthwork feature 13m southeast- northwest by 8m,, cut into the southeast facing slope near

the former Cwm Shenkin farmstead. Although the feature had previously described as a platform, the feature seemed heavily disturbed and appeared to have been used as a quarry.

J.J.Hall, Trysor, 13 March 2007

SMR PRN: CPAT 70050

Relationships: Photographs:

GC2007-022 15/02/2007 Quarry, looking north

NPRN: 289196

CWM SHENKIN, ENCLOSURE II ENCLOSURE

NGR: SO1947253549 Grid reference taken at centre of site Altitude: 412

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork Condition: D

Site Status:

Description: A former enclosure on the common, enclosing an area of denuded ridge and furrow. The bank

defining the enclosure was very denuded and could only be seen clearly in certain lighting conditions. Vegetation cover in February 2007 was dead bracken and grass. J.J.Hall, Trysor,

13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-021 15/02/2007 Enclosure, looking southeast

CWM SHENKIN, QUARRY QUARRY

NGR: SO1939053623 Grid reference taken at centre of site Altitude: 437

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: Alongside a modern trackway was an area of small quarry pits covering 30m north-south by

10m. When the features were recorded in February 2007, the vegetation cover was grass.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289198

CWM SHENKIN, ENCLOSURE I ENCLOSURE

NGR: SO1938053530 Grid reference taken at centre of site Altitude: 424

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: D

Site Status:

Description: A former roughly square enclosure on the common, measuring 32m. When the feature was

recorded in February 2007, the vegetation was dead bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-019 15/02/2007 Enclosure, looking southeast GC2007-020 15/02/2007 Enclosure, looking southwest

NPRN: 289199

CWM SHENKIN, CULTIVATION RIDGES II CULTIVATION RIDGE

NGR: SO1976053470 Grid reference taken at a central point within an extensive site Altitude: 425

Period: Post Medieval? Broadclass: Agriculture and Subsistence

Form: Earthwork **Condition:** C

Site Status:

Description: An area of ridge and furrow on what is now common land close to the former farmstaed at

Cwm Shenkin. Vegetation cover in February 2007 was heather and bracken. J.J.Hall, Trysor,

13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-025 21/02/2007 Cultivation ridges, looking

southeast

CWM SHENKIN, CULTIVATION RIDGES I CULTIVATION RIDGE

NGR: SO1935053440 Grid reference taken at a central point within an extensive sitee Altitude: 422

Period: Post Medieval? Broadclass: Agriculture and Subsistence

Form: Earthwork Condition: C

Site Status:

Description: An area of ridge and furrow seen on aerial photgraph RAF 106G UK 1190 4133 and identified

on the ground in February 2007. Vegetation cover was heather, dead bracken and grass.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-026 21/02/2007 Cultivation ridges, looking

southwest

NPRN: 289201

COLVA, QUARRY II QUARRY

NGR: SO1974353140 Grid reference taken at centre of site Altitude: 420

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: A small quarry 10m south southwest-north northeast by 5m and cut up to 1m deep into a south

facing slope. Some stone was visible but the feature was largely grassed over when visited in

February 2007. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289202

CWM SHENKIN, STONE SCATTER STONE SPREAD

NGR: SO1954053576 Grid reference taken at centre of site Altitude: 410

Period: Post Medieval?; Modern? **Broadclass:** Unassigned

Form: Earthwork Condition: D

Site Status:

Description: A stone scatter, 10m east-west by 8m, with a pit at its eastern edge. A small tree was growing

through part of the stone scatter and much of the rest was partially grassed over when recorded

in February 2007. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-024 21/02/2007 Stone pile, looking

north-northeast

FFYNNONAU, QUARRY QUARRY

NGR: SO1926553635 Grid reference taken at centre of site Altitude: 452

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A small quarry, 7m north northeast-south southwest by 5m and up to 0.75m deep, cut into the

western edge of a rock outcrop. Spoil mound to its west. The quarry is not shown on any edition of Ordnance Survey maps. When the site was recorded in February 2007, the

vegetation cover was grass and dead bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289204

UPPER YSGAWEN, QUARRY V QUARRY

NGR: SO1944153894 Grid reference taken at centre of site Altitude: 430

Period: Post Medieval Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A quarry, 25m north northeast-south southwest by 15m and up to 14m deep. Stone

outcropping in the quarry sides was visible and spoil tips on the quarry floor, all of which were covered by grass and dead bracken. The boundary of the common, 20m to the west of the quarry, was stone built and the quarry was probably dug to supply stone for this. J.J.Hall,

Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-027 21/02/2007 Quarry, looking west

NPRN: 289205

COLVA HILL, PLATFORM III PLATFORM

NGR: SO1942254318 Grid reference taken at centre of site Altitude: 456

Period: Post Medieval? Broadclass: Monument < By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A large earthwork platform, one of a pair, cut into a south facing slope. The level area of the

platform was 14m northeast-southwest by 5m. The cut into the slope at the northeast end was 2.5m deep and 4m wide. The apron at the southwest end was 2m high and 7m wide. A bank, presumably created from the spoil, was on the east, west and south sides. NPRN 289206, a smaller platform, lay to its east. When recorded in February 2007 J.J.Hall, Trysor, 13 March

2007

SMR PRN:

Relationships: Photographs:

Associated with 289206 GC2007-028 21/02/2007 Platform, looking north

GC2007-029 21/02/2007 Platform, looking southwest

COLVA HILL, PLATFORM VI PLATFORM

NGR: SO1943554312 Grid reference taken at centre of site Altitude: 456

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: An earthwork platform, one of a pair, cut into a south facing slope. The level area of the

platform was 9.25m northeast-southwest by 4.5m. The cut into the slope at the northeast end was 1.5m deep and 3m wide. The apron at the southwest end was 1m high and 5m wide. NPRN 289205, a larger platform, lay to its west. When recorded in February 2007, the

vegetation cover was dead bracken and grass. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289205 GC2007-030 21/02/2007 Platform, looking southwest

NPRN: 289207

COLVA, QUARRY III QUARRY

NGR: SO1999853314 Grid reference taken at centre of site Altitude: 440

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A small quarry pit, 4m in diameter and up to 1m deep. It was overgrown with grass and dead

bracken when recorded in February 2007. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289208

COLVA, PLATFORM PLATFORM?

NGR: SO1999353271 Grid reference taken at centre of site Altitude: 430

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: D

Site Status:

Description: A shallow, negative earthwork 11m in length east southeast-west northwest. At its west

northwest end it was terraced into the slope for 2m but there was no obvious positive feature at the other end. The site was covered with grass and gorse when recorded as part of Upland

Survey work in February 2007. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-053 24/02/2007 Platform, looking east-southeast

CWM GRIFFIN, ENCLOSURE II ENCLOSURE

NGR: SO1905254971 Grid reference taken at centre of site Altitude: 478

Period: Medieval?; Post Medieval? **Broadclass:** Monument < By Form>

Form: Earthwork Condition: B

Site Status:

Description: A sub circular enclosure, 29m northeast-southwest by 26m, defined by a bank between 0.50m and 0.80m high and up to 1.5m wide at its base. Entrances into the enclosure existed in its northeast, south and west sides. These were c.2m wide although the one in the south was harder to measure as the bank to the east of it was denuded. Two banks, NPRNs 289210 and 289211 ran away from the enclosure to the east southeast and roughly north respectively.

harder to measure as the bank to the east of it was denuded. Two banks, NPRNs 289210 and 289211 ran away from the enclosure to the east southeast and roughly north respectively, neither of them touching the enclosure itself but starting 2-3m away. Inside the enclosure was a feature NPRN 289345. When the enclosure was recorded in February 2007, it was very overgrown with heather, and it was not possible to discern if there were any other internal

features.

The date and function of the enclosure is unknown. It would appear to be a form of animal fold, and two short antennae banks that run northwards and eastwards from the main bank would perhaps suggest that it is associated with stock management. However, the possible hut or hut circle within its banks may indicate a settlement site.

It may be associated with possible longhouse NPRN 289212 and an area of cultivation NPRN

289213 to the west of it.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289210 GC2007-057 24/02/2007 Enclosure, looking south Associated with 289211 GC2007-058 24/02/2007 Enclosure bank, looking

Associated with 289345 northwest

NPRN: 289210

CWM GRIFFIN, BANK IV BANK (EARTHWORK)

NGR: SO1908154970 Grid reference taken at point along linear site Altitude: 479

Period: Medieval?;Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** B

Site Status:

Description: One of two banks running off from enclosure NPRN 289209, the other bank being NPRN

289211. This bank ran away from the enclosure at SO1907154974 southeastwards to SO1909454965. It does not join onto the enclosure, there being a gap of 2-3m between them. The bank was up to 2.3m wide at its base and about 1m high. When recorded in February

2007, it was covered in heather. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289209 GC2007-060 24/02/2007 Bank, looking east

CWM GRIFFIN, BANK III

BANK (EARTHWORK)

NGR: SO1905755014 Grid reference taken at point along linear site Altitude: 482

Period: Medieval?; Post Medieval? **Broadclass:** Monument < By Form>

Form: Earthwork Condition: B

Site Status:

Description: One of two banks running off from enclosure NPRN 289209, the other bank being NPRN

289210. This bank ran away from the enclosure at SO1905954991 roughly northwards to SO1905755020. It does not join onto the enclosure, there being a gap of 2-3m between them. The bank was up to 2.5m wide at its base and about 1m high. When recorded in February

2007, it was covered in heather. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289209 GC2007-059 24/02/2007 Bank, looking north

NPRN: 289212

CWM GRIFFIN, LONGHOUSE LONGHOUSE

NGR: SO1903555114 Grid reference taken at centre of site Altitude: 477

Period: Medieval?; Post Medieval? **Broadclass:** Domestic

Form: Earthwork Condition: C

Site Status:

Description: A rectangular earthwork structure thought to be the remains of a longhouse on a terrace on the

eastern side of Cwm Griffin. It was 16m externally, aligned south southwest - north northeast, by 6.5m, and 11m by 3m internally. The walls were earth banks, 1.5m wide at the base and 0.40m wide. The slope fell by 0.50m along the length of the feature. Possible entrances, 0.75m wide were seen in roughly the centre of the long walls. When recorded in February 2007, it

was overgrown with heather and moss. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-054 24/02/2007 Longhouse, looking

south-southwest

GC2007-055 24/02/2007 Longhouse, looking west

NPRN: 289213

CWM GRIFFIN, CULTIVATION RIDGES I LAZY BEDS?

NGR: SO1897255004 Grid reference taken at centre of site Altitude: 461

Period: Post Medieval? **Broadclass:** Agriculture and Subsistence

Form: Earthwork **Condition:** C

Site Status:

Description: An area of cultivation ridges, each ridge being 0.20m high and 1.2m wide. The whole area was

heavily overgrown with heather when visited during Uplands Survey work in 2007 so defining the extent of these ridges was difficult but it was at least 50m southwest-northeast by 20m.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

CWM GRIFFIN, CULTIVATION RIDGES II **CULTIVATION RIDGE**

NGR: SO1888354797 Grid reference taken at a central point within an extensive site **Altitude:** 450

Period: **Broadclass:** Agriculture and Subsistence Post Medieval?

Form: Earthwork Condition:

Site Status:

Description: An area of cultivation ridges. The whole area was heavily overgrown with heather when

visited during Uplands Survey work in 2007 so defining the extent of these ridges was difficult

but it they ran north-south. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

> GC2007-056 24/02/2007 Cultivation ridges, looking

> > south-southwest

NPRN: 289215

CWM GRIFFIN, EARTHWORK **EARTHWORK**

SO1924055067 Grid reference taken at centre of site **Altitude:** 496

Period: **Broadclass:** Unknown Monument < By Form>

Form: Earthwork **Condition:**

Site Status:

Description: A faint earthwork feature, 7m in diameter, consisting of a slight bank, less than 0.20m high,

forming a horseshoe-shape open to the southeast. Vegetation cover was heather in February

2007. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289216

LLANFIHANGEL HILL, BANK BANK (EARTHWORK)

NGR. SO1908155440 Grid reference taken at point along linear site 497 **Altitude:**

Period: Post Medieval? **Broadclass:** Monument < By Form>

Form: Earthwork **Condition:**

Site Status:

Description: A low earthwork bank 2m wide and 0.15m high running from SO1907555435 southwestwards

to SO1905255417 where it peters out. It is cut by a trackway at SO1905755424. Burnt

heather covered the feature when recorded in February 2007. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

ROUND BARROW? LLANFIHANGEL HILL, MOUND III

NGR: SO1894755554 Grid reference taken at centre of site Altitude: 508

Period: **Broadclass:** Religious, Ritual and Funerary Bronze Age?

Form: Earthwork **Condition:**

Site Status:

Description: A low earthwork mound 2m in diameter and 0.20m high. It lies approximately 45m to the

> southwest of round barrow NPRN 306098. Two other similar features, NPRNs 289147 and 289148 have been recorded in the area and although they were thought to be possible spoil tips from the excavation of the round barrow, the finding of this third mound further away changes that interpretation and makes it possible that they are Bronze Age funerary monumnets.

Vegetation cover in February 2007 was burnt heather. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289218

CAETY TRAYLOW, SHOOTING STAND III SHOOTING STAND

SO1927055926 Grid reference taken at centre of site Altitude: NGR: 475

Period: Modern **Broadclass:** Recreational

Form: Earthwork **Condition:**

Site Status:

Description: A large, earth shooting stand, measuring 8m by 4m, one of a line of shooting stands on Caety

> Traylow aligned southeast-northwest. It had been formed by pushing earth from the centre to the sides to form a central depression. Some fragments of timber were scattered around. Grass and reeds covered the feature when recorded in February 2007. J.J.Hall, Trysor, 13 March

2007

289222

289223

SMR PRN:

Associated with

Associated with

Photographs: Relationships:

GC2007-065 Associated with 289327 24/02/2007 Shooting stand, looking Associated with 289219 northwest Associated with 289220 Associated with 289221

289224 Associated with Associated with 289225

CAETY TRAYLOW, SHOOTING STAND IV SHOOTING STAND

NGR: SO1930155896 Grid reference taken at centre of site Altitude: 490

Period: Modern Broadclass: Recreational

Form: Earthwork **Condition:** C

Site Status:

Description: One of a line of shooting stands running northwest to southeast on Caety Traylow. An

artificial mound, 6m long and 4m wide and 0.3m deep with a central hollow within it. It was overgrown with reeds and grass when recorded in February 2007. J.J.Hall, Trysor, 13 March

2007

289221

SMR PRN:

Associated with

Relationships: Photographs:

Associated with 289327 GC2007-064 24/02/2007 Shooting stand, looking Associated with 289218 northwest 289220

Associated with 289222 Associated with 289223 Associated with 289224 Associated with 289225

NPRN: 289220

CAETY TRAYLOW, SHOOTING STAND V SHOOTING STAND

NGR: SO1933255868 Grid reference taken at centre of site Altitude: 500

Period: Modern Broadclass: Recreational

Form: Earthwork **Condition:** C

Site Status:

Description: One of a line of shooting stands aligned northwest-southeast on the northern slopes of Caety

Traylow. It consisted of a positive earth platform, 6m by 6m, with fragments of wood scattered over the surface. It was overgrown with reeds and grass when recorded in February 2007.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289327 Associated with 289218 Associated with 289219 Associated with 289221 Associated with 289222 Associated with 289223 Associated with 289224 Associated with 289225

CAETY TRAYLOW, SHOOTING STAND VI SHOOTING STAND

NGR: SO1936855837 Grid reference taken at centre of site Altitude: 500

Period: Modern Broadclass: Recreational

Form: Earthwork **Condition:** C

Site Status:

Description: One of a line of shooting stands aligned northwest-southeast on the northern slopes of Caety

Traylow. It was a low earth mound, 3.5m in diameter amd 0.3m high, with a central depression 0.10m deep. It was overgrown with moss and grass when recorded in February 2007.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

289327 Associated with Associated with 289218 Associated with 289219 Associated with 289220 Associated with 289222 Associated with 289223 Associated with 289224 Associated with 289225

NPRN: 289222

CAETY TRAYLOW, SHOOTING STAND VII SHOOTING STAND

NGR: SO1940455799 Grid reference taken at centre of site Altitude: 514

Period: Modern Broadclass: Recreational

Form: Earthwork **Condition:** C

Site Status:

Description: One of a line of shooting stands aligned northwest-southeast on the northern slopes of Caety

Traylow. It was a low earth mound, 4m northwest-southeast by 3m. It was overgrown with grass, moss and heather when recorded in February 2007. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289327 Associated with 289218 Associated with 289219 Associated with 289220 Associated with 289221 Associated with 289223 Associated with 289224 Associated with 289225

CAETY TRAYLOW, SHOOTING STAND SHOOTING STAND

XIV

NGR: SO1943255770 Grid reference taken at centre of site Altitude: 508

Period: Modern Broadclass: Recreational

Form: Earthwork **Condition:** C

Site Status:

Description: One of a line of shooting stands aligned northwest-southeast on the northern slopes of Caety

Traylow. It was a low earth mound, 4m northwest-southeast by 3m. It was overgrown with

moss and grass when recorded in February 2007. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289327 Associated with 289218 Associated with 289219 289220 Associated with Associated with 289221 Associated with 289222 Associated with 289224 289225 Associated with

NPRN: 289224

CAETY TRAYLOW, SHOOTING STAND IX SHOOTING STAND

NGR: SO1943855757 Grid reference taken at centre of site Altitude: 504

Period: Modern Broadclass: Recreational

Form: Earthwork Condition: C

Site Status:

Description: One of a line of shooting stands aligned northwest-southeast on the northern slopes of Caety

Traylow. It was a low circular earth mound, 4m in diameter. It was overgrown with gorse

when recorded in February 2007. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289327 289219 Associated with 289220 Associated with Associated with 289221 289222 Associated with Associated with 289223 Associated with 289225 Associated with 289218

CAETY TRAYLOW, SHOOTING STAND I SHOOTING STAND

NGR: SO1945955739 Grid reference taken at centre of site Altitude: 504

Period: Modern Broadclass: Recreational

Form: Earthwork Condition: C

Site Status:

Description: One of a line of shooting stands aligned northwest-southeast on the northern slopes of Caety

Traylow. It was a low earth mound, 4m by 3m. It was overgrown with moss and grass when

recorded in February 2007. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289327 Associated with 289219 Associated with 289220 Associated with 289221 Associated with 289222 Associated with 289223 Associated with 289224 Associated with 289218

NPRN: 289226

CAETY TRAYLOW, MOUND MOUND

NGR: SO1950055792 Grid reference taken at centre of site Altitude: 503

Period: Unknown **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: A low earth mound, 2.25m in diameter and 0.3m high. It may be a natural feature as the area to

the east is more generally hummocky but the area to the west is flat and this stands out in comparison. Vegetation cover in February 2007 was moss. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289227

CWM GRIFFIN, QUARRY QUARRY

NGR: SO1882054642 Grid reference taken at centre of site Altitude: 430

Period:Post MedievalBroadclass:IndustrialForm:EarthworkCondition:B

Site Status:

Description: A large quarry cut into the hillslope above the eastern side of Cwm Griffin. It covered an area

c. 50m northwest-southeast by 9m with a few outlying quarry pits south of the main pits. The quarry is shown on 1st Ordnance Survey map of 1891where it is named as "Old Quarry". Grass partially covered the rocks and spoil on the floor of the quarry in February 2007.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-043 21/02/2007 Quarry, looking northeast

CAETY TRAYLOW, BANK I

BANK (EARTHWORK)

NGR: SO1972856283 Grid reference taken at point along linear site Altitude: 505

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: An earthwork bank running for 60m northeast- southwest on Caety Traylow. The bank was up

to 1.5m wide and up tp 0.40m high, although normally closer to 0.25m. Vegetation cover in

February 2007 was dense heather. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-067 24/02/2007 Bank, looking northeast

NPRN: 289229

GLADESTRY HILL, BANK BAN

BANK (EARTHWORK)

NGR: SO2001355341 Grid reference taken at point along linear site Altitude: 494

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: An low, broad earthwork bank, with a gully on its west side, running from SO2001055351 to

SO2002255317. Vegetation cover in February 2007 was heather. J.J.Hall, Trysor, 13 March

2007

SMR PRN:

Relationships: Photographs:

NPRN: 289231

GLADESTRY HILL, LONG HUT LONG HUT

NGR: SO2010554888 Grid reference taken at centre of site Altitude: 425

Period:Post Medieval?Broadclass:DomesticForm:EarthworkCondition:C

Site Status:

Description: A very denuded rectilinear structure, 9m north-south by 4m externally, defined by earth banks

0.30m wide and 0.10m high. Vegetation cover in February 2007 was moss and heather.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-068 24/02/2007 Long hut, looking south

CWM CESTE, MOUND IV MOUND

NGR: SO1749855163 Grid reference taken at centre of site Altitude: 421

Period: Unknown **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: A low earth mound, 5m south southeast-north northwest by 4m and 0.40m high. Vegetation

cover in February 2007 was long grass and moss. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-069 25/02/2007 Mound, looking southeast

NPRN: 289233

UPPER FFYNNONAU, BANK BANK (EARTHWORK)

NGR: SO1923254606 Grid reference taken at point along linear site Altitude: 435

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** V

Site Status:

Description: An earthwork bank running from SO1922354611 at the eastern edge of a small stream

southeastwards to SO1924154583 where it fades out, via SO1923254606. The bank was about 1m wide at its base and 0.40m high. When recorded in February 2007 it was covered in dead

bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-032 21/02/2007 Bank, looking southwest GC2007-033 21/02/2007 Bank, looking southeast

NPRN: 289234

UPPER FFYNNONAU, PLATFORM PLATFORM

NGR: SO1919554610 Grid reference taken at centre of site Altitude: 434

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: An earthwork platform on the west side of a small stream. The level area of the platform was

9m north northeast - south southwest by 3.25m. The platform was cut into the slope at its north northeast end 1m deep and 2m wide. The other end was built out for 2.5m and 1m high. When recorded in February 2007 the platform was covered with grass, dead bracken and moss.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-034 21/02/2007 Platform, looking southeast GC2007-035 21/02/2007 Platform, looking east-northeast

CWM GRIFFIN, ENCLOSURE I ENCLOSURE

NGR: SO1897054600 Grid reference taken at centre of site Altitude: 432

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork Condition: B

Site Status:

Description: An enclosure adjacent to the common boundary, measuring 40m east-west by 15m. Three

sides of the enclosure were formed by an earth bank. 2m wide at the base and up to 0.70m high. The southern, fourth side was absent, although could have been the common boundary itself but a trackway running alongside the boundary had removed any evidence. A platform NPRN 289244, lay within the enclosure. Vegetation cover in Febraury 2007 was grass and

dead bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289344 GC2007-031 21/02/2007 Enclosure, looking northwest

GC2007-036 21/02/2007 Enclosure, looking west

NPRN: 289236

CWM GRIFFIN, STONE PILE STONE PILE

NGR: SO1876854672 Grid reference taken at centre of site Altitude: 420

Period: Post Medieval? Broadclass: Unassigned

Form: Other Structure Condition: D

Site Status:

Description: A rectangular stone pile, 3m northeast-southwest by 2m and 0.10m high. It was difficult to see

any structure within the pile but t was thought that it could be the remains of a shelter associated with quarry NPRN 289227. Vegetation cover in February 2007 was grass and dead

bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-041 21/02/2007 Stone pile, looking southwest

NPRN: 289238

CWM GRIFFIN, LEAT LEAT?

NGR: SO1875954609 Grid reference taken at point along linear site Altitude: 405

Period: Post Medieval? Broadclass: Water Supply and Drainage

Form: Earthwork Condition: B

Site Status:

Description: A water course on the west side of the Cwm Griffin valley created by a bank on its east side.

The water course or leat varied from 2m-4m wide and was up to 1.5m deep. The feature looks

like a leat but its purpose is unknown. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-038 21/02/2007 Leat, looking southwest GC2007-040 21/02/2007 Leat, looking south GC2007-042 21/02/2007 Leat, looking south

CWM GRIFFIN, PLATFORM I PLATFORM

NGR: SO1875154548 Grid reference taken at centre of site Altitude: 400

Period: Modern? Broadclass: Monument < By Form>

Form: Earthwork Condition: D

Site Status:

Description: A rectangular, level area of ground, 11m south southwest-north northeast by 6m on a generally

level area. It was defined by a very slight earth line, 0.10m high, and 0.30m wide. It was thought to be the base of a temporary structure, probably 20th century. Vegetation cover in

February 2007 was grass and moss. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-044 21/02/2007 Earthwork, looking north

NPRN: 289240

FFYNNONAU, BANK I BANK (EARTHWORK)

NGR: SO1871054570 Grid reference taken at point along linear site Altitude: 408

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: V

Site Status:

Description: A denuded boundary bank, 1.5m wide at its base and 0.15m high. It could be traced from

SO1876754596 to SO1869865562. At its west southwest end it carried on into improved pasture as a substantially less denuded bank, up to 0.60m high, and at its east northeast end continued down to the stream, but was cut by leat NPRN 289238. Dead bracken covered the

feature when it was recorded in February 2007. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289241

FFYNNONAU, ENCLOSURE ENCLOSURE

NGR: SO1865054590 Grid reference taken at centre of site Altitude: 418

Period: Post Medieval Broadclass: Monument < By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A former enclosure, defined by a denuded bank, up to 1.5m wide at its base but now less than

0.15m high, on the edge of the common. The bank formed a triangle running from the common boundary at SO1868254596 via SO1866754615 to SO1864954564 where it left the common again but continued through a strip of former plantation to re-enter the common at SO1861954429. The bank continues to SO1861654329 where it turns eastwards to the common boundary. This enclosure may have been previously been part of the enclosed land but the common boundary was altered and it became part of the common. The J.J.Hall,

Trysor, 13 March 2007

SMR PRN:

FFYNNONAU, BANK II

BANK (EARTHWORK)

NGR: SO1855654443 Grid reference taken at point along linear site Altitude: 422

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork Condition: D

Site Status:

Description: A very denuded field bank, one of several dividing up the former field system, NPRN 289370.

The bank ran from SO18556654443 eastwards down to the common boundary. Although the feature can be seen aerial photographs (for example RAF 106G UK1190, frames 4133 & 4134) it was only seen on the ground as recent cutting of the dead bracken had skimmed the top of

the slightly raised bank. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Part of 289370

NPRN: 289243

LLANFIHANGEL HILL, POND I POND

NGR: SO1891055285 Grid reference taken at centre of site Altitude: 485

Period: Modern? **Broadclass:** Water Supply and Drainage

Form: Earthwork Condition: B

Site Status:

Description: An artificial or artificially enhanced pond, oval in shape measuring 20m east-west by 15m,

with upcast forming a low earthwork around its sides. There was no obvious drainage in or out from this pond, nor NPRN 289244 just to the south southeast. Neither of the ponds are shown on 1st, 2nd or 4th edition Ordnance Survey maps dating from 1891-1953. The vegetation around the pond when it was recorded in February 2007 was heather. J.J.Hall, Trysor, 13

March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289244 GC2007-046 21/02/2007 Pond, looking west

NPRN: 289244

LLANFIHANGEL HILL, POND II POND

NGR: SO1892855234 Grid reference taken at centre of site Altitude: 483

Period: Post Medieval?;Modern? **Broadclass:** Water Supply and Drainage

Form: Earthwork Condition: A

Site Status:

Description: An artificial, or artificially enhanced pond, 30m in diameter, with upcast forming a low

earthwork around its sides. There was a drain out from the feature to the east. Neither this pond, nor NPRN 289243 just to the north northwest are shown on 1st, 2nd or 4th edition Ordnance Survey maps dating from 1891 to 1953. The vegetation around the pond when it

was recorded in February 2007 was heather. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289243 GC2007-047 21/02/2007 Pond, looking north

UPPER FFYNNONAU, BANK

BANK (EARTHWORK)

NGR: SO1926154692 Grid reference taken at point along linear site Altitude: 452

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: B

Site Status:

Description: An earthwork bank, 0.60m high and 1.5m wide, running from SO1926154692 to

SO1929254656. When the bank was recorded during Uplands Survey in February 2007, it was

covered with heather and moss. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289246

COLVA HILL, PLATFORM I PLATFORM?

NGR: SO1973854003 Grid reference taken at centre of site Altitude: 451

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: An artificially terraced area, possibly an earthwork platform, 11m east northeast - west

southwest by 4m. Across its eastern end is a bank, 0.60m high and 4m long, at what would be the positive end of a platform. When the feature was recorded in February 2007, it was

covered in dense dead bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-051 21/02/2007 Platform, looking east-northeast

NPRN: 289247

COLVA HILL, SHEEP FOLD SHEEP FOLD

NGR: SO2014353668 Grid reference taken at centre of site Altitude: 436

Period: Modern Broadclass: Agriculture and Subsistence

Form: Other Structure Condition: D

Site Status:

Description: A former post and wire sheep fold, 21m north-south by 12m. Only half the posts remained

standing and the wire was no longer attached when the feature was recorded in February 2007.

The vegetation at the time was dead bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-052 21/02/2007 Fold, looking north

BRYNTEGAN, CULTIVATION RIDGES CULTIVATION RIDGE

NGR: SO2017053545 Grid reference taken at a central point within an extensive site Altitude: 445

Period: Post Medieval? Broadclass: Agriculture and Subsistence

Form: Earthwork **Condition:** V

Site Status:

Description: An area of ridge and furrow aligned east southeast-west northwest. The horizontal distance

from top of ridge to bottom of furrow was 1.75m. When recorded in February 2007, the ridge and furrow was covered by dead bracken, making it hard to define its extent. J.J.Hall, Trysor,

13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289249

CWM CESTE, MOUND I MOUND

NGR: SO1749455165 Grid reference taken at centre of site Altitude: 422

Period: Unknown **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: A low earth mound, 3m in diameter and 0.20m high, one of a series of features near the

common boundary above Cwm Ceste. The feature was covered with moss and long grass

when recorded in February 2007. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289250 Associated with 289251 Associated with 289252

NPRN: 289250

CWM CESTE, MOUND V MOUND

NGR: SO1749155172 Grid reference taken at centre of site Altitude: 423

Period: Unknown **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: A low earth mound, 4m south southeast-north northwest by 3m and 0.25m high, one of a series

of features near the common boundary above Cwm Ceste. The feature was covered with moss, heather and long grass when recorded in February 2007. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289251 Associated with 289252 Associated with 289249

CWM CESTE, MOUND III MOUND

NGR: SO1748655182 Grid reference taken at centre of site Altitude: 422

Period: Unknown **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A low earth mound, 4m in diameter and 0.40m high, one of a series of features near the

common boundary above Cwm Ceste. The feature was covered with moss and grass when

recorded in February 2007. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289249 Associated with 289250 Associated with 289252

NPRN: 289252

CWM CESTE, MOUND II MOUND

NGR: SO1748155189 Grid reference taken at centre of site Altitude: 425

Period: Unknown **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A low earth mound, 4m in diameter and 0.40m high, one of a series of features near the

common boundary above Cwm Ceste. The feature was covered with moss, grass and reeds

when recorded in February 2007. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289249 GC2007-070 25/02/2007 Mound, looking south-southeast

Associated with 289250 Associated with 289251

NPRN: 289253

CWM CESTE, EARTHWORK VII EARTHWORK

NGR: SO1743755190 Grid reference taken at centre of site Altitude: 428

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: A small, D shaped earthwork, 5m in diameter, defined by a bank, 0.30m high and 1m wide.

The bank is best preserved on the southwest and north sides. A shallow terraced area 7m wide extended for 5m from its northwest side. When the feature was recorded in February 2007, it

was covered with moss and grass. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-071 25/02/2007 Earthwork, looking

west-southwest

CWM CESTE, EARTHWORK III EARTHWORK

NGR: SO1746355168 Grid reference taken at centre of site Altitude: 423

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A small oval earthwork, 5m southeast- northwest by 3m with a centrally depressed area with a

raised rim. It could be a animal feeding platform alongside the trackway but was recorded as there were other unexplained earthwork features nearby. Vegetation cover in February 2007

was moss and grass. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289255

CWM CESTE, EARTHWORK IV EARTHWORK

NGR: SO1749055153 Grid reference taken at centre of site Altitude: 421

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A slight earthwork feature, measuring 7m east-west by 6m. It took the form of a central

depression with a bank forming a slight raised rim, 0.75m wide and less than 0.15m high. May be connected with animal feeding but recorded along with several other unidentified earthwork features close by. Vegetation cover in February 2007 was grass and moss. J.J.Hall, Trysor, 13

March 2007

SMR PRN:

Relationships: Photographs:

GC2007-072 25/02/2007 Earthwork, looking north

NPRN: 289256

CWM CESTE, EARTHWORK V EARTHWORK

NGR: SO1748355159 Grid reference taken at centre of site Altitude: 422

Period: Post Medieval? Broadclass: Monument < By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A slight circular earthwork feature, measuring 6m in diameter. It took the form of a central

depression with a bank forming a slight raised rim, 0.75m wide and less than 0.25m high. May be connected with animal feeding but recorded along with several other unidentified earthwork features close by. Vegetation cover in February 2007 was grass and moss. J.J.Hall, Trysor, 13

March 2007

SMR PRN:

Relationships: Photographs:

GC2007-073 25/02/2007 Earthwork, looking

north-northeast

CWM CESTE, EARTHWORK VI PLATFORM?

NGR: SO1738955115 Grid reference taken at centre of site Altitude: 418

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A terraced area 15m west northwest-east southeast by 5m along a slope at the top of the north

side of the steep valley above Cwm Ceste. The north northeast side of the terrace cut back nto the slope for 2m, 1m deep. A slight bank followed the south and east sides. From the east end of the platform there was a step down onto another terrace (not numbered separately) that continued for another 20m, narrowing to the east. Vegetation cover in February 2007 was

bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-074 25/02/2007 Platform, looking west

GC2007-075 25/02/2007 Platform looking west-northwest

NPRN: 289258

CWM CESTE, BANK III BANK (EARTHWORK)

NGR: SO1736255184 Grid reference taken at point along linear site Altitude: 431

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A very denuded bank running southwest-northeast from SO1737255191 to SO1735355177.

The bank was 1.5m wide and 0.20m high. Vegetation cover in February 2007 was grass.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-076 25/02/2007 Bank, looking southwest

NPRN: 289259

CWM CESTE, TRACKWAY TRACKWAY

NGR: SO1734755193 Grid reference taken at point along linear site Altitude: 433

Period: Post Medieval? Broadclass: Transport

Form: Earthwork **Condition:** C

Site Status:

Description: A narrow trackway, 1.5m wide and 0.30m deep, running from SO1737455190 to

SO1731655196. Vegetation cover in February 2007 was grass. J.J.Hall, Trysor, 13 March

2007

SMR PRN:

BEILI BEDW, QUARRY QUARRY

NGR: SO1750856573 Grid reference taken at centre of site Altitude: 428

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A quarry shown on the 1st edition Ordnance Survey map of 1891 and named as "Old Quarry".

The quarry was cut into an east facing rock outcrop and included several smaller pits. J.J.Hall,

Trysor, 13 March 2007

SMR PRN: CPAT 22474

Relationships: Photographs:

GC2007-084 25/02/2007 Quarry, looking northeast

NPRN: 289261

BEILI BEDW, DAM DAM

NGR: SO1721856211 Grid reference taken at point along linear site Altitude: 384

Period: Post Medieval? **Broadclass:** Water Supply and Drainage

Form: Earthwork **Condition:** B

Site Status:

Description: A large earthwork dam acroos the Gilwern Brook. It was 14m long and over 2.5m high. It has

now been breached in the middle. The purpose of this dam is unknown. Previous fieldworkers mentioned leats in the area but these were not identified on the ground. J.J.Hall, Trysor, 13

March 2007

SMR PRN:

Relationships: Photographs:

GC2007-087 25/02/2007 Dam, looking north

NPRN: 289262

BEILI BEDW, STRUCTURE STRUCTURE

NGR: SO1720456157 Grid reference taken at centre of site Altitude: 387

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: A rectilinear structure on a flat earthen mound. It measured 8m east southeast-west northwest

by 5m. The walls, 0.75m wide, were moss covered but some stone was visible. Vegetation

cover in February 2007 was grass and moss. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Part of 289350 GC2007-088 25/02/2007 Building, looking east

BEILI BEDW, LONG HUT II LONG HUT

NGR: SO1755756066 Grid reference taken at centre of site Altitude: 380

Period: Post Medieval? Broadclass: Domestic

Form: Earthwork Condition: C

Site Status:

Description: A large long hut, 16m east-west by 8m, on a platform. The denuded banks that formed the

walls were 1m wide and less than 0.4m high, although the western one was 2m wide at the base and 0.5m high. Vegetation cover in February 2007 was grass. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Part of 289350 GC2007-089 25/02/2007 Long hut, looking northeast

NPRN: 289264

CWM TWRCH, BANK V BANK (EARTHWORK)

NGR: SO1628454281 Grid reference taken at point along linear site Altitude: 408

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: V

Site Status:

Description: A rectilinear bank forming part of the field system NPRN 289072. The bank itself varied in

size but at its most pronounced was 1.5m wide and 0.30m high and defined an area roughly 110m northwest-southeast by 35m. The bank was traced from SO1626954203, to SO1629954223 to SO1626654321 to SO1623554307. Vegetation cover in March 2007 was

dead bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Part of 289072 GC2007-090 01/03/2007 Bank, looking south-southeast

Part of 289072

NPRN: 289265

CWM TWRCH, BANK I BANK (EARTHWORK)

NGR: SO1636254236 Grid reference taken at point along linear site Altitude: 414

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** V

Site Status:

Description: A linear bank forming part of the field system NPRN 289072. The bank itself varied in size

but at its most pronounced was 2m wide and 0.50m high. It could be traced for roughly 250m from SO1632854103 via SO1636654219 to SO1631254329. Vegetation cover in March 2007

was heather. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Part of 289072 Part of 289072

CWM TWRCH, QUARRY VI QUARRY

NGR: SO1616154063 Grid reference taken at centre of site Altitude: 390

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: A platform or quarry area, 25m north-south by 10m and cut 2m deep into slope at its southern

end. The bottom of the feature was level sloping slightly down to the north. The east side was terraced into the slope. Vegetation cover in March 2007 was dead bracken and grass. J.J.Hall,

Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-091 01/03/2007 Quarry, looking north-northwest

NPRN: 289267

CWM TWRCH, QUARRY V QUARRY

NGR: SO1617253989 Grid reference taken at centre of site Altitude: 390

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork Condition: B

Site Status:

Description: A quarry cut into a southwest facing slope and measuring 12m northwest-southeast by 6m and

up to 4m deep. The spoil appeared to have been used to create a 1.5m wide bank on the outer, southwest edge of the quarry. Vegetation cover in March 2007 was dead bracken and grass.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-092 01/03/2007 Quarry, looking southeast

NPRN: 289268

CWM TWRCH, BANK IV BANK (EARTHWORK)

NGR: SO1631354060 Grid reference taken at point along linear site Altitude: 420

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A rectilinear bank forming part of the field system NPRN 289072. The bank itself varied in

size but on average was 1.5m wide and 0.20m high and defined an area roughly 110m north-south by 90m. The bank was traced from SO1623753994, to SO1629254011 to SO1632454101 to SO1621854104. Vegetation cover in March 2007 was dead bracken or

heather. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Part of 289072 GC2007-095 01/03/2007 Bank, looking north-northeast

Part of 289072 GC2007-096 01/03/2007 Bank, looking west

CWM TWRCH, MOUND I ROUND BARROW?

NGR: SO1632354018 Grid reference taken at centre of site Altitude: 421

Period: Bronze Age? **Broadclass:** Religious, Ritual and Funerary

Form: Earthwork Condition: C

Site Status:

Description: A earth mound, 4m in diameter and 0.25m high. Vegetation cover in March 2007 was heather

and moss. A similar mound, NPRN 289308, lay to 36m to the northeast. J.J.Hall, Trysor, 13

March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289308 GC2007-094 01/03/2007 Mound, looking west

NPRN: 289270

LITTLE HILL, POND V POND

NGR: SO1691154001 Grid reference taken at centre of site Altitude: 463

Period: Post Medieval?; Modern? **Broadclass:** Water Supply and Drainage

Form: Earthwork **Condition:** C

Site Status:

Description: A circular pond, 5m in diameter with a slight bank on the north side 1m wide and 0.20m high.

Vegetation cover around the pond in March 2007 was heather. J.J.Hall, Trysor, 13 March

2007

SMR PRN:

Relationships: Photographs:

NPRN: 289271

BLACK YATT, POND POND

NGR: SO1832656997 Grid reference taken at centre of site Altitude: 425

Period: Post Medieval?; Modern? Broadclass: Water Supply and Drainage

Form: Earthwork **Condition:** A

Site Status:

Description: A modern pond, roughly 20m in diameter, with an earth bank damming the eastern end.

Vegetation cover around the pond in March 2007 was grass, part of an extensive area of

improved pasture. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

BLACK YATT, BUILDING BUILDING

NGR: SO1839956471 Grid reference taken at centre of site Altitude: 374

Period: Post Medieval? Broadclass: Agriculture and Subsistence

Form: Ruin Condition: D

Site Status:

Description: A two celled rectangular structure, 20m east northeast-west southwest by 7m. The walls were

only standing to 0.40m high but stone was visible through the moss and grass covering.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-100 01/03/2007 Building, looking

west-southwest

GC2007-101 01/03/2007 Building, looking east-northeast

NPRN: 289273

BLACK YATT, OUTBUILDING OUTBUILDING

NGR: SO1835756508 Grid reference taken at centre of site Altitude: 375

Period: Post Medieval Broadclass: Unassigned

Form: Ruin Condition: D

Site Status:

Description: A small stone outbuilding, 3.75m northwest-southeast by 3.25m. The walls made of stone and

some brick stood to only 0.50m high. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-102 01/03/2007 Building, looking south

NPRN: 289274

BLACK YATT, FARMHOUSE FARMHOUSE

NGR: SO1836156486 Grid reference taken at centre of site Altitude: 375

Period: Post Medieval Broadclass: Domestic

Form: Ruin Condition: C

Site Status:

Description: The farmhouse at Black Yatt, now in a ruinous condition. The house measured 12.5m

northwest-southeast by 5m built of stone with yellow brick quoins using lime mortar. The south gable end still stood to nearly full height in March 2007but the others walls were much lower. Black Yatt was deserted by the mid-20th century. The house was blown up in the 1960s when it featured in a film about the Second World War ("It Happened Here", 1966) The black paint on the top of the south gable wall and the remains of the front wall relate to the

filming. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-103 01/03/2007 Farmhouse, looking east GC2007-104 01/03/2007 Farmhouse, looking northeast

BLACK YATT, LEAT LEAT

NGR: SO1811656292 Grid reference taken at point along linear site Altitude: 360

Period: Post Medieval Broadclass: Water Supply and Drainage

Form: Earthwork Condition: V

Site Status:

Description: A drainage leat taking water from a spring at SO1809256304. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2006-111 22/12/2006 Leat, looking north

NPRN: 289276

CWM TWRCH, QUARRY IV QUARRY

NGR: SO1620953984 Grid reference taken at centre of site Altitude: 395

Period: Post Medieval Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A quarry pit, 8m in diameter and up to 2m deep. The spoil was pushed to the outer edge on the

southwest side the quarry. Vegetation cover in March 2007 was dead bracken. J.J.Hall,

Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289277

CWM TWRCH, QUARRY III QUARRY

NGR: SO1633254006 Grid reference taken at centre of site Altitude: 419

Period: Post Medieval Broadclass: Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: A quarry pit, 10m in diameter and up to 2m deep. Vegetation cover in March 2007 was dead

bracken and grass. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

FOICE, POND POND

NGR: SO1825757438 Grid reference taken at centre of site Altitude: 385

Period: Modern Broadclass: Water Supply and Drainage

Form: Earthwork **Condition:** A

Site Status:

Description: A modern pond, dammed by an earth bank on its northern side. Vegetation around the pond in

March 2007 was improved pasture. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-098 01/03/2007 Pond, looking west

NPRN: 289279

COLVA HILL, SHOOTING STAND X SHOOTING STAND

NGR: SO1931154555 Grid reference taken at centre of site Altitude: 466

Period: Modern Broadclass: Recreational

Form: Earthwork **Condition:** C

Site Status:

Description: One of a line of former shooting stands depicted on modern Ordnance Survey maps. It

consisted of a low mound, 3m in diameter and 0.2m high, with a level top and a rectilinear depression in the centre. Decaying small timbers were scattered around it. The feature itself was covered by grass but surrounded by dead bracken when recorded in February 2007.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289280 Associated with 289281 Associated with 289282 Associated with 289283

NPRN: 289280

COLVA HILL, SHOOTING STAND VIII SHOOTING STAND

NGR: SO1934754574 Grid reference taken at centre of site Altitude: 473

Period: Modern Broadclass: Recreational

Form: Earthwork Condition: C

Site Status:

Description: One of a line of former shooting stands depicted on modern Ordnance Survey maps. It

consisted of a low mound, 3m in diameter and 0.2m high, with a level top and a rectilinear depression in the centre. Decaying small timbers were scattered around it. The feature itself was covered by grass but surrounded by dead bracken when recorded in February 2007.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289279
Associated with 289281
Associated with 289282
Associated with 289283

COLVA HILL, SHOOTING STAND VII SHOOTING STAND

NGR: SO1938354595 Grid reference taken at centre of site Altitude: 480

Period: Modern Broadclass: Recreational

Form: Earthwork Condition: C

Site Status:

Description: One of a line of former shooting stands depicted on modern Ordnance Survey maps. It

consisted of a low mound, 3m in diameter and 0.2m high, with a level top and a rectilinear depression in the centre. Decaying small timbers were scattered around it. The feature itself was covered by grass but surrounded by dead bracken when recorded in February 2007.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289279
Associated with 289280
Associated with 289282
Associated with 289283

NPRN: 289282

COLVA HILL, SHOOTING STAND VI SHOOTING STAND

NGR: SO1942854613 Grid reference taken at centre of site Altitude: 489

Period: Modern Broadclass: Recreational

Form: Earthwork Condition: D

Site Status:

Description: One of a line of former shooting stands depicted on modern Ordnance Survey maps. It

consisted of a low mound, 3m in diameter and 0.2m high, with a level top and a rectilinear depression in the centre. A sheep track runs through the feature, partially eroding it. The feature itself was covered by grass but surrounded by dead bracken when recorded in February

2007. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289279 Associated with 289280 Associated with 289281 Associated with 289283

COLVA HILL, SHOOTING STAND XII SHOOTING STAND

NGR: SO1945854625 Grid reference taken at centre of site Altitude: 492

Broadclass: Period: Modern Recreational

Form: Earthwork **Condition:**

Site Status:

Description: One of a line of former shooting stands depicted on modern Ordnance Survey maps. It

> consisted of a low mound, 3m in diameter and 0.2m high, with a level top and a central depression. Two upright small timber were still in place on the top of the mound. The feature itself was covered by grass but surrounded by dead bracken when recorded in February 2007.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289279 Associated with 289280 Associated with 289281 289282 Associated with

NPRN: 289284

CEFN HIR, TRACKWAY TRACKWAY

NGR: SO2083355297 Grid reference taken at point along linear site **Altitude:** 445

Period: Post Medieval **Broadclass: Transport** C

Form: Earthwork **Condition:**

Site Status:

A curvilinear trackway, not shown on Ordnance Survey maps, running from SO2057255374 to **Description:**

> SO2084055293 where a modern trackway cut it. The earlier trackway resumed at SO2091455270 andran to SO2120355101. Vegetation cover in March 2007 was heather.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289285

CARREG GWYN, TRACKWAY I TRACKWAY

SO2085654508 Grid reference taken at point along linear site NGR: **Altitude:** 412

Period: Post Medieval **Broadclass:** Transport

Earthwork **Condition:** Form: \mathbf{C}

Site Status:

A disused trackway leading to quarry NPRN 289311, but not shown on any edition Ordnance **Description:**

Survey map. It runs from SO2079254598 downslope to the east to SO2092454441. J.J.Hall,

Trysor, 26 March 2007

SMR PRN:

BLACK YATT, ENCLOSURE ENCLOSURE

NGR: SO1843156244 Grid reference taken at centre of site Altitude: 352

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: A small rectangular enclosure on the northern side of Gilwern Brook near Black Yatt. The

enclosure was roughly 16m northeast-southwest. The southeast, northwest sides were defined by banks but the southwest side was formed by a gully. Vegetation cover in

March 2007 was grass. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2006-112 22/12/2006 Enclosure, looking north

NPRN: 289287

BLACK YATT, FIELD SYSTEM FIELD SYSTEM

NGR: SO1836556407 Grid reference taken at a central point within an extensive site Altitude: 368

Period: Post Medieval Broadclass: Agriculture and Subsistence

Form: Earthwork Condition: D

Site Status:

Description: The field system at Black Yatt consists of two parts, the large rectangular enclosure that

includes the farmhouse and garden plot shown on all editions of the Ordnance Survey maps and much disturbed field system to the south of the farmhouse which has not been mapped.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289288

BLACK YATT, BANK II BANK (EARTHWORK)

NGR: SO1801456558 Grid reference taken at point along linear site Altitude: 394

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A curvilinear earth bank running from SO1787656626 to SO1797756555 to SO1701356557 to

SO1804756573 to SO1812456656. The bank is not shown on any edition Ordnance Survey map and probably relates to an earlier field system. Vegetation cover in March 2007 was

dense dead bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

BLACK YATT, BANK I

BANK (EARTHWORK)

NGR: SO1772156603 Grid reference taken at point along linear site Altitude: 409

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: A very denuded earth bank less than 0.15m high in a field of improved pasture. The

curvilinear bank ran from SO1756456549 to SO1784656631. It is probably part of a former field system connected with banks NPRNs 289300 and 289288. J.J.Hall, Trysor, 13 March

2007

SMR PRN:

Relationships: Photographs:

NPRN: 289290

BLAEN HEATH, BANK II BANK (EARTHWORK)

NGR: SO1731254822 Grid reference taken at point along linear site Altitude: 422

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: V

Site Status:

Description: A curvilinear bank, 2m wide and 0.40m high, defining a former enclosure on the common. The

end points of the bank were at SO1731154795 and SO1743754856. Vegetation cover in

February 2007 was grass and reeds. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289291

BLAEN HEATH, TERRACE T

TERRACED GROUND

NGR: SO1748354879 Grid reference taken at centre of site Altitude: 406

Period: Post Medieval? **Broadclass:** Agriculture and Subsistence

Form: Earthwork Condition: C

Site Status:

Description: A terrace cut into the east facing hillslope above Cwm Ceste, just within the common

boundary. The terrace was 15m south southwest-north northeast by 5m and cut into the slope by 1m. A trackway ran just to the south of the terrace. Vegetation cover in February 2007 was

dead bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

BLAEN HEATH, EARTHWORK II

EARTHWORK

NGR: SO1745854830 Grid reference taken at centre of site Altitude: 406

Period: Unknown **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: A U shaped depression slightly terraced into the slope and embanked. The feature measured

3m by 2m and was thought to be modern. Vegetation cover in February 2007 was grass and

dead bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289293

BLAEN HEATH, LONG HUT LONG HUT

NGR: SO1735354829 Grid reference taken at centre of site Altitude: 422

Period: Post Medieval? Broadclass: Domestic

Form: Earthwork Condition: C

Site Status:

Description: A possible long hut with very low denuded walls enclosing a depressed area within the

enclosure formed by bank NPRN 289290. The feature measured 7m by 4.5m externally and 3.25m by 2m internally. The feature had been eroded by water action and vegetation cover in

February 2007 was reeds. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289294

BLAEN HEATH, BANK I BANK (EARTHWORK)

NGR: SO1729154776 Grid reference taken at point along linear site Altitude: 415

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** V

Site Status:

Description: A U shaped enclosure, 17m in diameter and open to the south, to the east of bank NPRN

289290. The bank was denuded and eroded. In places it was up to 0.50m high but the average height was 0.25m. Vegetation cover in February 2007 was grass and reeds. J.J.Hall, Trysor,

13 March 2007

SMR PRN:

BLAEN HEATH, SHOOTING STAND SHOOTING STAND

NGR: SO1630354909 Grid reference taken at centre of site Altitude: 502

Period: Modern Broadclass: Recreational

Form: Earthwork Condition: B

Site Status:

Description: A shooting stand consisting of an earthwork mound with an intact upright wooden structure on

it. Vegetation cover in February 2007 was heather. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-078 25/02/2007 Shooting stand, looking

south-southeast

NPRN: 289296

BEILI BEDW, STONE STONE

NGR: SO1689056201 Grid reference taken at centre of site Altitude: 409

Period: Unknown Broadclass: Unassigned

Form: Other Structure Condition: U

Site Status:

Description: A single, square stone block earthfast in a small watercourse west of Beili Bedw. The stone

measured 0.50m by 0.60m and was recorded as stones of this size are not known in this area.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-080 25/02/2007 Stone, looking east

NPRN: 289297

BEILI BEDW, TERRACE TERRACED GROUND

NGR: SO1691556457 Grid reference taken at centre of site Altitude: 418

Period: Modern? Broadclass: Agriculture and Subsistence

Form: Earthwork Condition: C

Site Status:

Description: A terrace, probably modern, cut into the south facing slope above Beili Bedw. It measured

25m east southeast- west northwest by 7m. Vegetation over in February 2007 was grass.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

BLACK YATT, BANK IV

BANK (EARTHWORK)

NGR: SO1724456536 Grid reference taken at point along linear site Altitude: 435

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** V

Site Status:

Description: A large earth bank, up to 4m wide at the base and standing up to 0.80m high. It ran from

SO1724456536 to SO1749556665. Although shown on the 1st edition Ordnance Survey map of 1891 and on modern maps, it is no longer a field boundary. Vegetation cover in February

2007 was dead bracken and grass. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-081 25/02/2007 Bank, looking east

NPRN: 289300

BLACK YATT, BANK III BANK (EARTHWORK)

NGR: SO1746356540 Grid reference taken at point along linear site Altitude: 427

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: V

Site Status:

Description: An earthwork bank, 1.5m wide and 0.25m high running from SO1742756554, where it joined

onto NPRN 289298, to SO1749256525. Vegetation cover in February 2007 was dead bracken.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289301

COLVA HILL, SHOOTING STAND XI SHOOTING STAND

NGR: SO1949354635 Grid reference taken at centre of site Altitude: 497

Period: Modern Broadclass: Recreational

Form: Earthwork Condition: C

Site Status:

Description: One of a line of former shooting stands depicted on modern Ordnance Survey maps. It

consisted of a low mound, 3m in diameter and 0.2m high, with a level top but no central depression unlike the others in the line. The feature itself was covered by grass but surrounded

by heather when recorded in February 2007. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

COLVA HILL, SHOOTING STAND IX SHOOTING STAND

NGR: SO1953054649 Grid reference taken at centre of site Altitude: 500

Period: Modern Broadclass: Recreational

Form: Earthwork **Condition:** C

Site Status:

Description: One of a line of former shooting stands depicted on modern Ordnance Survey maps. It

consisted of a low mound, 3m in diameter and 0.1m high, with a level top. The feature itself was covered by grass but surrounded by heather when recorded in February 2007. J.J.Hall,

Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289303

BEILI BEDW, LONG HUT I LONG HUT

NGR: SO1739256100 Grid reference taken at centre of site Altitude: 382

Period: Post Medieval Broadclass: Domestic

Form: Earthwork **Condition:** C

Site Status:

Description: A long hut or longhouse on the south side of Gilwern Brook at Beili Bedw. The dry stone

structure measured 19m east-west by 6.8m with a possible extension to the east. J.J.Hall,

Trysor, 13 March 2007

SMR PRN: CPAT 33935

Relationships: Photographs:

Part of 289350

NPRN: 289304

BEILI BEDW, TRACKWAY I TRACKWAY

NGR: SO1730156091 Grid reference taken at point along linear site Altitude: 385

Period: Post Medieval? **Broadclass:** Transport

Form: Earthwork **Condition:** C

Site Status:

Description: A trackway within the deserted rural settlement at Beili Bedw. The trackway was traced

running from SO1728956081 to SO1731156101. Vegetation cover in February 2007 was

grass. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

BEILI BEDW, TRACKWAY II TRACKWAY?

NGR: SO1747456129 Grid reference taken at point along linear site Altitude: 382

Period: Post Medieval Broadclass: Transport

Form: Earthwork Condition: C

Site Status:

Description: Alinear earthwork within the deserted rural settlement at Beili Bedw. The earthwork was

traced running from SO1738756124 to SO1755356092. The feature was thought to be a trackway but maybe connected wih the leats mentioned by previous fieldworkers. Vegetation

cover in February 2007 was grass. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289306

BEILI BEDW, BANK BANK (EARTHWORK)

NGR: SO1754156098 Grid reference taken at point along linear site Altitude: 365

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: A bank within the deserted rural settlement at Beili Bedw. The bank was traced running from

SO1753056135 to SO1754556070. Vegetation cover in February 2007 was grass. J.J.Hall,

Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289307

CARREG GWYN, TRACKWAY II TRACKWAY

NGR: SO2062754554 Grid reference taken at point along linear site Altitude: 455

Period: Post Medieval Broadclass: Transport

Form: Earthwork Condition: C

Site Status:

Description: A trackway leading to quarry NPRN 289330 at Carreg Gwyn. The trackway was traced from

SO2070354541 to SO2058054596 via SO2064054542. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

CWM TWRCH, MOUND II ROUND BARROW?

NGR: SO1634854047 Grid reference taken at centre of site Altitude: 426

Period: Bronze Age? Broadclass: Religious, Ritual and Funerary

Form: Earthwork Condition: C

Site Status:

Description: A circular earth mound, 5m east-west by 4m and 0.25m high with a central depression. It may

be a round barrow, or the remains of a more recent shooting stand. Vegetation cover in March

2007 was heather. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289269 GC2007-093 01/03/2007 Mound, looking east

NPRN: 289309

GLADESTRY BROOK, BANK IV BANK (EARTHWORK)

NGR: SO2044854304 Grid reference taken at point along linear site Altitude: 378

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: An earth bank, 1m wide and 0.20m high on the east side of Gladestry Brook. The bank ran

from SO2043354387 to SO2045054235. Vegetation cover in March 2007 was dead bracken.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289310

CARREG GWYN, QUARRY I QUARRY

NGR: SO2073154371 Grid reference taken at centre of site Altitude: 415

Period: Post Medieval? **Broadclass:** Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: A small quarry, 8m by 6m and 1m deep. Vegetation cover in March 2007 was grass and dead

bracken. J.J.Hall, Trysor, 24 March 2007

SMR PRN:

CARREG GWYN, QUARRY II QUARRY

NGR: SO2080154610 Grid reference taken at centre of site Altitude: 435

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A series of quarry pits in an area 60m south southwest-north northeast by 20m. The pits were

up to 3m deep. Vegetation cover was heather, moss and grass. J.J.Hall, Trysor, 24 March

2007

SMR PRN:

Relationships: Photographs:

GC2007-109 18/03/2007 Quarry, looking south

NPRN: 289312

CEFN HIR, EARTHWORK QUARRY?;PLATFORM?

NGR: SO2110054904 Grid reference taken at centre of site Altitude: 409

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: A roughly level terrace, 11m northeast-southwest by 5m. It may be a platform or possibly a

quarry although no stone was visible. Vegetation cover was grass and dead bracken. J.J.Hall,

Trysor, 24 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-110 18/03/2007 Platform, looking northeast

NPRN: 289313

CEFN HIR, BANK III BANK (EARTHWORK)

NGR: SO2113054953 Grid reference taken at point along linear site Altitude: 410

Period: Post Medieval? Broadclass: Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: An earth bank, 0.70m wide and 0.20m high, traced from SO2112554935 to SO2113654971.

Vegetation cover in March 2007 was grass. J.J.Hall, Trysor, 24 March 2007

SMR PRN:

NPRN: 289314 CEFN HIR, BANK II

BANK (EARTHWORK)

NGR: SO2116555002 Grid reference taken at point along linear site Altitude: 410

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: V

Site Status:

Description: A former rectilinear enclosure on the common, about 100m northeast-southwest and 14m from

the common boundary. The earth bank that defined it was 1.5m wide and up to 0.7m high.

Vegetation cover in February 2007 was grass. J.J.Hall, Trysor, 24 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-111 18/03/2007 Bank, looking northeast

NPRN: 289315

CEFN HIR, BANK I BANK (EARTHWORK)

NGR: SO2143355245 Grid reference taken at point along linear site Altitude: 389

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** V

Site Status:

Description: Parts of a former rectilinear field system intruding onto the common consisting of a corner of

an enclosure, and a bank running north from this. A gap between the two seems to have been a trackway onto the common. The earth bank that defined it was up to 2.5m wide and 0.4m high. Vegetation cover in February 2007 was grass and dead bracken. J.J.Hall, Trysor, 24 March

2007

SMR PRN:

Relationships: Photographs:

NPRN: 289316

CEFN HIR, SHOOTING STAND III SHOOTING STAND

NGR: SO2051655306 Grid reference taken at centre of site Altitude: 472

Period: Modern Broadclass: Recreational

Form: Earthwork Condition: C

Site Status:

Description: A shooting stand, one of a line of shooting stands near Cefn Hir. It was an earth mound 4m in

diameter with a north-south cut through the middle. Vegetation cover in March 2007 was

heather. J.J.Hall, Trysor, 24 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289337
Associated with 289335
Associated with 289334
Associated with 289331

CAETY TRAYLOW, SHOOTING STAND XI SHOOTING STAND

NGR: SO1995655946 Grid reference taken at centre of site Altitude: 505

Period: Modern Broadclass: Recreational

Form: Earthwork **Condition:** D

Site Status:

Description: A shooting stand, one of a line of shooting stands on the eastern side of Caety Traylow. It was

a low, circular earth mound, 2m in diameter and less than 0.20m high. One timber stood upright and another was fallen. Vegetation cover in March 2007 was heather. J.J.Hall,

Trysor, 24 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289318

CAETY TRAYLOW, SHOOTING STAND XII SHOOTING STAND

NGR: SO1998555960 Grid reference taken at centre of site Altitude: 505

Period: Modern Broadclass: Recreational

Form: Earthwork Condition: C

Site Status:

Description: A shooting stand, one of a line of shooting stands on the eastern side of Caety Traylow. No

mound was visible but in a slight clearing in the vegetation, one timber stood upright and another was fallen. Vegetation around the feature in March 2007 was heather. J.J.Hall,

Trysor, 24 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289319

CAETY TRAYLOW, SHOOTING STAND SHOOTING STAND

XIII

NGR: SO2005255971 Grid reference taken at centre of site Altitude: 500

Period: Modern Broadclass: Recreational

Form: Earthwork **Condition:** C

Site Status:

Description: A shooting stand, one of a line of shooting stands on the eastern side of Caety Traylow. No

mound was visible but in a slight clearing in the vegetation, two timbers stood upright and decayed wood was scattered around on the ground. Vegetation around the feature in March

2007 was heather. J.J.Hall, Trysor, 24 March 2007

SMR PRN:

CAETY TRAYLOW, SHOOTING STAND X SHOOTING STAND

NGR: SO2010755988 Grid reference taken at centre of site Altitude: 500

Period: Modern Broadclass: Recreational

Form: Earthwork **Condition:** C

Site Status:

Description: A shooting stand, one of a line of shooting stands on the eastern side of Caety Traylow. No

mound was visible but in a slight clearing in the vegetation, one timber stood upright and another was fallen. Vegetation around the feature in March 2007 was heather. J.J.Hall,

Trysor, 24 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289321

CAETY TRAYLOW, SHOOTING STAND SHOOTING STAND

VIII

NGR: SO2030356070 Grid reference taken at centre of site Altitude: 473

Period: Modern Broadclass: Recreational

Form: Earthwork Condition: C

Site Status:

Description: A shooting stand, one of a line of shooting stands on the eastern side of Caety Traylow. No

mound was visible but in a 2m diameter clearing in the vegetation, one timber stood upright and wood fragments were scattered on the ground. Vegetation around the feature in March

2007 was heather. J.J.Hall, Trysor, 24 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289322

CAETY TRAYLOW, QUARRY I QUARRY

NGR: SO2062556062 Grid reference taken at centre of site Altitude: 410

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: A quarry, 10m in diameter and up to 3m deep. Vegetation cover in March 2007 was grass.

J.J.Hall, Trysor, 24 March 2007

SMR PRN:

CAETY TRAYLOW, PLATFORM I PLATFORM

NGR: SO2067656113 Grid reference taken at centre of site Altitude: 385

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: An earthwork platform cut into a northeast facing slope. It measured 16m southeast-northwest

by 9m and was terraced in by 1m. Vegetation cover in March 2007 was dead bracken.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-114 18/03/2007 Platform, looking east

NPRN: 289324

CAETY TRAYLOW, PLATFORM II PLATFORM

NGR: SO2062455975 Grid reference taken at centre of site Altitude: 390

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: An earthwork platform terraced into a steep south southeast facing slope. The platform

measured 10m south southeast-north northwest by 9m. It was terraced at the north northwest end by 2m and an apron 2m high at the other end. Vegetation cover in March 2007 was grass.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-117 18/03/2007 Platform, looking south

NPRN: 289325

CWM EINION, PLATFORM II PLATFORM

NGR: SO2061855738 Grid reference taken at centre of site Altitude: 385

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: B

Site Status:

Description: An earthwork platform terraced into a north northeast facing slope. The platform measured

17m north northeast-south southwest by 5m. It was terraced at the south end by 1.5m and an apron 1.5m high at the other end. The platform loses 1m in height along its length. Vegetation

cover in March 2007 was dead bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-115 18/03/2007 Platform, looking south GC2007-116 18/03/2007 Platform, looking south GC2007-118 18/03/2007 Platform, looking south

CWM EINION, PLATFORM I PLATFORM

NGR: SO2070355723 Grid reference taken at centre of site Altitude: 375

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: D

Site Status:

Description: An earthwork platform terraced into a north northeast facing slope. The platform measured

8m north northeast-south southwest by 6m. It was terraced at the south end by 1.5m and an apron 1.5m high at the other end. A modern trackway cut across the centre of the platform, partially obscuring it. Vegetation cover in March 2007 was dead bracken. J.J.Hall, Trysor, 13

March 2007

SMR PRN:

Relationships: Photographs:

GC2007-119 18/03/2007 Platform, looking east

NPRN: 289327

CAETY TRAYLOW, SHOOTING STAND II SHOOTING STAND

NGR: SO1923455953 Grid reference taken at centre of site Altitude: 461

Period: Modern Broadclass: Recreational

Form: Earthwork **Condition:** C

Site Status:

Description: One of a series of shooting stands on the northern slope of Caety Traylow. J.J.Hall, Trysor, 13

March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289218 Associated with 289219 Associated with 289220 Associated with 289221 289222 Associated with Associated with 289223 289224 Associated with 289225 Associated with

NPRN: 289328

COLVA HILL, SHOOTING STAND V SHOOTING STAND

NGR: SO1928254536 Grid reference taken at centre of site Altitude: 455

Period: Modern Broadclass: Recreational

Form: Earthwork **Condition:** C

Site Status:

Description: One of a series of shooting stands on the western slopes of Colva Hill. Shown on modern

Ordnance Survey maps but not identified in the field. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

LLANHAYLOW, QUARRY I QUARRY

NGR: SO2047053795 Grid reference taken at centre of site Altitude: 365

Period: Post Medieval? Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: Two small adjacent quarry pits on a north-facing slope. J.J.Hall, Trysor, 24 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-107 18/03/2007 Quarry, looking south-southwest

NPRN: 289330

CARREG GWYN, QUARRY III QUARRY

NGR: SO2057554597 Grid reference taken at centre of site Altitude: 470

Period: Post Medieval Broadclass: Industrial

Form: Earthwork **Condition:** C

Site Status:

Description: Small quarry in a natural rock outcrop. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-108 18/03/2007 Quarry, looking northwest

NPRN: 289331

CEFN HIR. SHOOTING STAND IV SHOOTING STAND

NGR: SO2049355046 Grid reference taken at centre of site Altitude: 509

Period: Modern Broadclass: Recreational

Form: Earthwork Condition: U

Site Status:

Description: One of a line of 6 shooting stands above Cefn Hir, shown on modern Ordnance Survey maps.

Disused. J.J.Hall, Trysor, 24 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289337 Associated with 289336 Associated with 289335 Associated with 289334 Associated with 289316

CARREG GWYN, EARTHWORK QUARRY?;PLATFORM?

NGR: SO2063754312 Grid reference taken at centre of site Altitude: 420

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: A subcircular sccop cut into the slope with a slight semicircular bank on its southeastern

downslope side. The feature is 3m in diameter and the bank was 1.3m wide and 0.30m high.

Vegetation cover in March 2007 was dead bracken. J.J.Hall, Trysor, 24 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289333

CARREG GWYN, QUARRY IV QUARRY?

NGR: SO2061154392 Grid reference taken at centre of site Altitude: 423

Period: Post Medieval? **Broadclass:** Industrial

Form: Earthwork Condition: C

Site Status:

Description: A rectilinear depression, 5m southeast-northwest by 3m with another amorphous depression to

its southwest, possibly an old quarry pit. Vegetation cover in March 2007 was dense heather

and moss. J.J.Hall, Trysor, 24 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289334

CEFN HIR, SHOOTING STAND VI SHOOTING STAND

NGR: SO2049955123 Grid reference taken at centre of site Altitude: 504

Period: Modern Broadclass: Recreational

Form: Earthwork **Condition:** C

Site Status:

Description: One of a line of 6 shooting stands above Cefn Hir, shown on modern Ordnance Survey maps.

Disused. J.J.Hall, Trysor, 24 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289316 Associated with 289337 Associated with 289331 Associated with 289336

CEFN HIR, SHOOTING STAND II SHOOTING STAND

NGR: SO2050355163 Grid reference taken at centre of site Altitude: 497

Period: Modern Broadclass: Recreational

Form: Earthwork Condition: C

Site Status:

Description: One of a line of 6 shooting stands above Cefn Hir, shown on modern Ordnance Survey maps.

Disused. J.J.Hall, Trysor, 24 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289316 Associated with 289337 Associated with 289336 Associated with 289334 Associated with 289331

NPRN: 289336

CEFN HIR, SHOOTING STAND I SHOOTING STAND

NGR: SO2050555209 Grid reference taken at centre of site Altitude: 493

Period: Modern Broadclass: Recreational

Form: Earthwork Condition: C

Site Status:

Description: One of a line of 6 shooting stands above Cefn Hir, shown on modern Ordnance Survey maps.

Disused. J.J.Hall, Trysor, 24 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289316 Associated with 289337 Associated with 289335 Associated with 289331 Associated with 289331

NPRN: 289337

CEFN HIR, SHOOTING STAND V SHOOTING STAND

NGR: SO2051055256 Grid reference taken at centre of site Altitude: 484

Period: Modern Broadclass: Recreational

Form: Earthwork Condition: C

Site Status:

Description: One of a line of 6 shooting stands above Cefn Hir, shown on modern Ordnance Survey maps.

Disused. J.J.Hall, Trysor, 24 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289316 Associated with 289335 Associated with 289334 Associated with 289331

CWM EINION, CULTIVATION RIDGES CULTIVATION RIDGE

NGR: SO2061955759 Grid reference taken at a central point within an extensive site Altitude: 360

Period: Post Medieval Broadclass: Agriculture and Subsistence

Form: Earthwork Condition: C

Site Status:

Description: An area of ridge and furrow, now overgrown with bracken, probably associated with two

platforms which are also located on the southern side of the upper Einion valley. J.J.Hall,

Trysor, 24 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-112 18/03/2007 Cultivation ridges, looking

south

NPRN: 289339

PANT GLAS, COTTAGE COTTAGE

NGR: SO1854055922 Grid reference taken at centre of site Altitude: 380

Period:Post MedievalBroadclass:DomesticForm:BuildingCondition:A

Site Status:

Description: A small cottage on the northern flank of Llanfihangel Hill. It seems to have been abandoned

during the 20th century, but re-occupied by the latter part of the century and remains in

occupation in 2007. J.J.Hall, Trysor, 24 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289340

PANT GLAS, FIELD SYSTEM FIELD SYSTEM

NGR: SO1859056010 Grid reference taken at a central point within an extensive site Altitude: 370

Period: Post Medieval **Broadclass:** Agriculture and Subsistence

Form: Earthwork Condition: C

Site Status:

Description: A small field system associated with the cottage of Pant Glas. It includes three small fields

forming an isolated area of improved pasture carved out of the common. J.J.Hall, Trysor, 24

March 2007

SMR PRN:

Relationships: Photographs:

GC2007-099 01/03/2007 Field system, looking south

MOUNTAIN HALL, QUARRY I QUARRY

NGR: SO1511956268 Grid reference taken at centre of site Altitude: 450

Period: Post Medieval Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: Marked as an "Old Quarry" on the 1st edition Ordnance Survey map of 1891. J.J.Hall, Trysor,

13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289342

MOUNTAIN HALL, QUARRY II QUARRY

NGR: SO1493956331 Grid reference taken at centre of site Altitude: 470

Period: Post Medieval Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: Marked as an "Old Quarry" on the 1st edition Ordnance Survey map of 1891. J.J.Hall, Trysor,

13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289343

CWM GRIFFIN, BANK II BANK (EARTHWORK)

NGR: SO1904154665 Grid reference taken at point along linear site Altitude: 435

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status:

Description: An old field boundary, very eroded, standing less than 0.30m high. J.J.Hall, Trysor, 13 March

2007

SMR PRN:

Relationships: Photographs:

GC2007-049 21/02/2007 Bank, looking southwest GC2007-050 21/02/2007 Bank, looking southwest

CWM GRIFFIN, PLATFORM II PLATFORM

NGR: SO1897654597 Grid reference taken at centre of site Altitude: 427

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: A probable house or building platform within enclosure NPRN 289235. The platform is

parallel to the contour and measures 17m east-west by 5m. At the east end of the platform is a pile of stones 4m x 4m and up to 0.25m high, presumed to be derived from a structure that

occupied the platform. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289235 GC2007-037 21/02/2007 Platform, looking west

NPRN: 289345

CWM GRIFFIN, PLATFORM III PLATFORM

NGR: SO1906154975 Grid reference taken at centre of site Altitude: 479

Period: Medieval?; Post Medieval? **Broadclass:** Monument < By Form>

Form: Earthwork Condition: C

Site Status:

Description: A sub-rectilinear platform or possible hut circle within enclosure NPRN 289209. It measured

6m southwest-northeast by 9m and the northeast side was cut into the slope up to a depth of

1m. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Associated with 289209 GC2007-061 24/02/2007 Platform, looking southeast

NPRN: 289346

BLAEN ROTHROW, TRACKWAY I TRACKWAY

NGR: SO1766453921 Grid reference taken at point along linear site Altitude: 360

Period: Post Medieval Broadclass: Transport

Form: Earthwork Condition: C

Site Status:

Description: A short section of trackway, 90m long from SO1765653954 where it joins the common to

SO1767453871. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

BLAEN ROTHROW, TRACKWAY II TRACKWAY

NGR: SO1761753943 Grid reference taken at point along linear site Altitude: 370

Period: Post Medieval Broadclass: Transport

Form: Earthwork Condition: C

Site Status:

Description: A short section of trackway or path, 195m long from SO1755654029 to SO1767153871. The

trackway was only 0.50m wide. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289348

COLVA HILL, TRACKWAY II TRACKWAY

NGR: SO1994054050 Grid reference taken at point along linear site Altitude: 430

Period: Post Medieval Broadclass: Transport

Form: Earthwork Condition: C

Site Status:

Description: A section of trackway running from SO1987053850 to SO2002654188. Northwards from this

point it was hard to define where the original track went. The modern track follows the fence line towards Gladestry Brook. Vegetation cover around the trackway in February 2007 was

dead bracken. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289349

BEILI BEDW, ENCLOSURE ENCLOSURE

NGR: SO1734756110 Grid reference taken at centre of site Altitude: 381

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status:

Description: An sub rectangular enclosure, part of the deserted rural settlement at Beili Bedw, NPRN

289350. The enclosure, 45m east-west by 12m, was defined by large grassed over banks.

J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Part of 289350

BEILI BEDW, DESERTED RURAL

DESERTED RURAL SETTLEMENT

SETTLEMENT

NGR: SO1739256091 Grid reference taken at a central point within an extensive site Altitude: 385

Period:Post MedievalBroadclass:DomesticForm:ComplexCondition:V

Site Status:

Description: The deserted rural settlement complex at Beili Bedw was reasonably well preserved.

Unfortunately, this site was inaccessible duringUplands Survey as the landowner could not be traced, and could only be viewed from adjacent land. At least three buildings were present (NPRNs 289262, 289263, 289303) as well as an enclosure (NPRN 289349) and a series of trackways and banks. There also appears to be a large earthwork dam (NPRN 289261) across the Gilwern Brook just to the west of the complex, the purpose of which is unclear, but may be relevant to the history of the settlement. Beili Bedw does not appear on the 1831 Ordnance Survey map, although the boundary banks of its field system are shown, and by the time of the 1840 Glascwm parish tithe map the site has been turned into a nursery for local woodland

plantations. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships:		Photographs:		
Consists of	289349	GC2006-104	09/12/2006	Deserted settlement, looking
Consists of	289303			east-southeast
Consists of	289262	GC2007-079	25/02/2007	Deserted settlement, looking
Consists of	289263			northeast
		GC2007-082	25/02/2007	Deserted settlement, looking south
		GC2007-085	25/02/2007	Deserted settlement, looking south
		GC2007-086	25/02/2007	Deserted settlement, looking southeast

NPRN: 289352

COLVA HILL, TRACKWAY I TRACKWAY

NGR: SO1975153262 Grid reference taken at point along linear site Altitude: 440

Period: Post Medieval Broadclass: Transport

Form: Earthwork **Condition:** C

Site Status:

Description: A trackway, not shown on Ordnance Survey maps, running from the common boundary at

SO1973953101uphill to SO1991753452, via SO1971453214 and SO1973555229. J.J.Hall,

Trysor, 26 March 2007

SMR PRN:

CAETY TRAYLOW, QUARRY II QUARRY

NGR: SO1932056090 Grid reference taken at centre of site Altitude: 480

Period: Post Medieval Broadclass: Industrial

Form: Earthwork Condition: B

Site Status:

Description: A quarry shown on the 1st edition Ordnance Survey map of 1891, nut not named or described.

The quarry was approximately 50m northwest-southeast by 15m and up to 2m deep. Vegetation cover in February 2007 was grass, moss and heather. J.J.Hall, Trysor, 26 March

2007

SMR PRN:

Relationships: Photographs:

GC2007-066 24/02/2007 Quarry, looking northwest

NPRN: 289354

TY'N-Y-COED, QUARRY II QUARRY

NGR: SO1378154455 Grid reference taken at centre of site Altitude: 420

Period: Post Medieval Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A quarry shown on the 1st edition Ordnance Survey map of 1891 where it is named as

"Quarry". By the time of the 2nd edition map of 1905 it is named "Old Quarry", although it seems to have been used more recently. It was approximately 25m in diameter and up to 3m

deep. J.J.Hall, Trysor, 26 March 2007

SMR PRN: CPAT 22489

Relationships: Photographs:

NPRN: 289355

BLACK YATT, BARN BARN

NGR: SO1775056450 Grid reference taken at centre of site Altitude: 387

Period: Post Medieval Broadclass: Agriculture and Subsistence

Form: Ruin Condition: C

Site Status:

Description: A field barn shown on the 1st edition Ordnance Survey map of 1891, and in a field named as

"Barn Field" on the 1840 Glascwm parish tithe map. Access issues meant that the barn was not visited directly but it was now within an area of heavily improved pasture. J.J.Hall, Trysor, 26

March 2007

SMR PRN: CPAT 4109

BLACK YATT, PLANTATION I PLANTATION

NGR: SO1812056650 Grid reference taken at centre of site Altitude: 400

Period: Post Medieval Broadclass: Agriculture and Subsistence

Form: Documents Condition: E

Site Status:

Description: Plantation shown on 1st edition Ordnance Survey map of 1891. One of several around Black

Yatt. Still shown on 1905 2nd edition OS map, but gone by the time of the survey of the 4th

edition map of the 1930s. No trace of plantation now. J.J.Hall, Trysor, 26 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289357

BLACK YATT, PLANTATION II PLANTATION

NGR: SO1800056220 Grid reference taken at centre of site Altitude: 365

Period: Post Medieval **Broadclass:** Agriculture and Subsistence

Form: Topography Condition: B

Site Status:

Description: Plantation shown on 1st edition Ordnance Survey map of 1891. One of several around Black

Yatt. Still shown on 1905 2nd edition OS map, but gone by the time of the survey of the 4th edition map of the 1930s. A small conifer plantation now occupies the site. J.J.Hall, Trysor,

26 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-083 25/02/2007 Plantation, looking southeast

NPRN: 289358

CEFN HIR, QUARRY QUARRY

NGR: SO2062255640 Grid reference taken at centre of site Altitude: 415

Period: Post Medieval Broadclass: Industrial

Form: Earthwork Condition: C

Site Status:

Description: A small quarry above the Cwm Hir valley. Not shown on any Ordnance Survey maps. J.J.Hall,

Trysor, 26 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-113 18/03/2007 Quarry, looking south

BEILI BEDW, PLANTATION II PLANTATION

NGR: SO1737756085 Grid reference taken at centre of site Altitude: 385

Period: Post Medieval Broadclass: Agriculture and Subsistence

Form: Documents Condition: E

Site Status:

Description: A forest nursery is shown here on the Colva Parish tithe map of 1840 (parcel no. 354).

Apparently no longer in existence by the time of the 1891 Ordnance Survey map. No trace of

plantation now. J.J.Hall, Trysor, 26 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289360

BEILI BEDW, PLANTATION I PLANTATION

NGR: SO1800956123 Grid reference taken at centre of site Altitude: 360

Period: Post Medieval **Broadclass:** Agriculture and Subsistence

Form: Documents Condition: D

Site Status:

Description: A forest nursery is shown here on the Colva Parish tithe map of 1840 (parcel no. 356).

Apparently no longer in existence by the time of the 1891 Ordnance Survey map. No trace of

plantation now. J.J.Hall, Trysor, 26 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289361

BLAEN BEDW, MOUND I MOUND

NGR: SO1402954405 Grid reference taken at centre of site Altitude: 445

Period: Unknown Broadclass: Monument <By Form>

Form: Earthwork **Condition:** B

Site Status:

Description: A earthen mound, measuring 6m square x 1m high, sub-rectilinear in plan. It lies a short

distance to the north of the Giants Grave round barrow (NPRN24594). Its date and purpose are unknown, but it has been suggested that it may represent a prehistoric funerary monument or

even a gibbet mound. J.J.Hall, Trysor, 26 March 2007

SMR PRN: CPAT 4111

Relationships: Photographs:

GC2006-020 18/06/2006 Mound, looking east

GC2006-021 18/06/2006 Mound, looking south. NPRN

24594 in background

GELLIDYWYLL, PLATFORM III PLATFORM

NGR: SO1423252817 Grid reference taken at centre of site Altitude: 395

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status: RD168

Description: A earth building platform cut into a south-southeast facing slope at the edge of Little Hill

common. It measures 12m north-northwest x south-southeast and is 5.2m wide. It is terraced 1.5 into the slope. There is a step down of 0.4m 5m from the north-northwest end of the platform. It is close to, and possibly paired with platform NPRN 289363. When visited in the

summer of 2006, the site was obscured by bracken. J.J.Hall, Trysor, 26 March 2007

SMR PRN:

Relationships: Photographs:

GC2006-024 18/06/2006 Platform, looking south

NPRN: 289363

GELLIDYWYLL, PLATFORM II PLATFORM

NGR: SO1422152813 Grid reference taken at centre of site Altitude: 393

Period: Post Medieval Broadclass: Monument <By Form>

Form: Earthwork Condition: C

Site Status: RD168

Description: A earth building platform cut into a south-southeast facing slope at the edge of Little Hill

common. It measures 6m north-northwest x south-southeast and is 5m wide. It is terraced 1.2 into the slope at its north-northwest end. The apron is 1.2m high. It is close to, and possibly paired with platform NPRN 289362. When visited in the summer of 2006, the site was

obscured by bracken. J.J.Hall, Trysor, 26 March 2007

SMR PRN:

Relationships: Photographs:

GC2006-025 18/06/2006 Platform, looking southeast

NPRN: 289364

GELLIDYWYLL, PLATFORM I PLATFORM

NGR: SO1426152819 Grid reference taken at centre of site Altitude: 388

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status: RD168

Description: A earth building platform cut into a south-southeast facing slope at the edge of Little Hill

common. It measures 12.5m north-northwest x south-southeast and is 4.2m wide. It is terraced 2m into the slope at its north-northwest end. When visited in the summer of 2006, the

site was obscured by bracken. J.J.Hall, Trysor, 26 March 2007

SMR PRN:

Relationships: Photographs:

GC2006-026 18/06/2006 Platform, looking southeast

GELLIDYWYLL, PLATFORM IV PLATFORM

NGR: SO1429752838 Grid reference taken at centre of site Altitude: 380

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork Condition: C

Site Status: RD168

Description: A earth building platform cut into a south-southeast facing slope at the edge of Little Hill

common. It measures 11m northwest x southeast and is 5m wide. It is terraced 2m into the slope at its northwest end. A trackway crosses the southeast end of the platform where some stoen is exposed. When visited in the summer of 2006, the site was obscured by bracken.

J.J.Hall, Trysor, 26 March 2007

SMR PRN:

Relationships: Photographs:

GC2006-027 18/06/2006 Platform, looking north

northeast

GC2006-028 18/06/2006 Platform, looking east northeast

NPRN: 289366

GELLIDYWYLL, EARTHWORK SHELTER?;PLATFORM?

NGR: SO1426352865 Grid reference taken at centre of site Altitude: 398

Period: Post Medieval **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** C

Site Status: RD168

Description: A earth building platform cut into a south-southeast facing slope at the edge of Little Hill

common. It measures 4m in diameter externally, and 2m internally. There is some stone visible in an eroded patch at the north side of the platform. Bilberries grow on this platform, it

is above the bracken line. J.J.Hall, Trysor, 26 March 2007

SMR PRN:

Relationships: Photographs:

GC2006-029 18/06/2006 Small platform, looking north

NPRN: 289367

GELLIDYWYLL, PLATFORM V PLATFORM

NGR: SO1431152844 Grid reference taken at centre of site Altitude: 381

Period: Post Medieval Broadclass: Monument < By Form>

Form: Earthwork Condition: C

Site Status: RD168

Description: A earth building platform cut into a south-southeast facing slope at the edge of Little Hill

common. It measures 7m east-northeast x west-southwest and is 3.5m wide and is cut parallel to the contour. It is cut by a trackway running east-west which is causing some damage. When visited in the summer of 2006, the site was obscured by bracken. J.J.Hall, Trysor, 26 March

2007

SMR PRN:

Relationships: Photographs:

GC2006-030 18/06/2006 Platform, looking east

FFYNNONAU, BANK IV

BANK (EARTHWORK)

NGR: SO1856354534 Grid reference taken at point along linear site Altitude: 425

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork Condition: D

Site Status:

Description: A very denuded field bank, an internal division within field system NPRN 289370. The bank

runs east - west down to the common boundary. It was 2m wide but only 0.10m high. J.J.Hall,

Trysor, 26 March 2007

SMR PRN:

Relationships: Photographs:

Part of 289370

NPRN: 289369

FFYNNONAU, BANK III BANK (EARTHWORK)

NGR: SO1857254578 Grid reference taken at point along linear site Altitude: 428

Period: Post Medieval? **Broadclass:** Monument <By Form>

Form: Earthwork **Condition:** D

Site Status:

Description: A very denuded field bank, one of several dividing up the former field system, NPRN 289370.

The bank, 2m wide but only 0.10m high, ran from SO1857254578 eastwards down to the common boundary. Although the feature can be seen aerial photographs it was only seen on the ground as recent cutting of the dead bracken had skimmed the top of the slightly raised

bank. J.J.Hall, Trysor, 13 March 2007

SMR PRN:

Relationships: Photographs:

Part of 289370

NPRN: 289370

FFYNNONAU, FIELD SYSTEM FIELD SYSTEM

NGR: SO1837054350 Grid reference taken at a central point within an extensive site Altitude: 435

Period: Post Medieval? Broadclass: Agriculture and Subsistence

Form: Complex **Condition:** D

Site Status:

Description: This denuded field system on the edge of the common, comprises field boundaries

NPRN289242, 289368 and 289369 and an area of cultivation NPRN 289371. It is visible on

RAF aerial photographs 106G/UK/1190/4133-4134. J.J.Hall, Trysor, 26 March 2007

SMR PRN:

Relationships: Photographs:

Consists of 289242 GC2007-045 21/02/2007 Field system, close up

Consists of 289369 GC2007-048 21/02/2007 Field system, looking southwest

Consists of 289368

FFYNNONAU, CULTIVATION RIDGES CULTIVATION RIDGE

NGR: SO1845954143 Grid reference taken at a central point within an extensive site Altitude: 413

Period: Post Medieval Broadclass: Agriculture and Subsistence

Form: Earthwork Condition: C

Site Status:

Description: An area of cultivation at the common edge, possibly associated with field system NPRN

289370. It is visible on RAF aerial photographs 106G/UK/1190/4133-4134. J.J.Hall, Trysor,

26 March 2007

SMR PRN:

Relationships: Photographs:

GC2007-039 21/02/2007 Northern part of cultivated area,

looking northwest

NPRN: 289372

COLVA HILL, CULTIVATION RIDGES CULTIVATION RIDGE

NGR: SO1924054250 Grid reference taken at a central point within an extensive site Altitude: 432

Period: Post Medieval? **Broadclass:** Agriculture and Subsistence

Form: Earthwork Condition: D

Site Status:

Description: An area of broad cultivation ridges on a level area of ground at the western edge of Colva Hill.

It is visible on RAF aerial photographs 106G/UK/1190/4133-4134. It may be associated with a

nearby pair of platforms (NPRNs 289205-289206). J.J.Hall, Trysor, 26 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 289373

LLYN Y WAUN, CULTIVATION RIDGES CULTIVATION RIDGE

NGR: SO1479054960 Grid reference taken at a central point within an extensive site Altitude: 492

Period: Post Medieval? **Broadclass:** Agriculture and Subsistence

Form: Earthwork Condition: D

Site Status:

Description: An area of ridge and furrow, at least 300m northeast-southwest by 70m. J.J.Hall, Trysor, 26

March 2007

SMR PRN:

PANT GLAS, CULTIVATION RIDGES CULTIVATION RIDGE

NGR: SO1857055860 Grid reference taken at a central point within an extensive site Altitude: 400

Period: Post Medieval? Broadclass: Agriculture and Subsistence

Form: Earthwork Condition: V

Site Status:

Description: An extensive area of cultivation ridges to the west and south of the enclosed field system,

NPRN 289340, at Pant Glas. J.J.Hall, Trysor, 26 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 306091

CWMCESTE, BARROW ROUND BARROW

NGR: SO1775655582 Grid reference taken at centre of site Altitude: 393

Period: Bronze Age Broadclass: Religious, Ritual and Funerary

Form: Earthwork Condition: C

Site Status:

Description: 1. A mound, 9.0m in diameter and 0.4m high. (source Os495card; SO15NE8). J.Wiles

22.08.02

2. A very denuded round barrow, now measuring 7m x 6.5m and only 0.25m high. It is

covered by grass and reeds. J.J.Hall, Trysor, 26 March 2007

SMR PRN: CPAT 1492

Relationships: Photographs:

GC2006-101 09/12/2006 Round barrow, looking west

LLANFIHANGEL HILL, BARROW

ROUND BARROW

NGR: SO1897755598 Grid reference taken at centre of site Altitude: 505

Period: Bronze Age Broadclass: Religious, Ritual and Funerary

Form: Earthwork Condition: C

Site Status: RD241

Description: 1. A centrally disturbed barrow or cairn, 26m by 28m and 1.8m high (source Os495card;

SO15NE26). J.Wiles 22.08.02

2. Remains of a round barrow situated on the summit of Llanfihangel Hill. The heather covered barrow is circular on plan and measures about 25m in diameter and up to 1.8m in height. Source: Cadw scheduling description. 07/10/2004/RCAHMW/FF

3. When the round barrow was visited in December 2006, its dimensions were as described above, based on the Cadw scheduling description. The top of the barrow had had several pits dug into. Most of these were grown over, but a larger one towards the north revealed unstructured stone. A trackway cut the northern most edge of the barrow. The feature was covered with Heather and grass. J.J. Hall, Trysor, 2 January 2007

SMR PRN: CPAT 2113

Relationships: Photographs:

GC2006-126 23/12/2006 Round barrow, showing interior

detail

GC2006-127 23/12/2006 Round barrow, interior detail GC2007-062 24/02/2007 Round barrow, looking

northeast

GC2007-063 24/02/2007 Round barrow, looking

southwest

395

NPRN: 306127

GELLI DYWYLLI, HOUSE PLATFORM I

BUILDING PLATFORM

NGR: SO14225282 Grid reference taken at centre of site Altitude:

Period: Medieval? Broadclass: Domestic

Form: Documents Condition: U

Site Status: RD168

Description: 1. One of a scattered group of house platforms on the S side of Little Hill, 10m by 4.0m,

mutilated. (source Os495card; SO15SW24). J.Wiles 23.08.02

2. RCAHMW recorded three platforms here previously, NPRN 306127, 306128 and 306129. When the area was visited during Uplands Survey in summer 2006, it was not possible to confidently correlate the three records with any of the platforms seen on the ground. Therefore the three original records have been left and new records created for all the platforms recorded

during fieldwork. J.J.Hall, Trysor, 26 March 2007

SMR PRN:

GELLI DYWYLLI, HOUSE PLATFORM II BUILDING PLATFORM

NGR: SO14265281 Grid reference taken at centre of site Altitude: 385

Period: Medieval? **Broadclass:** Domestic

Form: Documents Condition: U

Site Status: RD168

Description: 1. One of a scattered group of house platforms on the S side of Little Hill, 10m by 4.0m,

mutilated. (source Os495card; SO15SW24). J.Wiles 23.08.02

2. RCAHMW recorded three platforms here previously, NPRN 306127, 306128 and 306129. When the area was visited during Uplands Survey in summer 2006, it was not possible to confidently correlate the three records with any of the platforms seen on the ground. Therefore the three original records have been left and new records created for all the pltaforms recorded

during fieldwork. J.J.Hall, Trysor, 26 March 2007

SMR PRN:

Relationships: Photographs:

NPRN: 306129

GELLI DYWYLLI, HOUSE PLATFORM III BUILDING PLATFORM

NGR: SO14285283 Grid reference taken at centre of site Altitude: 385

Period:Medieval?Broadclass:DomesticForm:DocumentsCondition:U

Site Status: RD168

Description: 1. One of a scattered group of house platforms on the S side of Little Hill, 10m by 4.0m,

mutilated. (source Os495card; SO15SW24). J.Wiles 23.08.02

2. RCAHMW recorded three platforms here previously, NPRN 306127, 306128 and 306129. When the area was visited during Uplands Survey in summer 2006, it was not possible to confidently correlate the three records with any of the platforms seen on the ground. Therefore the three original records have been left and new records created for all the platforms recorded

during fieldwork. J.J.Hall, Trysor, 26 March 2007

SMR PRN:

GILWERN BROOK, BARROW I ROUN

ROUND BARROW

NGR: SO1851256144 Grid reference taken at centre of site Altitude: 366

Period: Bronze Age Broadclass: Religious, Ritual and Funerary

Form: Earthwork Condition: B

Site Status: RD242

Description: 1. One of a pair of barrows set in a valley bottom (see also NPRN 308023), 20m in diameter

and 0.6m to 1.5m high. (source OS495card; SO15NE6). J.Wiles 04.03.03

2. Remains of a round barrow, a burial mound probably dating to the Bronze Age, and situated in open moorland on a rounded spur above and to the south of a deep river gully. The heather covered barrow is circular on plan and measures about 20m in diameter and up to 1.5m in height. Source: Cadw scheduling description. 07/10/2004/RCAHMW/FF

3. When the round barrow was visited in December 2006, it was as described above based on the Cadw scheduling description. J.J. Hall, Trysor, 2 January 2007

SMR PRN: CPAT 1489

Relationships: Photographs:

GC2006-113 22/12/2006 Round barrow, looking

south-southeast

NPRN: 308023

GILWERN BROOK, BARROW II

ROUND BARROW

NGR: SO18515618 Grid reference taken at centre of site Altitude: 364

Period: Bronze Age **Broadclass:** Religious, Ritual and Funerary

Form: Earthwork Condition: C

Site Status:

Description: 1. One of a pair of barrows set in a valley bottom (see also NPRN 308021), 3.5m in diameter

and 0.45m high. (source OS495card; SO15NE6). J.Wiles 04.03.03

2. A small mound, probably a Bronze Age round barrow, 50m north of the larger round barrow, NPRN 1489. The feature is slightly irregular in shape but is roughly 3.5m in diameter and 0.45m high. When the round barrow was recorded in December 2006, it was covered in

long grass. J.J. Hall, Trysor, 2 January 2006

SMR PRN: CPAT 1490

Relationships: Photographs:

GC2006-114 22/12/2006 Round barrow, looking north