

**Phase 3
Proposed Ground-works**

Where indicated by blue hatch, allow for the removal of ground vegetation, including careful removal of any rooted systems. Should any artefacts or fallen stones be found these are to be recorded (found location & photography) and references and stored in a safe location. Contractor is to alert the architect/CA of any 'found' items. Clearance within these areas are to be undertaken under an archaeological watching brief.

Once vegetation has been removed, the surface of the areas is to be carefully raked over to create a level surface in preparation for membrane and gravel. Refer to NBS sections Q20 and Q23. Gravel sourced and laid to be Cotswold Path Gravel from Hills Quarry. Contact: Wilshire House, Country Park, Business Centre, Shrivensham Road, Swindon, SN1 2NR
Tel: 01793 714999
Email: info@hills-group.co.uk

Prior to any ground works commencing archaeological evaluation is required in the identified areas of ground works. This is to better design the level and requirement of filling material. A series of trial pits will be identified, say 4 locations, for the areas of archaeological investigations. The archaeologist will prepare a report confirming the information discovered during the ground works, which will be issued prior to any further works commencing.




Proposed protection to previously treated areas

Where indicated, allow for protection to areas previously treated with gravel. Following the conservation repairs and removal of scaffolding, allow for clearance of any debris and clear vegetation growth from this area.



Proposed Guardrails

Where indicated install 2 no 40mm square wrought iron bars to form guardrails within openings. Two bars are to be inserted, with the lowest bar 500mm from finished ground level, the second bar installed at 950mm from finished ground level. Prior to installing, levels are to be agreed with the architect to ensure that key architectural feature stones are not compromised. Please also refer to structural engineers details for details on anchoring back to the masonry.



Removal of Guardrails

Where indicated 2 no guardrails have been inserted. Allow for the removal of guardrails previously installed. Utilise previously installed rails for proposed new locations. Where guardrails have been removed, allow for filling holes with pinning stone and lime mortar.

Notes:
Drawings are based on survey data and may not accurately represent what is physically present.
Do not scale from this drawing. All dimensions are to be verified on site before proceeding with the work.
All dimensions are in millimeters unless noted otherwise.
Purcell shall be notified in writing of any discrepancies.

A	07/01/2020	AN	Contract issue
First Issue	20/04/18	AN	
ISSUE	DATE	DRAWN	CHECKED
			DESCRIPTION

CLIENT	Cadw Welsh Government's historic environment service
PROJECT	Neath Abbey - Tudor Mansion House Phase 3
DRAWING STATUS	CONTRACT

DRAWING TITLE	Ground Floor Plan Proposed groundworks and guardrails
SIZE & SCALE	A1 at 1:50

JOB NUMBER	237495/04
DRAWING NO.	202
REVISION	A

